

0045



STATE OF UTAH
NATURAL RESOURCES & ENERGY
Oil, Gas & Mining

Scott M. Matheson, Governor
Temple A. Reynolds, Executive Director
Cleon B. Feight, Division Director

4241 State Office Building • Salt Lake City, UT 84114 • 801-533-5771

March 22, 1983

Mr. R.A. Clawson
Utah Power & Light Company
1407 West North Temple
P.O. Box 899
Salt Lake City, Utah 84110

RE: Timing Delay of Construction
on the Truck Turn-around
Price River Coal Company Complex
ACT/007/004 ✓
Carbon County, Utah
Folder No. 3 & 4

Dear Mr. Clawson:

As you have amended the timing of your plan of operations, in the letter March 15, 1983, for the construction of the truck turn-around, no additional information is required. The proposal is acceptable and no problems should develop if the plans are implemented as described.

Please contact our office when the approved construction is completed. Thank you for keeping the Division informed.

Sincerely yours,

A handwritten signature in cursive script, appearing to read "Thomas N. Tetting".

THOMAS N. TETTING
ENGINEERING GEOLOGIST

TNT/gb

cc: Rob Wiley, PRCC
Ben Young, OSM Denver

Enclosure

UTAH POWER & LIGHT COMPANY

1407 WEST NORTH TEMPLE STREET

P. O. BOX 899

SALT LAKE CITY, UTAH 84110

March 15, 1983

Mr. Thomas N. Tetting
State of Utah
Division of Oil, Gas & Mining
4241 State Office Building
Salt Lake City, Utah 84114

Re: Modification to the Truck Turnaround
at the Price River Coal Co.
Your ACT/007/004
Carbon County, Utah

Dear Mr. Tetting:

Utah Power & Light Company requests deletion of your requirement specifying dredging or boundary expansion of Price River Coal Co. Pond 012. Pond modification was specified for material encroachment. As discussed verbally with Mr. T. Needs of this office, our request is based on the fact that replacement run-off ponds are under construction by Price River Coal Co. and that completion is scheduled during the week of March 21, 1983. These new ponds, per Mr. R. Wiley of Price River Coal Co., will collect all drainage at the scale area except for approximately one acre of surface drainage in the immediate truck turnaround area which will continue to drain into the old 012 Pond. Pond 012 capacity is estimated to be 1,400 cu. yds. With construction of the turnaround area, fill material encroachment will deposit approximately 335 cu. yds. and reduce the existing pond capacity to approximately 1,065 cu. yds. .66 ac - ft.

Please notify Utah Power & Light Company if the reduced 012 Pond capacity is acceptable for drainage of the truck turnaround area. With your approval, and after completion of the new Price River Coal Co. drainage ponds, we will start construction at the truck turnaround area.

Sincerely,



R. A. Clawson
Plant Projects Supervisor

RAC:TJN:cd

cc: R. Wiley

MAR 16 1983