0053

File
ACT/007/006
Copy to Shannon
Pam (enclosures, too!)

PLATEAU MINING COMPANY

A Subsidiary of Getty Mining Company
P.O. Drawer PMC Price, Utah 84501
Telephone (801) 637-2875

May 23, 1983

Ms. Pamela Grubaugh-Littig
Division of Oil, Gas and Mining
4241 State Office Bldg.
Salt Lake City, Utah 84114

RE: PLATEAU RECLAMATION BOND

Dear Pamela,

Enclosed, please find the corrections to the estimate for the Corner Canyon fan area. As we discussed on the phone, the bond estimate was changed to reflect the Corner Canyon Fan Application. The total bond estimate figure was not changed.

I have forwarded the bond information on to the appropriate Getty people to execute.

If you have any questions, please contact me.

Sincerely,

PLATEAU MINING COMPANY

Ben Grimes
Environmental Coordinator

BG/lm

Enclosure

RECEIVED
MAY 25 1983
DIVISION OF
OIL, GAS & MINING

SUMMARY

AREA DESCRIPTION	NO. OF ACRES	CONCRETE AND/OR BLACKTOP REMOVAL	BACK-FILLING	GRADING	RIPPING	TOPSOIL SPREADING	SOIL ADDITIVES	SEEDING AND TREE PLANTING	MOISTURE RETENTION	MAINTENANCE AND MONITORING	BUILDING AND STRUCTURE REMOVAL	TOTAL
AREA 1 Lower Operations	125.0	64,130	38,990	8,470	83,500	229,000	43,750	75,000	150,000	150,000	143,671	986,511
2 No. 1 Mine	11.3	6,270	28,900	19,210	22,250	28,250	3,955	6,780	13,560	13,560	8,421	151,156
3 No. 2 Mine	5.7	100	7,500	9,690	14,250	14,250	1,995	3,420	6,840	6,840	910	65,795
4 Lion Portal	12.5	55,704	36,970	21,250	21,250	31,250	4,375	7,500	15,000	15,000	67,622	276,171
5 Mud Water Fan	1.7	1,300	32,500	2,890		4,250	595	1,020	2,040	2,040	11,179	57,814
6 Corner Canyon Fan	0.4	420	29,520	760		1,200	160	280	480	520	2,850	36,190
7 Road	2.4	34,848		4,080		6,000	840	1,440	2,880	2,880		52,968
8 Road	15.8	47,916		26,860		39,500	5,530	9,480	18,960	18,960		167,206
9 Road	5.0			8,500		12,500	1,750	3,000	6,000	6,000		37,750
10 Road	32.9	90,024		55,930		82,250	11,515	19,740	39,480	39,480		338,419
11 Road	2.4			4,080		6,000	840	1,440	2,880	2,880		18,120
12 Old Tram Road	2.2			3,740		5,500	770	1,320	2,640	2,640		16,610
TOTAL	217.3	300,712	173,910	165,380	141,500	459,750	76,055	130,380	260,760	260,760	235,495	2,204,702

AREA DESCRIPTION	NO. OF ACRES	CONCRETE AND/OR BLACKTOP REMOVAL	BACK-FILLING	GRADING	RIPPING	TOPSOIL SPREADING	SOIL ADDITIVES	SEEDING AND TREE PLANTING	MOISTURE RETENTION	MAINTENANCE AND MONITORING	BUILDING AND STRUCTURE REMOVAL	TOTAL
AREA 4 (cont.)												
Oil Storage Structure		100									2,640	2,740
Substation		100									300	400
Power Poles & Lines											5,000	5,000
Structural Steel											13,640	13,640
SUB TOTAL AREA 4	12.5	55,704	36,970	21,250	21,500	31,250	4,375	7,500	15,000	15,000	67,622	276,171
AREA 5 MUDWATER FAN AREA												
Operations	1.7		20,000	2,890		4,250	595	1,020	2,040	2,040		32,835
Portals 5 ea. (seals)			12,500									12,500
Ventilation Fan		1,300									1,023	2,323
Substation											156	156
Power Roads & Line											10,000	10,000
SUB TOTAL AREA 5	1.7	1,300	32,500	2,890		4,250	595	1,020	2,040	2,040	11,179	57,814
AREA 6 CORNER CANYON FAN AREA												
Operations	0.4		23,520	760		1,200	160	280	480	520		26,920
Ventilation Fan		420									1,750	2,170
Portals 3 ea. (seals)			6,000									6,000
Steel/Fence											1,100	1,100
SUB TOTAL AREA 6	0.4	420	29,520	760		1,200	160	280	480	520	2,850	36,190