STATE OF UTAH
NATURAL RESOURCES
Oil, Gas & Mining

Scott M. Matheson, Governor
Temple A. Reynolds, Executive Director
Dianne R. Nielson, Ph.D., Division Director

4241 State Office Building • Salt Lake City, UT 84114 • 801-533-5771

August 2, 1984

Mr. Ben Grimes
Plateau Mining Company
P. O. Drawer PMC
Price, Utah 84501

Dear Mr. Grimes:

RE: Approval of "As Built" Runoff and Sedimentation Control Plan Modifications, Starpoint Mines, Plateau Mining Company, ACT/007/006, Folder 2, 3, and 4, Carbon County, Utah

The Division's technical staff has reviewed the "As Built" Runoff and Sediment Control Plan" for the Star Point Mines received by the Division January 23, 1984, as well as, the July 10, 1984 Modification Plans for Diversions 16 and 18. Based on that review the Division hereby grants approval to the following modifications to the approved runoff control plan:

- Installation of the 54" half-round CMP culvert in Ditch No. 14.
- Installation of the 12" CMP culvert, associated with Ditch No. 18 under the railroad tracks, plus the construction of Ditches 18A, 18B, and 18C.
- Installation of the 14" CMP culvert associated with Ditch No. 16, under the truck crossing to the coal stockpile and refuse area.
- Construction of Diversion Ditch No. 25.
- Lining of Ditches No. 4, 5, 6A, 6B, 11, 12, 15 and 20.

The Division cannot approve modifications to Sediment Ponds 4, 5 and 6 until Plateau Mining Company submits the requested information regarding design of the outlet works for the ponds and it has been reviewed by the Division and determined to be adequate. Also, Sediment Pond No. 2 and the replacement treatment facility cannot be approved until certified design plans with accompanying details (i.e. elevation-capacity curve, cross-sections of the spillway and dewatering structures, and plan view of the facility) are received, reviewed and determined to be adequate.

All information for these ponds should be dated and submitted to the Division in a format that can be inserted directly into the appropriate section of the existing Mining and Reclamation Plan following approval.

Please call me or Tom Suckhoski if you have any questions.

Sincerely,

D. Wayne Hedberg

D. Wayne Hedberg
Permit Supervisor/
Reclamation Hydrologist

DWH/TJS:jvb

cc: Robert Hagen, OSM
Allen Klein, OSM
Jim Smith, DOGM
Joe Helfrich, DOGM
Sue Linner, DOGM
Dave Lof, DOGM
Tom Suchoski, DOGM
94590-20