0022

ACT/007/006
#2

CYPRUS
Plateau Mining

Cyprus Plateau Mining Corporation
P.O. Drawer PMC
Price, Utah 84501
(801) 637-2875

July 26, 1989

RECEIVED
JUL 28 1989
DIV. OF OIL, GAS & MINING

Mr. Tom Munson
Utah Department of Natural Resources
Division of Oil, Gas and Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, UT 84180-1203

Re: Inlet Protection Culverts 7F and 6B, Additional Copies of Culvert 6B Design and Ditch 7G and Culvert 7G Designs

Dear Mr. Munson:

In confirmation of our phone conversation today, I am enclosing three additional copies of the designs for Culvert 6B, Ditch 7G, and Culvert 7G.

You said Bob Lauman's letter dated July 21, 1989, was adequate to document inlet protection at Culvert 6B. A similar treatment will be made at Culvert 7F; rock with a mean diameter of 0.5 feet will be placed in the channel at the inlet for a distance of 10 feet upstream. A trash rack constructed of 1/2 inch diameter rebar or 5/8 inch roof bolts will be placed at the inlet end of the culvert.

Construction of the new Ditch 7G and Culvert 7G will be completed within 30 days of receipt of approval of the design from the Division.

I suggest adding these amendments as a new exhibit (Exhibit 54) along with my June 15, 1989, submittal. Six copies of the List of Exhibits page showing this addition are enclosed.

Six copies of this letter are enclosed for insertion in PAP sets. If you need anything further, give me a call.

Respectfully,

Ben Grimes
Sr. Environmental Engineer

/kam

Enclosures

Chrono: BG890703

File: ENV 2-5-2-12