SCA PERMIT AREA
PERMIT C/007/042
NOVEMBER, 2003

AREAS WHERE POCKETS OF COAL REFUSE WERE LEFT IN-PLACE AND COVERED WITH A MINIMUM OF 4' OF SOIL

PHILLIPS UTILITY CORRIDOR.
PHASE III BOND RELEASE
DECEMBER, 2003

SOURCE OF TOPSOIL TO COVER POCKETS OF COAL REFUSE LEFT IN-PLACE IN THE FACILITIES AREA (APPROX. 13,300 CY)

WELL NO. 10-526

WELL NO. 10-525

SPRD-40
SPRD-47a
SPRD-49
SPRD-31
SPRD-47
SPRD-31
SPRD-48
SPRD-30
SPRD-29b
SPRD-46
SPRD-29a
SPRD-26a
SPRD-26
SPRD-28
SPRD-26
SPRD-27
SPRD-31
SPRC-22
SPRD-24
SPRD-22a
SPRD-33
SPRD-35
SPRD-35a
SPRD-36a

SCA PERMIT AREA
PERMIT C/007/042
NOVEMBER, 2003

N437,000
N436,000
N435,000
N434,000
E2,135,000
E2,136,000
E2,137,000
E2,138,000
E2,139,000
E2,140,000
E2,141,000

LEGEND

- PRIMARY ROAD
- SECONDARY ROAD
- TRAIL
- BRIDGE, CULVERT
- RAILROAD
- BUILDINGS, STRUCTURES
- LAKE, POND
- RIVER, STREAM
- FENCE
- ASBUILT CONTOURS
- TREE LINES
- RECLAMATION DISTURBED AREA BOUNDARY
- CROSS SECTION
- PERMIT BOUNDARY
- PHILLIPS GAS WELLS AND UTILITY CORRIDOR (11.77 ACRES POST MINING LAND USE CHANGE AND PHASE III BOND RELEASED IN DECEMBER 2003)
- SECTION CORNER
- PARTIALLY BACKFILLED PRE-SMCRA CUTSLOPE
- SCA PERMIT BOUNDARY AND PERMIT C/007/042 NOVEMBER, 2003
- RECLAMATION CHANNEL
- DEEP GOUGED SURFACE (HAY AND STRAW MULCH) LAST AUGMENTED SEEDING FALL 2002

NOTES:

1. PHASE 1 BOND RELEASE FOR 93.77 ACRES.
2. BACKFILL, GRADING AND GROWTH MEDIA/TOPSOIL PLACEMENT FOR THE MINE #1 AND MINE #2 AREAS BEGAN IN AUGUST, 2001 AND WERE COMPLETED IN DECEMBER, 2001. GROWTH MEDIA/TOPSOIL PLACEMENT OCCURRED CONCURRENTLY WITH BACKFILLING AND GRADING AS AREAS ACHIEVED FINAL GRADE.
3. BACKFILL, GRADING AND GROWTH MEDIA/TOPSOIL PLACEMENT FOR THE LOADOUT AREA BEGAN IN SEPTEMBER, 2001 AND WERE COMPLETED IN DECEMBER, 2001. GROWTH MEDIA/TOPSOIL PLACEMENT OCCURRED CONCURRENTLY WITH BACKFILLING AND GRADING AS AREAS ACHIEVED FINAL GRADE.
4. ALL EXCESS COAL REFUSE FROM THE MAIN CHANNEL AREA, NOT USED AS BACKFILL, WAS PLACED ON THE REFUSE PILE.
5. TOWNSHIP 15 SOUTH, RANGE 8 EAST.

NORTH

200' 100' 0 200'

FILE: G:\UC779\07\DWG\542200C-AB\ 08-08-03

REGISTERED PROFESSIONAL ENGINEER
No. 189797
LAYNE D. JENSEN
6-25-04
NOT VALID WITHOUT A SIGNATURE
STATE OF UTAH

RAG

REVISION/HISTORY

BY	DATE	DESCRIPTION
LDJ	10-10-03	AS-BUILT
1		
LDJ	02-05-04	RESPOND TO TA COMMENTS
2		
3		
4		
5		
6		

STARPOINT MINE

AS-BUILT RECLAMATION TOPOGRAPHY AND TREATMENT MAP

SHEET 3

RECEIVED
JUL 21 2004
DIV. OF OIL, GAS & MINING

PLATEAU MINING CORPORATION
847 NW HIGHWAY 191 HELPER, UTAH 84526
PHONE: (435) 472-0475

MAP 542.200c