

UtahAmerican Energy, Inc.



C/007/013  
Lila Canyon Project  
P. O. Box 910  
East Carbon, Utah 84501  
Phone: (435) 888-4000  
(435) 650-3157  
Fax: (435) 888-4002  
Incoming  
# 4453  
R

November 21, 2013

Daron Haddock  
Permit Supervisor  
1594 West North Temple, Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801



Re: UtahAmerican Energy, Inc. Lila Canyon Mine, ACT/009-013, Mid-Term Review,  
Task ID #4406, (L13-003)

Dear Mr. Haddock:

Please find attached three (3) copies of the Response to Mid-Term Review.

The C1 and C2 forms as well as Red Line Strikeouts are included.

If you have any questions please give me a call.

Sincerely,

*R. Jay Marshall*  
R. Jay Marshall P.E.  
Project Manager / Chief Engineer  
Lila Canyon Mine

DIV. OF OIL, GAS & MINING

NOV 22 2013

RECEIVED

# APPLICATION FOR PERMIT PROCESSING

<input type="checkbox"/> Change	<input type="checkbox"/> New Permit	<input type="checkbox"/> Renewal	<input type="checkbox"/> Transfer	<input type="checkbox"/> Exploration	<input type="checkbox"/> Bond Release	Permit Number: ACT/007/013
Title of Proposal: Mid Term Review (13-003)						Mine: Horse Canyon
						Permittee: UtahAmerican Energy, Inc.

Description, include reason for application and timing required to implement:

**Instructions:** If you answer yes to any of the first 8 questions (gray), submit the application to the Salt Lake Office. Otherwise, you may submit it to your reclamation


<input type="checkbox"/> Yes	<input type="checkbox"/> No	1. Change in the size of the Permit Area? _____ acres Disturbed Area? _____ acres <input type="checkbox"/> increase <input type="checkbox"/> decrease.
<input type="checkbox"/> Yes	<input type="checkbox"/> No	2. Is the application submitted as a result of a Division Order? DO # _____
<input type="checkbox"/> Yes	<input type="checkbox"/> No	3. Does application include operations outside a previously identified Cumulative Hydrologic Impact Area?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	4. Does application include operations in hydrologic basins other than as currently approved?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	5. Does application result from cancellation, reduction or increase of insurance or reclamation bond?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	6. Does the application require or include public notice/publication?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	7. Does the application require or include ownership, control, right-of-entry, or compliance information?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	8. Is proposed activity within 100 feet of a public road or cemetery or 300 feet of an occupied dwelling?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	9. Is the application submitted as a result of a Violation? NOV # _____
<input type="checkbox"/> Yes	<input type="checkbox"/> No	10. Is the application submitted as a result of other laws or regulations or policies? Explain: <b>Mid Term Review</b>
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	11. Does the application affect the surface landowner or change the post mining land use?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	12. Does the application require or include underground design or mine sequence and timing? (Modification of R2P2?)
<input type="checkbox"/> Yes	<input type="checkbox"/> No	13. Does the application require or include collection and reporting of any baseline information?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	14. Could the application have any effect on wildlife or vegetation outside the current disturbed area?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	15. Does application require or include soil removal, storage or placement?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	16. Does the application require or include vegetation monitoring, removal or revegetation activities?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	17. Does the application require or include construction, modification, or removal of surface facilities?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	18. Does the application require or include water monitoring, sediment or drainage control measures?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	19. Does the application require or include certified designs, maps, or calculations?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	20. Does the application require or include subsidence control or monitoring?
<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	21. Have reclamation costs for bonding been provided for?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	22. Does application involve a perennial stream, a stream buffer zone or discharges to a stream?
<input type="checkbox"/> Yes	<input type="checkbox"/> No	23. Does the application affect permits issued by other agencies or permits issued to other entities?

**X Attach 3 complete copies of the application.**

I hereby certify that I am a responsible official of the applicant and that the information contained in this application is true and correct to the best of my information and belief in all respects with the laws of Utah in reference to commitments, undertakings, and obligations, herein.

  
 Signed - Name - Position - Date  
 \_\_\_\_\_ 11/18/13

Subscribed and sworn to before me this 18<sup>th</sup> day of November, 2013

  
 Notary Public  
 My Commission Expires: 3.27.17



Attest: \_\_\_\_\_ ) ss:

Received by Oil, Gas & Mining  
  
 NOV 22 2013  
  
 DIV. OF OIL, GAS & MINING  
 DIV. OF OIL, GAS & MINING  
 ING

ASSIGNED TRACKING NUMBER

## Application for Permit Processing Detailed Schedule of Changes to the MRP

Mid Term Review (13-003) deficiencies      TASK ID#4406

Permit Number: ACT/007/013

Mine: Horse Canyon

Permittee: UtahAmerican Energy, Inc.

Provide a detailed listing of all changes to the mining and reclamation plan which will be required as a result of this proposed permit application. Individually list all maps and drawings which are to be added, replaced, or removed from the plan. Include changes of the table of contents, section of the plan, pages, or other information as needed to specifically locate, identify and revise the existing mining and reclamation plan. **Include page, section and drawing numbers as part of the description.**

	DESCRIPTION OF MAP, TEXT, OR MATERIALS TO BE CHANGED		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE	Plate 1-2 with new Plate 1-2		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE	Plates 2-2 and 2-3 with new Plates 2-2 and 2-3		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE	Plates 5-2 and 5-6 with new Plates 5-2 and 5-6		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE	Plates 7-2, 7-5, and 7-7 with new Plates 7-2, 7-5, and 7-7		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE	Chapter 3 Text with new Pages 10, 13, 20 to end		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE	Chapter 7 Text Pages 56-67 with new Pages 56-67		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE	Chapter 8 Appendix 8-1 with new Appendix 8-1 (All)		
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			
<input type="checkbox"/> ADD <input type="checkbox"/> REPLACE <input type="checkbox"/> REMOVE			

Any other specific or special instructions required for insertion of this proposal into the Mining and Reclamation Plan?

RECEIVED

NOV 22 2013

DIV. OF OIL, GAS & MINING

**Response to Mid-Term Deficiencies**  
**Lila Canyon Mine**  
**December 4, 2013**

**Reclamation Plan**  
**Bonding**

**R645-301-830.140** The Permittee must update the unit costs used to develop the 2008 reclamation cost estimate using 2013 R.S. Means unit costs from their Heavy Construction Data manual. That total, including direct and indirect costs, must be escalated to 2018 using the current 2013 escalation factor of 1.5% to determine the bond amount required to be maintained to keep the Lila Canyon Mine in compliance.

*Unit costs for all sections, Demolition, Earthwork and Reclamation, have been revised using the R.S. Means Heavy Construction Data Manual online for 2013 Quarter 3. All line item numbers were updated from the 1995 master format to the 2010 master format. The labor type used was open shop and the location used was Price, Utah.*

**Operation Plan**

**HABITAT ENHANCEMENT AND MITIGATION**

**R646-301-322, 301-333, 301-342, 301-358** According to the text on page 10, Chapter 3 the eagle nests were to be mitigated by a prey base off-site vegetation treatment project with a reference to page 19. The reference needs to be corrected to pages 11, 17 and 18. The vegetation treatment is scheduled to be completed in the fall of 2013.

*Page 20 of Chapter 3 has been revised to reference pages 11, 17, and 18.*

**RAPTOR AND NEST PROTECTION**

For possible subsidence impacts to raptor nests, the Permittee will develop a mitigation plan, that must be submitted and approved within 6 months after issuance of permit and apply for take permit through USFWS 2 years prior to subsidence of the nests. The mitigation is scheduled to be completed in the Fall of 2013. The permittee needs to identify which nests are being referred to (previously identified or from future surveys). If nests are identified through aerial surveys the permittee us apply for taker permit through USFWS 2 years prior to subsidence of the nests.

*The nests that are referred to in the mitigation plan are nests 456 and 946. The text in chapter 3 page 10 has been revised to identify the nests referred to in the mitigation plan by number. The only nest within the subsidence zone is nest #719, which can no longer be found.*

### **RAPTOR PROTECTION**

Employee education to remove road kill from the coal haul road. Ongoing, the permittee needs to correct the pagination error that begins on page 20. The employee awareness program should include annual training and as needed as well as text that describes the removal of animal carcasses.

*The pagination error beginning on page 20 of Chapter 3 has been corrected. The employee environmental awareness program does include annual training that addresses the removal of animal carcasses.*

Escarpment barrier of at least 200' to prevent cliff habitat loss. The text of Chapter three, page 13, Section 332 (1) needs to be revised for clarified to demonstrate how the 200' barrier will be measured.

*Chapter three page 13 has been revised to clarify that the escarpment barrier is measured from the coal outcrop.*

### **SEED MIX TAGS**

Provide the division biologist with seed mix tags prior to or during interim, contemporaneous, and final reclamation projects. The division is recommending that the topsoil pile and disturbed areas not being utilized for mining activities be scarified and seeded in the Fall of 2013 to minimize the current infestation of halogeton. Seed tags should be provided to the inspector.

*Seed tags describing the seed used for interim, contemporaneous and final reclamation projects will be provided to the inspector.*

### **VEGETATION TEST PLOT**

To test whiter summer seeding will increase establishment of the warm season species (blue gramma and galleta). Area 1 and 4 were seeded in July and area 2 and 3 were seeded in October following construction. The Division needs to meet with the permittee in the Spring of 2014 to visit the test plot areas and discuss the information provided in the 2012 annual report to determine what recommendation should be made regarding the warm season seeding of blue gramma and galleta spp.

*The operator will meet with the Division to visit the test plots in the spring of 2014 whenever the Division would like to schedule the meeting. The Division will notify the operator of the scheduled meeting.*

### **NOXIOUS WEED CONTROL**

To control invasive species in and adjacent to the disturbed area. The permittee should

implement a noxious/invasive species weed control program. The Division is recommending that this commitment be added to the Lila Canyon MRP list of commitments. The regulatory basis is found at R645-301-357.320-324. The permittee needs to address the current infestation of halogeton and Russian thistle. In these areas. The Division has recommended scarifying and seeding in the Fall of 2013 and spraying based on a site inspection in the Spring of 2014.

*The operator will scarify and reseed the area North of the topsoil pile in the fall of 2013. The area will be inspected in the Spring of 2014.*

#### **TOPSOIL AND SUBSOIL**

**R645-301-251.** The phased construction plan should not preclude follow through on statement in Section 234.230 that the topsoil stockpile will have an irregular, pitted surface and will be mulched and seeded (and treated with inoculum) and have a silt fence at the base. The south half of the topsoil requires final treatment as soon as possible, regardless of the progress of construction. The Division requests that the MRP include a deadline for completion of topsoil pile construction and that the deadline be set for late fall (late November - mid December) 2014.

*The operator will grade, pock, mulch and reseed the south end of the topsoil pile as discussed with DOGM. The previously mentioned work will be done in the fall of 2013.*

*At this time UEI cannot set a deadline for the completion of Phase II and the final topsoil construction. The completion of Phase II depends completely upon the coal market and the need for the coal to fill existing contracts. At this time the MRP will not be revised to reflect arbitrary deadlines that the operator cannot committed to.*

#### **HYDROLOGIC GENERAL**

r645-301-700-731.214 The MRP should be updated in the following sections to more clearly define the current water monitoring plan:

Page 56 of Chapter 7 should be updated to reflect the current monitoring plan for Quaker Spring now that baseline data collection has been completed.

*Chapter 7 Page 56 has been revised to reflect the current monitoring plan for Quaker Spring.*

Section 731.224.2 should be updated to clarify which sites are temporarily suspended.

*Section 731.224.2 has been revised to reference Table 7-3 which should clarify which sites are temporarily suspended.*

Table 7-3 should be updated to indicate the current water monitoring plan for Quaker Spring.

*Table 7-3 has been updated to indicate the current water monitoring plan for Quaker Spring.*

#### **MAPS FACILITIES**

**R645-301-121.100** Plate 5-2 should reflect current site conditions with regard to shading of the disturbed area within the permit boundary. Placement of an aerial photo laid over the Plate 5-2 design would enable distinction between existing conditions and future approved construction depicted on the map.

*An aerial phot was laid over Plate 5-2 to help distinguish between existing and future approved conditions. While correcting plate 5-2 the operator also corrected the following plates to accurately show the permit boundary and the areas of undisturbed within the disturbed. Plates 1-2, 2-2, 2-3, 5-2, 5-6, 7-2, 7-5, and 7-7.*

mitigated and is defined in the Environmental Assessment submitted in association with the Right-Of-Way applications.

The USFWS recognizes that the permit area is within range of endangered species, including the black-footed ferret, MSO, and the bald eagle (Letter dated February 4, 1998, Appendix 3-3).

Raptor surveys were initiated in 1998 and continue annually with the exception of 2004. These surveys were initiated before ground-breaking of the Lila project. The results of these surveys are in Appendix 3-5. The entire Book Cliffs escarpment within the permit area was inventoried for cliff nesting raptors. In addition, a 1-mile buffer zone was inventoried around areas of potential development.

An active golden eagle nest, (456) with possible young, was documented during the 1999 spring raptor survey. In 2005 nest 946 contained a chick that was possibly dead. USFWS, Laura Roma, UDWR, Chris Colt, and BLM, Dave Mills determined, during the EA process, that there was a high probability these nest sites would be abandoned. A cooperative agreement with the regulatory agencies and UEI was finalized and is made part of the mitigation for the Lila Canyon EA. One nest discussed above, also lies in an area of potential subsidence which is a mute point due to its close proximity to the mine site. Since the nests are located so close to the mine surface facility and that there was a high probability these nest sites would be abandoned, these nests will be mitigated by a prey base off-site vegetation treatment project approved by the USFWS, UDWR and BLM (See page ~~19~~s 11, 17, and 18 for BLM mitigation information).

Although it was predicted that these nests might be abandoned, the Operator will coordinate closely with USFWS, DWR, and the Division to avoid "take" of golden eagles prior to

discharge and for the mine discharge and have a habitat consisting of an overstory of piñon-juniper.

**330. Operation Plan.** A plan for protection of vegetation, fish and wildlife resources follows:

**331.** The Lila permit area is approximately 4664.32 acres of which only 42.6 acres are within the surface disturbance area. All incidental disturbance, which will not be utilized in operations, will be revegetated with an interim seed mix proven beneficial to wildlife. The revegetation plan is addressed in Section 341 and the seed mixes are addressed in Tables 3-4 and 3-5. Revegetation will occur the first desirable period following disturbance and/or abandonment.

**332.** The extent and degree of subsidence will be in large dependent on both the amount of overburden as well as the mining method. Employees and or consultants of the operator have numerous years of experience mining the Bookcliffs and Wasatch areas and none have observed nor are aware of any negative impacts on wildlife or vegetation, as a result of subsidence, with the exception of

- 1) Escarpment Failure which is not anticipated.
  - 2) Disruption of Surface and / or Ground Water, which is not anticipated.
- (1) Escarpments will be protected by implementing escarpment barriers. An escarpment barrier of a minimum of 200' from the outcrop, within which no second mining will take place, will be used to protect escarpments immediately above the coal seam and protect against unplanned holeouts.
  - (2) Disturbance of Surface and / or Ground Water. Considering, the permit area has no surface water with the exception of intermittent or ephemeral flow associated with precipitation events and / or snow melt, subsidence should have no adverse effect. The ephemeral stream channels, in the area's of potential subsidence, will be monitored to insure there are no adverse impacts to the ephemeral flow.

No negative impacts to vegetation are anticipated. However, vegetation will be monitored in conjunction with subsidence monitoring, utilizing infrared aerial photography once every five

mitigated and is defined in the Environmental Assessment submitted in association with the Right-Of-Way applications.

The USFWS recognizes that the permit area is within range of endangered species, including the black-footed ferret, MSO, and the bald eagle (Letter dated February 4, 1998, Appendix 3-3).

Raptor surveys were initiated in 1998 and continue annually with the exception of 2004. These surveys were initiated before ground-breaking of the Lila project. The results of these surveys are in Appendix 3-5. The entire Book Cliffs escarpment within the permit area was inventoried for cliff nesting raptors. In addition, a 1-mile buffer zone was inventoried around areas of potential development.

An active golden eagle nest, (456) with possible young, was documented during the 1999 spring raptor survey. In 2005 nest 946 contained a chick that was possibly dead. USFWS, Laura Roma, UDWR, Chris Colt, and BLM, Dave Mills determined, during the EA process, that there was a high probability these nest sites would be abandoned. A cooperative agreement with the regulatory agencies and UEI was finalized and is made part of the mitigation for the Lila Canyon EA. One nest discussed above, also lies in an area of potential subsidence which is a mute point due to its close proximity to the mine site. Since the nests are located so close to the mine surface facility and that there was a high probability these nest sites would be abandoned, these nests will be mitigated by a prey base off-site vegetation treatment project approved by the USFWS, UDWR and BLM (See pages 11, 17, and 18 for BLM mitigation information).

Although it was predicted that these nests might be abandoned, the Operator will coordinate closely with USFWS, DWR, and the Division to avoid "take" of golden eagles prior to

discharge and for the mine discharge and have a habitat consisting of an overstory of pinion-juniper.

**330. Operation Plan.** A plan for protection of vegetation, fish and wildlife resources follows:

**331.** The Lila permit area is approximately 4664.32 acres of which only 42.6 acres are within the surface disturbance area. All incidental disturbance, which will not be utilized in operations, will be revegetated with an interim seed mix proven beneficial to wildlife. The revegetation plan is addressed in Section 341 and the seed mixes are addressed in Tables 3-4 and 3-5. Revegetation will occur the first desirable period following disturbance and/or abandonment.

**332.** The extent and degree of subsidence will be in large dependent on both the amount of overburden as well as the mining method. Employees and or consultants of the operator have numerous years of experience mining the Bookcliffs and Wasatch areas and none have observed nor are aware of any negative impacts on wildlife or vegetation, as a result of subsidence, with the exception of

- 1) Escarpment Failure which is not anticipated.
  - 2) Disruption of Surface and / or Ground Water, which is not anticipated.
- (1) Escarpments will be protected by implementing escarpment barriers. An escarpment barrier of a minimum of 200' from the outcrop, within which no second mining will take place, will be used to protect escarpments immediately above the coal seam and protect against unplanned holeouts.
- (2) Disturbance of Surface and / or Ground Water. Considering, the permit area has no surface water with the exception of intermittent or ephemeral flow associated with precipitation events and / or snow melt, subsidence should have no adverse effect. The ephemeral stream channels, in the area's of potential subsidence, will be monitored to insure there are no adverse impacts to the ephemeral flow.

No negative impacts to vegetation are anticipated. However, vegetation will be monitored in conjunction with subsidence monitoring, utilizing infrared aerial photography once every five

Permittee to conduct activity near or within the 0.5 mile buffer zone of raptor nest and during raptor exclusionary periods (February 1 to July 15 for golden eagles), the Permittee will immediately contact the Division, BLM, DWR, and USFWS. The agencies will immediately coordinate to determine appropriate measures that may include conducting ground surveys, in coordination with DWR, to determine if birds are tending nests or nesting and possibly determine the life stage of the offspring; developing a mitigation plan, in coordination with the agencies, for possible impacts to nests or birds; or ceasing operations until the end of breeding season to avoid 'take'. If the agencies recommend surveys, the Permittee must submit all survey results to the Division in Annual Reports. If the agencies recommend mitigation, the Permittee must submit all mitigation plans to the Division for incorporation into Appendix 3 of the MRP.

The Applicant does not plan to monitor any wildlife species during the life of the operation with the exception of raptors. Spring raptor surveys will be conducted at a minimum of a 1-mile radius around any new or potentially disruptive mining activity, 2-years prior and annually after the proposed activity. The Operator will contact the USFWS and the Division immediately following raptor surveys if raptors are observed tending nests or nesting.

The mine will emphasize their commitment to legal requirements of firearm and off-road vehicle-use by employees. This type of program has been adopted by the operator and will continue throughout the operation. An education program aimed at minimizing potential negative impacts by employees will be presented during the Operators annual retaining programs. Employees will be informed about the wildlife in the area and about which species are protected. They will be counseled to refrain from poaching or harassing animals and about the need to

preserve the wildlife. They will also be instructed on the danger of animals on the road during dusk and night hours and consequently the need to reduce speed to avoid colliding with animals difficult to see in these periods of poor light. All threatened or endangered wildlife sighted within or adjacent to the permit area will be reported to the appropriate state and / or federal agency.

The location and construction of the haulage road, as well as measures for the protection of surface hydrology, from sedimentation, including the sedimentation pond and other drainage control structures, are discussed in Chapter 7, Hydrology.

Any waters discharged from the facility will be monitored in accordance with UPDES Permit No.UTG040024. Major disturbances will be scheduled to avoid deer / antelope fawning times.

No use of pesticides or chemicals that have serious consequences to plants or wildlife will be used on the permit area, unless recommended by a regulatory agency and under their direction.

Prevention of fires and their spreading outside the permit area will be accomplished through; water sprays, and fire extinguishers located at all facilities . Wild fires will be addressed by the appropriate state and federal agencies. Operation and reclamation activities will be done in compliance with the Endangered Species Act of 1973. As instructed by the Bureau of land Management and the Utah Division of Wildlife Resources, fencing will be removed when DOGM determines that all reclamation standards have been met. Further measures taken to enhance wildlife habitat during reclamation are discussed under the "Reclamation Plans" section of this chapter.

The interim reseeding of small areas will provide some small amounts of additional forage and

seed. Reseeding will particularly benefit rodents and passerine birds seeking seeds in this sparse vegetative type. The seeding of sediment pond slopes usually provides a bonus crop of seeds as the plants are watered by intermittent runoff.

Within the disturbed area, there are areas of undisturbed ground such as in topsoil storage areas. These areas will be posted so as to preclude trespass by vehicles and/or mine equipment. In addition, dust control will be practiced throughout the life of the mine to minimize impacts from blowing dust .

The sediment pond on the disturbed area will hold water during short periods and will provide some additional surface water for wildlife. The stored water may prolong use of that portion of the winter range by deer because water is often the limiting factor on dry winter ranges. Migrating small birds and mourning doves will also utilize this water to recuperate during their flights, as well as a small indigenous flock of chukkers. In the event the water in the pond were to contain any material which would be hazardous to wildlife (ex: oil, grease), the material would be removed by the use of petroleum selected filtration material. The filtration material will be used when an apparent sheen is visible on the pond. If hazardous materials are observed the Division will be notified immediately to develop a protection plan for wildlife. The pond will be monitored visually daily by surface personnel for signs of oil and grease.

#### **340. Reclamation Plan.**

A reclamation plan for final revegetation is presented below.

- 341.100.** TABLE 3-3 is a timetable of reclamation activities upon cessation of operation. The tentative life of a mine is twenty years depending on market and mining conditions. As such, the time table is generic and no set year will be specified for the cessation and

abandonment of operations.

**341.200.** This section is addressed in 341.210.

**341.210.** TABLE 3-4 indicates the species and amounts per acre of seeds to be used in revegetation.

The seed mixture used to revegetate the disturbed areas at Lila Canyon Mine is given on TABLE 3-4, along with the rates of application. The seed mixture was developed for the disturbed area with respect to a number of considerations. Climatic conditions of area and the availability of water were reviewed to assess the need for drought-tolerant species. The vegetation information was evaluated to determine the seed mixture needs corresponding to productivity, cover and diversity requirements. Data was gleaned from the soils report to select species adapted to the physical and chemical characteristics of the potential seedbed.

**341.220.** The disturbed area will be reclaimed after all operations have ceased at the mine site and all pertinent structures have been removed. The coal will be loaded out and the surface will be left relatively free of debris. The area will be recontoured to approximate pre-mine configurations. The soil will then be ripped to a depth of 16 -18 inches.

The previously salvaged top soil will then be redistributed over the total disturbed area. Soil depth and soil cover are addressed in Chapter 2.

The seedbed will be prepared by completing the final grading and again either gouged or ripped to a depth of 6-18 inches or to bedrock. Ripping the soil will be completed at a speed that maximizes the action of the ripper shanks and promotes spoil material disruption to the required depth.

During the final ripping or gouging process, seedbed material will be collected and sent to a laboratory for analysis to determine fertilizer

requirements. The fertilizer recommendations will be added to the soil at the specified rate of application. Seed and fertilizer will be distributed utilizing a hydroseeder . Fertilizer and seed will not be mixed during hydroseeding operations.

Hydroseeding operations will not be conducted when wind velocities would interfere with the even distribution of the material. All efforts will be made to attain an even distribution of seed. (See Appendix 5.8)

Once Hydroseeding is complete, the area will be hydromulched, see Appendix 5-8 and Section 341.230.

The area will be seeded and fertilized (if needed) with the recommended species ( see TABLE 3-4), and nutrients at the specified rate of application. At present a general recommendation indicates that 100 pounds per acre of 16-16-8 will need to be added as a nutrient.

All efforts will be made to insure the quality of materials purchased for reclamation activities are maintained throughout all work. Commercially purchased seed will have the seed names, lot number, percentages of purity, germination, hard seed and percentage of maximum weed seed count clearly marked on each container. No seed will be accepted if they contain seeds of a state-recognized noxious weed species. Sources for "common" seed should be those with climatic and elevational characteristics as close to site characteristics as possible. Legume seed will be inoculated with the correct Rhizobium.

**341.230.** The site will be hydro-seeded with seed and an initial 500#/acre of mulch and 100#/acre of tac agent. Followed shortly by an additional 1500 to 2000#/acre of mulch. Finally, an additional 100#acre of tac and fertilizer, choice and application rate to be determined by the testing

in section 243, will be applied. Fertilizer and seeds will not be mixed together during the hydro-mulching operations.

**341.240.** There will be no irrigation or supplementary water used during or after the revegetation of the area. There are no planned pest or disease control measures for the mine site reclamation. Pest or disease control measures may be included in this plan if results from the test plot and / or reference area indicate a need. The measures will be consistent with proper rangeland and wildlife management.

**341.250.** A reference area for the mine site disturbance was established adjacent to the proposed facilities during the summer of 2003 (Figure 1, Appendix 3-1). The reference area was chosen in an area which represents the natural premining conditions of the permit area. This reference area will facilitate the determination of successful revegetation and the resultant final bond release for the Applicant.

Comparisons of the revegetated area and the reference area will be made using the data obtained from the ninth and tenth year sampling. This data will be used to obtain statistical information that will show the site meets the requirements for bond release.

**341.300.** The methods outlined have a proven performance based on the successful reclamation of the Horse Canyon Mine in the immediate drainage to the north (less than two miles) in like habitat and aspect.

The Operator will conduct a study to determine the optimum time for seeding warm seasons species (refer to page 29).

Table 3.4/3.5 INTERIM AND FINAL RECLAMATION SEED MIX Recommended Seed Mix for Lila Canyon Mine						
Species	Latin Name	Seeds/lb	# Seeds per Acre Planted	%Mix Planted	Seeding Rate Lbs / acre	Seeds / ft <sup>2</sup>
<u>Grasses</u>						
Needle And Thread	Stipa Comata	115,000	230,432	5	2.00	5.3
Indian Ricegrass	Achnatherum humenoides	141,000	282,269	6	2.00	6.5
Basin Wild Rye	Leymus cinereus	130,000	129,373	3	1.00	3.0
Galleta	Hilaria jamesii	314,500	313,632	6	1.00	7.2
Bluebunch Wheatgrass	Pseudoroegneria spicata	140,000	139,392	3	1.00	3.2
Slender Wheatgrass	Elymus trachycaulus	159,000	317,988	6	2.00	7.3
Blue Gamma	Bouteloua gracilis	825,000	827,640	17	1.00	19.0
Subtotal						51.4
<u>Forbs</u>						
Blue Flax	Linum lewisii	293,000	294,030	6	1.00	6.8
Palmer Penstemon	Penstemon palmeri	610,000	152,460	3	0.25	3.5
Globemallow	Sphaeralcea ambigua	500,000	250,470	5	0.50	5.8
Indian Paintbrush	Castilleja linariaefolia	4,915,000	479,160	10	0.10	11.0
Fringed Sage	Artemisia frigida	4,536,000	435,600	9	0.10	10.0
Subtotal						37.0
<u>Shrubs</u>						
Wyoming Big Sage	Artemisia tridentata	2,576,000	653,400	13	0.25	15.0
Green Rabbitbrush	Chrysothamnus nauseosus	400,000	41,382	1	0.10	1.0
Fourwing Saltbush	Atriplex canescens	52,000	43,560	1	0.84	1.0
Winterfat	Ceratoides lanata	56,700	56,628	1	1.00	1.3
Shadscale	Antriplex confertifolia	64,900	64,904	1	1.00	1.5
Cliffrose	Cowania mexicana	64,600	64,469	1	1.00	1.5
Black Sage	Artemisia nova	907,200	230,868	5	0.25	5.3
Subtotal						26.5
<b>TOTAL PER ACRE</b>		<b>16,799,900</b>	<b>5,007,658</b>	<b>100</b>	<b>16.39</b>	<b>115</b>

**342. Fish and Wildlife. A fish and wildlife plan follows:**

**342.100.** The sediment pond will be maintained through the life of the operation and will be removed when effluent criteria is met following reclamation.

**342.200.** Rangeland for domestic stock is the secondary intended postmining land use with wildlife habitat as the primary land use. Plant species appropriate for enhancing the wildlife habitat were selected on the basis of known wildlife requirements including nutritional value for fish and wildlife, use as cover for fish and wildlife and ability to support and enhance fish and wildlife habitat. The Pinyon/Juniper area will be enhanced and reclaimed to the Grass/Shrub community type. The habitat type provides excellent winter range for big game, as well as, an increase in rodent populations which in turn are beneficial to raptors. The Lila Canyon EA has stipulated that in excess of 70 acres of wildlife habitat will be enhanced to help offset negative impacts.

**342.210.** This section is addressed in 342.200.

**342.220.** This section is addressed in 342.200.

**342.230.** This section is addressed in 342.200.

**342.300.** This section is not applicable.

**342.400.** This section is not applicable.

**350. Performance Standards**

**351.** All coal mining and reclamation operations will be carried out according to plans provided under R645-301-330 through R645-301-340.

- 352.** Lila Canyon Mine will implement contemporaneous reclamation on all areas that are disturbed through construction or in the course of mining that will not be utilized for future activity that constitutes continued disturbance.
- 353.** General Requirements. The Permittee will establish on regraded areas and on all other disturbed areas a vegetative cover that is in accordance with the approved permit and reclamation plan. The first available season following abandonment / completion the area will be seeded and mulch in accordance with the approved reclamation plan.
- 353.100** The contemporaneous seed mix TABLE 3-5 is capable of self-regeneration.
- The seed mix in Table 3-5 is designed to be compatible with native plant species and beneficial to the animals indigenous to the area for both forage and cover.
- All seed used in contemporaneous revegetation will be certified and in compliance with all state and federal laws governing seeding.
- 353.130.** The vegetative cover will be at least equal in extent of cover to the natural vegetation of the area; and
- 353.140.** Capable of stabilizing the soil surface from erosion.
- 353.200.** The reestablished plant species will:
- 353.210.** Be compatible with the approved postmining land use:
- 353.220.** Have the same seasonal characteristics of growth as the original vegetation:
- 353.230.** Be capable of self-regeneration and plant succession:
- 353.240.** Be compatible with the plant and animal species of the area; and:

- 353.250.** Meet the requirements of applicable Utah and federal seed, poisonous and noxious plant; and introduced species laws or regulations.
- 353.300.** The Division may grant exception to the requirements of 353.220 and 353.230 when the species are necessary to achieve a quick-growing, temporary, stabilizing cover, and measures to establish permanent vegetation are included in the approved permit and reclamation plan.
- 353.400.** There are no prime farm lands within the permit area or anticipated crop lands.
- 354.** Timing: Seeding will occur between September 30 and may proceed up until March 30 depending on snow and frost condition
- DOG M has expressed a concern over the fall planting of the warm season species, Blue grama and Galleta. Both of these species are in evidence at the Horse Canyon Site, which was reclaimed in the fall of 1991. However, UEI is committed to use these species in the interim seed mix, adjacent to the sediment pond. Area 1, the Southeast corner, and Area 4 the Northwest corner of the pond disturbance, will be seeded mid summer (July) following the construction. Area 2, the Southwest quarter and Area 3 the Northeast quarter of the disturbance, will be seeded late fall (October) following construction. The line separating the four areas will be staked on the ground. Ocular estimates of the success of the reclamation will be implemented each fall for 3 years following the reclamation. In year 4, if there appears to be an apparent difference in success, a quantitative sample will be taken. The sample will identify both species composition as well as overall vegetative cover for both areas.
- If in the event a conclusion as to the timing of planting results in a significant degree of success, the reclamation plan can be modified during the 5 year renewal process.
- 355.** Mulch will be applied on the same bases as indicated for permanent reclamation.
- 356.** Standards for Success:

**356.100** Success of revegetation will be judged on the effectiveness of the vegetation for the approved postmining land use, the extent of cover compared to the extent of cover of the reference area.

**356.110.** Standards for success, statistically valid sampling techniques for measuring success, and approved methods are identified in the Division's "Vegetation Information Guidelines, will be followed closely. (See "Lila Canyon Vegetation Inventory" found in Appendix 3-1)

**356.120.** Standards for success recommended in the "Vegetation Information Guidelines" will be followed closely. (See "Lila Canyon Vegetation Inventory" found in Appendix 3-1)

**356.200.** Standards for success will be applied in accordance with the approved postmining land use of wildlife and incidental use by domestic stock.

**356.210.** This Section does not apply since the area is post mining wildlife habitat, with incidental use by domestic stock.

**356.220.** This Section does not apply since there are no agriculture lands within the permit area and no prime farm lands. See Chapter 2, Appendix 2-1 (Prime Farmland Letter).

**356.230.** Success of vegetation will be determined on the basis of tree and shrub stocking and vegetative ground cover. Such parameters are described as follows:

The requirements for cover, productivity and woody plant density are, at least 90% of the cover, woody plant density and productivity of the reference area with 90% statistical adequacy. The site will be sampled in a manner similar to the

method used to sample the reference area.

Diversity will be determined with the following method:

- 1) All species encountered with at least a 20% frequency in the vegetation sampling will be categorized into life forms. The life form categories that will be used are native grass, native broadleaf forbs, native shrub, desirable introduced, and undesirable. Undesirable species are those generally classified as weeds or that are poisonous to livestock. If there is any question whether a species should be considered undesirable, the Division and UtahAmerican will consult with the Emery County Weed Department.
- 2) The standard will be that the reclaimed area must have at least as many native grass, native broadleaf forbs, and native shrub species occurring at 20% or greater frequency as the reference area. For example, if the reference area has 3 native shrub species occurring at 20% or greater frequency, the reclaimed area must also have this many species. The species do not need to be the same.

Essentially the same method would be used to judge seasonality, but the only categories would be warm and cool season.

Erosion control relative to both vegetation density and species composition would be based on effluent standards as committed in the UDPES permit. All drainages leading away from the permit area will be sampled as often as practical. When effluent standards are met, the vegetation will have demonstrated its erosion control effectiveness. Woody plant density for the entire area will be established with 1,500 plants per acre, unless the Divisions consultation

with area agencies determines a different density.

**356.231.** (See Section 256.230)

**356.232.** Tree stocking / woody plant density will meet or exceed UDOGM guidelines for bond release.

**356.233.** Success standards for vegetative ground cover: (See Section 256.230)

**356.240.** This Section does not apply since no portion of the permit area will be used for industrial, commercial or residential use.

**356.250.** No pre-law mining occurred on the Lila Canyon Permit area.

**356.300.** Lila Canyon Mine is committed to maintain siltation structures until vegetative cover is adequate to allow runoff to meet affluent limits as directed by UDOGM at a minimum two years following vegetation establishment.

**356.400.** Lila Canyon Mine will have all disturbance associated with removal of siltation structures seeded and mulch in accordance with the approved revegetation plan.

**357. Revegetation: Extended Responsibility Period.**

**357.100.** The period of extended responsibility for successful vegetation will begin after the last year of seeding, fertilization, irrigation, or other work, excluding approved husbandry practices.

**357.200.** Vegetation parameters will equal or exceed the

approved success standard during the growing seasons for the last two years of the responsibility period. The period of extended responsibility will continue for five or ten years based on precipitation data.

**357.210.** Since Lila Canyon has an average annual precipitation of less than 26.0 inches this section is not applicable.

**357.220.** The mine plan area averages nine inches at the lowest elevation (area of greatest disturbance) to fourteen to sixteen inches at the highest elevation. Lila Canyon Mine will assume the ten year bond liability period.

**357.300. Husbandry Practices - General Information**

**357.301.** Lila Canyon Mine would like to reserve the right to apply for augmentation of reclaimed area extending the bond liability period on a site specific case scenario.

**357.302.** Husbandry practices proposed for the reclaimed areas are not necessitated by inadequate grading practices, adverse soil conditions, or poor reclamation procedures.

**357.303.** The Division will consider the entire area that is bonded within the same increment, as defined in R645-301-820.110, when calculating the extent of area that may be treated by husbandry practices.

**357.304.** If it is necessary to seed or plant in excess of the limits set forth under R645-301-357.300, the Division may allow a separate extended responsibility period for these reseeded or replanted areas in accordance with R645-301-820.330.

**357.310. Reestablishing trees and shrubs**

- 357.311.** Trees or shrubs may be replanted or reseeded at a rate of up to a cumulative total of 20% of the required stocking rate through 40% of the extended responsibility period.
- 357.312.** Lila Canyon Mine has incorporated wood plant / tree seeding into the seed mix (see TABLE 3-4). If after two years following seeding and mulching it is apparent that woody plant density / tree cover appear to be insufficient for bond release; the mine may elect to re-enter selected areas and augment the direct seeding with either / or containerized or bare root seedlings, this determination will need to be made on a site specific bases. The goal for bond release is the establishment of 1500 woody plants per acre.
- 357.320.** Based on similar reclamation projects in adjacent areas, the need to control weeds other than by selected removal is unlikely. In the unlikely event that weed control is required by chemical means, R645-357357.321 will be followed. In the unlikely event that weed control is required by Biological means, R645-357.323 will be followed. In the unlikely event that weed control is required by mechanical means, R645-357.322 will be followed.
- 357.321.** In the unlikely event that weed control is required by Chemical means, R645-357.321 will be followed by mine personnel.
- 357.322.** In the unlikely event that weed control is required by Mechanical means, R645-357.322 will be followed by mine personnel.
- 357.323.** In the unlikely event that weed control is required by Biological

means, R645-357.323 will be followed by mine personnel.

**357.324.** In the unlikely event that weed control practices damage desirable vegetation, R645-357.324 will be followed by mine personnel.

**357.330.** Wildlife habitat is the priority post mining land use. As such, control of wildlife is not anticipated.

**357.331.** Wildlife habitat is the priority post mining land use. As such, control of wildlife is not anticipated.

**357.332.** Mine personnel do not anticipate a need to implement control measures for small mammals or insects. However, in the unlikely event that control is necessary, R645-357.332 will be followed. The Division must approved animal control methods sited in R645-357.332.

**357.340.** Natural Disasters and Illegal Activities Occurring After Phase II Bond Release. Where necessitated by a natural disaster, excluding climatic variation, or illegal activities, such as vandalism, not caused by any lack of planning, design, or implementation of the mining and reclamation plan on the part of the Permittee, the seeding and planting of the entire area which is significantly affected by the disaster or illegal activities will be allowed as an accepted husbandry practice and thus will not restart the extended responsibility period. Appendix C of the Division's "Vegetation Information Guidelines" references publications that show methods used to revegetate damaged land. Examples of natural disasters that may

necessitate reseeding which will not restart the extended responsibility period include wildfires, earthquakes, and mass movements originating outside the disturbed area.

**357.341.** The extent of the area where seeding and planting will be allowed will be determined by the Division in cooperation with the Permittee.

**357.342.** All applicable revegetation success standards will be achieved on areas reseeded following a disaster, including R645-301-356.232 for areas with a designated postmining land use of forestry or wildlife.

**357.343.** Seeding and planting after natural disasters or illegal activities will only be allowed in areas where Phase II bond release has been granted.

**357.350.** No Irrigation is anticipated.

**357.360.** Rills and gullies in excess of eight inches width and / or depth will be repaired on a seasonal bases. Repairs will be made in such manner that minimizes additional disturbance and yet is cost effective based on site specific conditions.

**357.361.** After the first 20% of the extended responsibility period but prior to the end of the first 60% of the responsibility period or until Phase II bond release, whichever comes first, highly erodible area and rill and gully repair will be considered augmentative, and will thus restart the responsibility period, if the area

- to be repaired is greater than 3% of the total disturbed area or if a continuous area is larger than one acre.
- 357.362.** The extent of the affected area will be determined by the Division in cooperation with the Permittee.
- 357.363.** The area affected by the repair of highly erodible areas and rills and gullies is defined as any area that is reseeded as a result of the repair. Also included in the affected areas are interspatial areas of thirty feet or less between repaired rills and gullies. Highly erodible areas are those areas which cannot usually be stabilized by ordinary conservation treatments and if left untreated can cause severe erosion or sediment *damage*.
- 357.364.** The repair and/or treatment of rills and gullies which result from a deficient surface water control or grading plan, as defined by the recurrence of rills and gullies, will be considered an augmentative practice and will thus restart the extended responsibility period.
- 357.365.** The areas of concern on the initial reclamation are those natural drainage channels which will be reconstructed during the earth moving phase of reclamation. Specific design and specifications are included in Chapter 7 (Drainage Design). All regraded areas in excess of three percent slope will be sacrificed to aid in the retention of moisture and minimize

erosion. Areas in excess of 3:1 slopes will receive additional mulch and tac to facilitate vegetation establishment.

**358.** Protection of Fish, Wildlife Values: Mine personnel will be trained annually on environmental awareness, a portion of the training will deal with wildlife concerns, such as avoidance during stress periods, caution in driving to and from work during peak usage periods, recognition of any threatened and endangered species etc. Speed limits will be posted to minimize vehicular / wildlife accidents. In addition, all suitable water encountered during mining will be discharged in such a manner to make it available to wildlife.

**358.100.** Appendix 3-3 is a letter from U.S. Fish and Wildlife Service identifying all threatened and endangered species that could occur in the permit area or within a one-half mile proximity. All mine personnel will be trained about these species and notify the environmental coordinator at the mine. The environmental coordinator will confirm, if possible, the identification, notify USFWS and the Division, and then take what ever actions are necessary to safeguard both the species and it's habitat.

In addition, a threatened and endangered species inventory will be conducted prior to any disturbance. Historical as well as current threatened and endangered inventories are included in Appendix 3-4.

Prior to any new surface disturbance a raptor inventory will be conducted to ensure that no raptors or their nests or young would be adversely impacted through any mining or mine related activity. A copy of historical raptor data as well as current survey results are attached as Appendix 3-5.

A one-half mile buffer zone of no new disturbance during critical nesting periods will be maintained during that portion of the year that the nest sites are active.

As part of normal mining operation requirements, the Permittee must submit all results of the raptor surveys to the Division in Annual Reports and must immediately contact the Division, BLM, and USFWS following any raptor survey that shows that eagles are tending nests or nesting. The agencies will immediately coordinate to determine if the Permittee must implement appropriate measures. If the agencies recommend mitigation, the Permittee must submit all plans to the Division for incorporation into Appendix 3 of the MRP.

In the event of unforeseen changes in construction or mine plans, or in the case of emergency situations that may force the Permittee to conduct activity near or within the 0.5 mile buffer zone of raptor nest and during raptor exclusionary periods (February 1 to July 15 for golden eagles), the Permittee will immediately contact the Division, BLM, DWR, and USFWS. The agencies will immediately coordinate to determine appropriate measures that may include conducting ground surveys, in coordination with DWR, to determine if birds are tending nests or nesting and possibly determine the life stage of the offspring; developing a mitigation plan, in coordination with the agencies, for possible impacts to nests or birds; or ceasing operations until the end of breeding season to avoid 'take'. If the agencies recommend surveys, the Permittee must submit all survey results to the Division in Annual Reports. If the agencies recommend mitigation, the Permittee must submit all mitigation plans to the Division for incorporation

- 358.200.** No coal mining and reclamation operations will be conducted in a manner which would result in the unlawful taking of a bald or golden eagle, its nests, or any of the eggs.
- 358.300.** This section is addressed in 358.200.
- 358.400.** There are no wetlands and / or riparian areas within the area of potential disturbance.
- 358.500.** Each operator will, to the extent possible using the best technology currently available:

- 358.510.** All power and transmission lines will be designed with the best technology available to safeguard raptors.
- 358.520.** All structures; fences, conveyors etc., will be designed to allow free movement of large mammals except in those areas where it is necessary to preclude large animals for their own safety; example: power substations, oil storage area etc.
- 358.530.** All structures; fences, conveyors etc., will be designed to allow free movement of large mammals except in those areas where it is necessary to preclude large animals for their own safety; example: power substations, oil storage area etc.

731.214.2 until "Monitoring is no longer necessary to achieve the purposes set forth in the monitoring plan approved under R645-301-731.211."

Therefore, UEI requests that the ground water monitoring plan be modified as follows:

One spring to the north of the northern edge of the permit boundary named Quaker Spring, will be monitored for two years to develop a baseline data set. It will be designated as L-20-G. Following the baseline data collection its monitoring will follow the operational monitoring schedule for the upper springs (shown on Table 7-3).

As baseline for the ground water conditions has been described by the monitoring to date for the Lila Canyon permit area, UEI ~~would like to~~will discontinue monitoring of the monitoring well water levels until mining intercepts the projected regional piezometric surface, as shown on Plate 7-1, and the springs and seeps until just before second mining takes place within the mine permit area. If mining encounters the regional piezometric surface, then water level monitoring will be resumed. Two years before second mining is anticipated to ~~start~~enter into an area that could affect the surface waters, then monitoring of the wells and springs and seeps will resume and the data compared with the baseline. All surface water monitoring will not start at the same time. Monitoring will resume as the second mining enters an area where the mining could affect the surface waters.

UEI recognizes the Division's concerns for springs, L-G-16 and L-G-17, located at the top of the Mancos Shale, below the escarpment. While concerns of the use of these springs for wildlife have been suggested, UEI does not believe that the wildlife are using these waters. The TDS values have been excessive which are believed to limit or preclude the use of this water by wildlife. At the Division's request, these sampling sites will continue to be monitored, while additional evaluation of wildlife use is made.

The existing baseline data shows the current ground water conditions for the permit area. No significant groundwater impacts have been identified from current first mining

As baseline for the surface water conditions have been described by the monitoring to date for the Lila Canyon permit area, UEI ~~would like to~~will discontinue monitoring of the surface water sites away from the surface facilities until just before second mining takes place within the mine permit area. Two years before second mining is anticipated to start, then monitoring will commence again and the data compared with the baseline.

The existing baseline data shows the current surface water conditions for the permit area. No significant surface water impacts have been identified from current first mining activities. Continuous additional monitoring will only unnecessarily duplicate costs for data that has already been collected.

As the two years of ephemeral wash characterization data have been collected and the data reflects the flow conditions as described in the surface water hydrology sections of the PAP, the sites CG-1 through CG-7 will be suspended and discontinued. Also, the upper rain gauge RS-2 will be suspended. These sites were installed and data were collected, as part of a Board Order settlement, to demonstrate that the upper drainages were ephemeral in nature and that the flow characteristics had been correctly described in the PAP.

Additionally, the sampling frequency for sites ~~L-S-1~~L-1-S, ~~L-S-2~~L-2-S, and ~~L-S-3~~L-3-S be changed from monthly to quarterly. As the baseline for these sites have been determined and there is no impact from the mining, reduction of the sampling frequency is justified. These sites will be sampled quarterly and flows will be recorded when they occur.

Also, it is desired that the monitoring during the first quarter not be continued. During the data collection period, there have been few first quarter periods when it was feasible to gain access to the upper elevations of the Book Cliffs and when access was available to the top during these periods, the snow cover in the canyons prevented access to the sampling locations and the sites which were accessed were either dry or frozen. Therefore, it would be realistic to

recognize the existing field conditions and adjust the monitoring plan accordingly.

The monitoring plan would be modified to require monitoring during the 2<sup>nd</sup>, 3<sup>rd</sup>, and 4<sup>th</sup> quarters.

[See Table 7-3 for the surface water monitoring schedule.](#)

**731.225 Monitoring Equipment** Equipment, structures and other devices used in conjunction with monitoring the quality and quantity of surface water on-site and off-site will be properly installed, maintained and operated and will be removed by the operator when no longer needed.

**731.300 Acid- and Toxic-Forming Materials** Drainage from acid- and toxic-forming materials and underground development waste into surface water and ground water will be avoided by implementation of a Spill Prevention Control and Countermeasure (SPCC) Plan and by the following:

**731.311 Identification/Burial of Acid- or Toxic-Forming Materials**

Potentially acid- or toxic-forming materials will be identified by use of Material Safety Data Sheets (MSDS), or by direct sampling and analysis in the case of underground development waste.

Any material which exhibits acid- or toxic-forming characteristics will be properly stored, protected from runoff, removed to an approved disposal site or buried on site beneath a minimum of 4' of non-acid, non-toxic material.

**731.312 Storage of Acid- or Toxic-Forming Materials** Storage of potentially acid- or toxic-forming materials, such as fuel, oils, solvents and non-coal waste will be in a controlled manner, designed to contain spillage and prevent runoff to surface or ground water resources.

All oils and solvents will be stored in proper containers within enclosed structures. Fuels will be stored in appropriate tanks, enclosed within concrete or earthen bermed areas designed to contain any spillage.

<b>Table 7-3</b> Lila Canyon Mine Water Monitoring Stations				
Station	Location	Type	Frequency	Remarks
L-11-G	Lila Canyon	Spring	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Mont/Leslie Spring Replaces L-6-G Water Right 91-618
L-12-G	Section 25 Spring	Spring	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Replaces L-10-G
L-13-S	Little Park Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	At Road Crossing
L-14-S	Section 25 Noname Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	At Road Crossing
L-15-S	Williams Draw Wash	Dry Wash	<b>Sampling Permanently Suspended 1Qtr of 2003</b>	At Road Crossing
L-16-G	Stinky Spring Wash	Seep	Quarterly <u>2-3-4</u>	Top of Mancos
L-17-G	Stinky Spring Wash	Seep	Quarterly <u>2-3-4</u>	Top of Mancos
L-18-S	Stinky Springs Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Adjacent to Access Road
L-19-S	Little Park Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	At Permit Boundary

<b>Table 7-3</b> Lila Canyon Mine Water Monitoring Stations				
Station	Location	Type	Frequency	Remarks
L-20-G	Quaker Spring	Seep	<b>Sampling            Commenced            4Qtr</b> <u>Temporarily Suspended            3Qtr 2014</u>	North of Permit Boundary
IPA-1	Little Park	Borehole	<b>Sampling            Temporarily            Suspended            3Qtr 2011</b>	Water Level Only
IPA-2	Little Park	Borehole	<b>Sampling            Temporarily            Suspended            3Qtr 2011</b>	Water Level Only
IPA-3	Little Park	Borehole	<b>Sampling            Temporarily            Suspended            3Qtr 2011</b>	Water Level Only

NOTE: Sites CG-2, CG-3, CG-4, CG-5, CG-6, and CG-7 were suspended following completion of wash characterization study.

Other sites temporarily suspended until two year prior to second mining influence.

Due to access concerns only the 2<sup>nd</sup>, 3<sup>rd</sup> and 4<sup>th</sup> quarters will be sampled. First quarter has been no access.

**731.214.2** until "Monitoring is no longer necessary to achieve the purposes set forth in the monitoring plan approved under R645-301-731.211."

Therefore, UEI requests that the ground water monitoring plan be modified as follows:

One spring to the north of the northern edge of the permit boundary named Quaker Spring, will be monitored for two years to develop a baseline data set. It will be designated as L-20-G. Following the baseline data collection its monitoring will follow the operational monitoring schedule for the upper springs (shown on Table 7-3).

As baseline for the ground water conditions has been described by the monitoring to date for the Lila Canyon permit area, UEI will discontinue monitoring of the monitoring well water levels until mining intercepts the projected regional piezometric surface, as shown on Plate 7-1, and the springs and seeps until just before second mining takes place within the mine permit area. If mining encounters the regional piezometric surface, then water level monitoring will be resumed. Two years before second mining is anticipated to enter into an area that could affect the surface waters, then monitoring of the wells and springs and seeps will resume and the data compared with the baseline. All surface water monitoring will not start at the same time. Monitoring will resume as the second mining enters an area where the mining could affect the surface waters.

UEI recognizes the Division's concerns for springs, L-G-16 and L-G-17, located at the top of the Mancos Shale, below the escarpment. While concerns of the use of these springs for wildlife have been suggested, UEI does not believe that the wildlife are using these waters. The TDS values have been excessive which are believed to limit or preclude the use of this water by wildlife. At the Division's request, these sampling sites will continue to be monitored, while additional evaluation of wildlife use is made.

The existing baseline data shows the current ground water conditions for the permit area. No significant groundwater impacts have been identified from current first mining

activities. Continuous additional monitoring will only unnecessarily duplicate costs for data that has already been collected.

Also, it is desired that the monitoring during the first quarter not be continued. During the data collection period, there have been few first quarter periods when it was feasible to gain access to the upper elevations of the Book Cliffs and when access was available to the top during these periods, the snow cover in the canyons prevented access to the spring locations and the springs which were accessed were frozen. Therefore, it would be realistic to recognize the existing field conditions and adjust the monitoring plan accordingly.

The monitoring plan would be modified to require monitoring during the spring, summer and fall quarters.

**731.215 Monitoring Equipment** equipment, structures and other devices used in conjunction with monitoring the quality of ground water on-site and off-site will be properly installed, maintained and operated and will be removed by the operator when no longer needed.

**731.220 Surface Water Monitoring** Surface water monitoring will be conducted in accordance with the plan described in this section.

Based on results of the PHC determination, baseline study and other available information, numerous small springs and seeps exist within, and adjacent to, the permit area. In addition, ephemeral drainages in the area flow in response to snow melt and precipitation events. The proposed surface water monitoring program will monitor the significant surface water sources, including drainages above and below the disturbed mine site area, and all point-source discharges (i.e. sediment pond). Seeps, springs and potential mine water discharge will be monitored in accordance with the Ground Water Monitoring Plan in the previous section.

It should be noted that field sheets in Appendix 7-2 refer to a point HC-2, while Bar Graphs and Spreadsheets refer to a station B-1. It has been determined that these are the same point. The site is designated B-1 on Plate 7-1, with a red HC-2 in parenthesis. The

electronic data inventory (EDI) also shows both B-1 and HC-2 designations for this site.

Another HC-2 site is listed in the seep/spring inventories in Appendix 7-6 and in the baseline data in Appendix 7-1. This station is also occasionally referred to as H-2 in the seep/spring inventories (Appendix 7-6). It has been determined that the H-2 and HC-2 sites referred to in these two appendices are the same station. The station location is shown on Plate 7-1, where it is designated H-2 with a green (HC-2) in parentheses.

There is one other station with confusing designations in the data from Appendix 7-2 and 7-6 - station HCSW-1. This station has 3 different designations in the data - HCSW-1, HSW-1, and HC-1. The point is shown as HC-1 on Plates 7-1 and 7-4; however, a note has been added to Plate 7-1 to show the station is also called (HCSW-1), to eliminate confusion. It should also be noted that there is a seep/spring site designated as H-1 on Plate 7-1. This is not to be confused with any of the above listed HC, HSW or HCSW sites.

These are the only known duplication or wrong designation of sample site numbers. It appears that different samplers or companies conducting seep/spring inventories occasionally used different designations for the same sites - the main problem being the use of H-# or HC-# for the same location, in some instances. Every effort has been made to refine the station identifications and locations on Plate 7-1 to reflect the sampling data provided in Appendices 7-1, 7-2 and 7-6. Wherever a site has 2 different designations, both are shown with one in parentheses.

Table 7-3 presents a list of proposed surface water monitoring sites. Based on the two years of surface water sampling at locations CG-2, CG-3, CG-4, CG-5, CG-6, and CG-7 which characterized the drainages as Intermittent by rule with ephemeral flow or ephemeral, which matched the description of these drainages provided in the PAP, these sampling locations will no longer be sampled. Additionally, the surface water sites for these drainages are also requested to be discontinued as explained below in Section 731.224.2.

Locations of all monitoring sites are shown on Plate 7-4 , "Water Monitoring Location Map".

Proposed monitoring methods, parameters and frequencies are described in Table 7-3, "Water Monitoring Stations", Table 7-4, "Surface Water Monitoring Parameters", and Table 7-5 "Ground Water Monitoring Parameters".

In any active quarter, a minimum of three unsuccessful attempts will be made by using either 4 wheel drive vehicles or ATV's to access all water monitoring sites prior to reporting any site as "No Access". However, safety and common sense will prevail while making these attempts.

Monitoring reports will be submitted to the Division at least every 3 months, within 30 days following the end of each quarter.

**731.221 Surface-Water Monitoring Plan** The proposed surface-water monitoring plan is detailed in Section 731.220. This plan is based on PHC determination and analysis of all baseline hydrologic, geologic and other information in this permit application. The plan provides for monitoring of parameters that relate to the suitability of the surface water for current and approved postmining land uses and to the objectives for protection of the hydrologic balance as set forth in 751 (see Table 7-4).

**731.222 Surface-Water Monitoring Parameters** The surface-water monitoring parameters are shown in Table 7-4. Water monitoring locations and sample frequencies are described in Table 7-3 and on Plate 7-4 .

The plan will provide data to show impacts to potentially affected springs, seeps, impoundments and drainages within and adjacent to the permit area, by comparison with relevant baseline data and with applicable effluent limitations.

**731.222.1 Non-point Source Locations** The parameter list in Table 7-4 provides monitoring for all parameters required by this section. The monitoring locations and frequencies described in Table 7-3 show that all significant springs, seeps, impoundments and drainages that could potentially be impacted by the mining and reclamation operations will be monitored on a regular basis.

**731.222.2 Point-source Discharges** Point-source discharge monitoring will be conducted in accordance with 40 CFR Parts 122 and 123, R645-301-751 and as required by the Utah Division of Environmental Health for Utah Pollutant Discharge Elimination System (U.P.D.E.S.) permits. A U.P.D.E.S. discharge permit application has been submitted to the Division of Environmental Health for the proposed sediment pond and mine water for the Lila Canyon operation. Existing U.P.D.E.S. permit applications for the Lila Canyon Mine are provided in Appendix 7-5.

**731.223 Reporting** As indicated in Section 731.220, surface-water monitoring data will be submitted at least every 3 months during active monitoring for each monitoring location. When analysis of any surface water sample indicates non-compliance with the permit conditions, the company will promptly notify the Division and immediately take actions to identify the source of the problem, correct the problem and, if necessary, to provide warning to any person whose health and safety is in imminent danger due to the non-compliance.

**731.224 Duration** Surface-water monitoring will continue through mining and reclamation until bond release. Locations, parameters and/or sampling frequency (other than U.P.D.E.S. discharge points) may be modified by the Division if:

**731.224.1** "The operator has minimized disturbance to the hydrologic balance in the permit and adjacent areas and prevented material damage to the hydrologic balance outside the permit area; water quantity and quality are suitable to support approved postmining land uses"; or,

**731.224.2** "Monitoring is no longer necessary to achieve the purposes set forth in the monitoring plan approved under 731.221.

Therefore, UEI requests that the surface water monitoring plan be modified as follows:

As baseline for the surface water conditions have been described by the monitoring to date for the Lila Canyon permit area, UEI will discontinue monitoring of the surface water sites away from the surface facilities until just before second mining takes place within the mine permit area. Two years before second mining is anticipated to start, then monitoring will commence again and the data compared with the baseline.

The existing baseline data shows the current surface water conditions for the permit area. No significant surface water impacts have been identified from current first mining activities. Continuous additional monitoring will only unnecessarily duplicate costs for data that has already been collected.

As the two years of ephemeral wash characterization data have been collected and the data reflects the flow conditions as described in the surface water hydrology sections of the PAP, the sites CG-1 through CG-7 will be suspended and discontinued. Also, the upper rain gauge RS-2 will be suspended. These sites were installed and data were collected, as part of a Board Order settlement, to demonstrate that the upper drainages were ephemeral in nature and that the flow characteristics had been correctly described in the PAP.

Additionally, the sampling frequency for sites L-1-S, L-2-S, and L-3-S be changed from monthly to quarterly. As the baseline for these sites have been determined and there is no impact from the mining, reduction of the sampling frequency is justified. These sites will be sampled quarterly and flows will be recorded when they occur.

Also, it is desired that the monitoring during the first quarter not be continued. During the data collection period, there have been few first quarter periods when it was feasible to gain access to the upper elevations of the Book Cliffs and when access was available to the top during these periods, the snow cover in the canyons prevented access to the sampling locations and the sites which were accessed were either dry or frozen. Therefore, it would be realistic to recognize the existing field conditions and adjust the monitoring plan accordingly.

The monitoring plan would be modified to require monitoring during the 2<sup>nd</sup>, 3<sup>rd</sup>, and 4<sup>th</sup> quarters.

See Table 7-3 for the surface water monitoring schedule.

**731.225 Monitoring Equipment** Equipment, structures and other devices used in conjunction with monitoring the quality and quantity of surface water on-site and off-site will be properly installed, maintained and operated and will be removed by the operator when no longer needed.

**731.300 Acid- and Toxic-Forming Materials** Drainage from acid- and toxic-forming materials and underground development waste into surface water and ground water will be avoided by implementation of a Spill Prevention Control and Countermeasure (SPCC) Plan and by the following:

**731.311 Identification/Burial of Acid- or Toxic-Forming Materials**

Potentially acid- or toxic-forming materials will be identified by use of Material Safety Data Sheets (MSDS), or by direct sampling and analysis in the case of underground development waste.

Any material which exhibits acid- or toxic-forming characteristics will be properly stored, protected from runoff, removed to an approved disposal site or buried on site beneath a minimum of 4' of non-acid, non-toxic material.

**731.312 Storage of Acid- or Toxic-Forming Materials** Storage of potentially acid- or toxic-forming materials, such as fuel, oils, solvents and non-coal waste will be in a controlled manner, designed to contain spillage and prevent runoff to surface or ground water resources.

All oils and solvents will be stored in proper containers within enclosed structures. Fuels will be stored in appropriate tanks, enclosed within concrete or earthen bermed areas designed to contain any spillage.

Non-coal waste (garbage) will be stored in a designated location, in dumpsters, and removed to an approved landfill (East Carbon Development Contractors - ECDC) on a regular, as-needed basis.

Unused or obsolete equipment or supplies will be stored in a designated area. Drainage from the storage area will be directed to the sediment pond as shown on the Sediment Control Map, Plate 7-5.

Underground development waste (if any) will also be stored in a designated area. Such waste will be tested for acid- or toxic-forming potential, and if found to be acid- or toxic-forming, the waste site will be protected from surface runoff by the use of earthen berms.

**731.320 Storage, Burial, Treatment** All storage, burial and treatment practices will be as described in this permit, and consistent with applicable material handling and disposal provisions of the R645-Rules.

**731.400 Transfer of Wells** There are presently three piezometers on this permit. When these piezometers are no longer required, they will be sealed in a safe, environmentally sound manner in accordance with regulations (see Section 631.200). The Horse Canyon Well has been donated to the College of Eastern Utah as part of the Post Mine Land Use Change.

**731.500 Discharges** The only proposed discharges from this operation will be from the sediment pond and/or underground mine water. Each of these potential discharges would be monitored and controlled within requirements of approved U.P.D.E.S. Discharge Permits.

**731.510 Discharges into an Underground Mine** There are no plans to discharge any water into an underground mine. This section is not applicable.

**731.512 Types of Discharge** The only planned discharges from this site are water, in the form of sediment pond discharge or underground mine water discharge.

**731.512.1 Water** See Section 731.512.

**731.512.2 Coal Processing Waste** N/A - There are no plans to process coal or discharge coal processing waste from this site.

**731.512.3 Fly Ash from a Coal-Fired Facility** N/A - There are no plans for a coal-fired facility at this time.

**731.512.4 Sludge from Acid-Mine-Drainage Treatment**  
N/A There are no plans for an acid-mine-drainage treatment facility at this time.

<b>Table 7-3</b> Lila Canyon Mine Water Monitoring Stations				
Station	Location	Type	Frequency	Remarks
L-1-S	Lila Canyon	Int. Stream	<b>Quarterly</b>	At mine Site
L-2-S	Rt. Fork Lila (above mine)	Ephemeral Stream	<b>Quarterly</b>	RF Above Mine Site
L-3-S	Lila Canyon (below mine)	Int. Stream	<b>Quarterly</b>	RF Below Mine Site
L-4-S	Sediment Pond	Discharge	Monthly or as occurs	Per UPDES Permit
L-5-G	Mine Water	Discharge	Monthly or as occurs	Per UPDES Permit
L-6-G	Lila Canyon	Spring	<b>Sampling Permanently Suspended 1Qtr 2003</b>	Replaced by L-11-G Water Right 91-617
L-7-G	Little Park	Spring	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Cottonwood Spring Sample Site 9 Water Right 91-2521
L-8-G	Little Park	Spring	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Unnamed Spring Sample Site 10 Water Right 91-2538
L-9-G	Little Park	Spring	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Pine Spring Sample Site 16Z Water Right 91-2539
L-10-G	Williams Draw	Spring	<b>Sampling Permanently Suspended 1Qtr 2003</b>	Replaced by L-12-G Water Right 91-809

<b>Table 7-3</b> Lila Canyon Mine Water Monitoring Stations				
Station	Location	Type	Frequency	Remarks
L-11-G	Lila Canyon	Spring	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Mont/Leslie Spring Replaces L-6-G Water Right 91-618
L-12-G	Section 25 Spring	Spring	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Replaces L-10-G
L-13-S	Little Park Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	At Road Crossing
L-14-S	Section 25 Noname Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	At Road Crossing
L-15-S	Williams Draw Wash	Dry Wash	<b>Sampling Permanently Suspended 1Qtr of 2003</b>	At Road Crossing
L-16-G	Stinky Spring Wash	Seep	Quarterly 2-3-4	Top of Mancos
L-17-G	Stinky Spring Wash	Seep	Quarterly 2-3-4	Top of Mancos
L-18-S	Stinky Springs Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Adjacent to Access Road
L-19-S	Little Park Wash	Dry Wash	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	At Permit Boundary

<b>Table 7-3</b> Lila Canyon Mine Water Monitoring Stations				
Station	Location	Type	Frequency	Remarks
L-20-G	Quaker Spring	Seep	<b>Sampling Temporarily Suspended 3Qtr 2012</b>	North of Permit Boundary
IPA-1	Little Park	Borehole	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Water Level Only
IPA-2	Little Park	Borehole	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Water Level Only
IPA-3	Little Park	Borehole	<b>Sampling Temporarily Suspended 3Qtr 2011</b>	Water Level Only

NOTE: Sites CG-2, CG-3, CG-4, CG-5, CG-6, and CG-7 were suspended following completion of wash characterization study.

Other sites temporarily suspended until two year prior to second mining influence.

Due to access concerns only the 2<sup>nd</sup>, 3<sup>rd</sup> and 4<sup>th</sup> quarters will be sampled. First quarter has been no access.

Bonding Calculations  
Horse Canyon MineC/007/013  
Lila Canyon Section

Bond Summary

Direct Costs

Subtotal Demolition and Removal	\$563,565.00	
Subtotal Backfilling and Grading	\$494,315.00	
Subtotal Revegetation	\$238,309.00	
Direct Costs	\$1,296,189.00	

Indirect Costs

Mob/Demob	\$129,619.00	10.0%
Contingency	\$64,809.00	5.0%
Engineering Redesign	\$32,405.00	2.5%
Main Office Expense	\$88,141.00	6.8%
Project Management Fee	\$32,405.00	2.5%
Subtotal Indirect Costs	\$347,379.00	26.8%

Total Cost \$1,643,568.00

Escalation factor for 2013 @1.5% 1.50%  
Number of years 5  
Escalation \$127,022.00

Reclamation Cost \$1,770,590.00

Bond Amount (rounded to nearest \$1,000) \$1,771,000.00  
2013 Dollars

Bond Posted Up to December 2010 \$1,807,000.00

Difference Between Cost Estimate and Bond \$36,000.00  
Percent Difference 1.99%

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Office Bathhouse																				\$95,424
Shop Warehouse																				\$129,592
Security Shack																				\$523
Mine Substation																				\$11,113
Underground Power Lines																				Left in place
Water Treatment Plant																				\$1,983
Potable Water Tank																				1345
Process Water Tank																				1345
Sewer Tank																				\$1,431
Drain Field																				Left in place
Ventilation Fan																				\$51,377
Conveyor Tunnels to Coal Stockpile																				\$32,296
Conveyor ROM Stockpile to Crusher																				11552
Conveyor Crusher to Loadout Bin																				\$8,175
Conveyor Loadout Bin Truck Loadout																				\$538
Reclaim Escape Tunnel Fan House																				18949
Conveyor Storage Pile Staking Tube																				11475
Crusher Screen Plant																				4505
Truck Scale to Loadout																				\$7,907
Coal Storage Bin																				\$4,054
Guard Rail																				4149.52
Underground Pipes																				Left in place
Chain Link Fence																				\$5,715
Mine Facilities Rd Truck Loadout Rd																				\$32,903
Office Bathhouse Warehouse Parking																				\$55,623
Mine Parking																				\$14,016
Fuel Tanks																				\$2,842
Powder and Cap Magazine																				\$2,440
Cutverts																				13334.55
Old Horse Canyon Fan Portals in Lila Canyon																				\$5,000
Lila Ventilation Portals North and South																				\$25,000
Pole Barn																				\$5,613
Rock Dust Silo																				\$2,142
<b>Total</b>																				<b>\$683,665</b>

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volumes	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Office Bathroom																				
Structure's Demolition Cost	Steel Bld. Large	024116130020	0.23 /CF	CF	150	100	15									0.3	225000	CF	53500	
Structure's Vol. Demolished																	23600	CF		
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck			13.63 /Ton	Ton																
Transportation Cost Steel Truck Drive		Scamp																		
Disposal Cost Steel		Nielsons	7.00 /TON	TON																
<b>Subtotal</b>												450			lb/cf					75375
Equipment's Disposal Cost																				
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.53 /BCY	BCY	150	100	1													
Concrete's Vol. Demolished																				
Loading and Trucking Cost			19.37 /LCY	LCY																
Transportation Cost																				
Disposal Costs			9.54 /LCY	LCY																
<b>Subtotal</b>																				21116
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				56494
<b>Total</b>																				

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swall Factor	Quantity	Unit	Cost	
Shop Warehouse																				
Structure's Demolition Cost	Steel Bld. Large	024116130020	0.28	/CF	150	100	20								FT		300000	CF	84000	
Structure's Vol. Demolished																	5.3	3333	CY	
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck																				
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel	Transportation to Nielsons Dump	Scamp	13.63	/Ton																10954
Subtotal	Nielsons Construction	Nielsons	7.00	/TON								480			lb/cf					5900
																				100504
Equipment's Disposal Cost																				
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.63	/CY	150	100	1								FT					3686
Concrete's Vol. Demolished																	1.3	723	CY	
Loading and Trucking Cost																				14005
Transportation Cost																				
Disposal Costs																				
Subtotal																				5827
																				24585
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Total																				
																				125032

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Security Shack																				
Structure's Demolition Cost	Steel Bld, Large	024116130020	0.28	CF	20	10	8										1600	CF	443	
Structure's Vol, Demolished																	0.3	18	CV	
Rubble's Weight, (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck	Transportation to Nielsons Dump	Scamp	13.63	Ton																55
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel												480								28
Subtotal	Nielsons Construction	Nielsons	7.00	Ton																531
Equipment's Disposal Cost																				
Dismantling Cost																				
Equipment's Vol, Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.53	ICY	20	10	0.25													13
Concrete's Vol, Demolished																				
Loading and trucking Cost	Loading and Trucking	024119193090	19.37	ICY																88
Transportation Cost																				0
Disposal Costs	On site disposal	024116174200	9.54	ICY																28
Subtotal																				160
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol, Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol, Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Total																				631

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Mine Substation																				
Structure's Demolition Cost																				
Structure's Vol. Demolished																				
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck																				
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel																				
Subtotal																				
Equipment's Disposal Cost	Mechanical equipment heavy	230505/029600	641.65	ton								4		4	ton					10288
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
Subtotal																				
Equipment's Disposal Cost	Chain link remove 8'-10'	2411360/750	3.41	HLF	160										FT					150
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.63	CY	20	20	0.5								4	FT				45
Concrete's Vol. Demolished																				
Loading and Trucking Cost	Loading and Trucking	024119193080	19.37	/CY													1.3			9
Transportation Cost																				
Disposal Costs	On site disposal	024116174200	9.54	/CY																
Subtotal																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Total																				
																				11118

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Underground Power Lines																				
	Structure's Demolition Cost																				
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	<b>Subtotal</b>																				
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	<b>Total</b>																				left in place

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area Volume	Weight Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Water Treatment Plant																		
	Structure's Demolition Cost	Steel Bld. Large	024116130020	0.28/CF	CF					1800						1800 CF		594	
	Structure's Vol. Demolished															20 CY			
	Rubble's Weight (exclude steel)																		
	Truck's Capacity																		
	Haulage																		
	Transportation Cost Non Steel Truck																		
	Transportation Cost Non Steel Drive																		
	Disposal Cost Non Steel																		
	Steel's Weight																		
	Truck's Capacity																		
	Haulage																		
	Transportation Cost Steel Truck	Transportation to Nielsens Dump	Scamp	13.63/Ton	Ton													68	
	Transportation Cost Steel Truck Drive																		
	Disposal Cost Steel	Nielsens Construction	Nielsens	7.00/TON	TON							430						35	
	<b>Subtotal</b>																	<b>807</b>	
	Equipment's Disposal Cost																		
	Dismantling Cost	3000 gal. to 5000 gal. tank	026510300110	484.43 Ea.	Ea.													484	
	Equipment's Vol. Demolished																		
	Loading Costs																		
	Transport Costs																		
	Disposal Costs	3000 gal. to 5000 gal. tank	026510301023	719.96 Ea.	Ea.													120	
	<b>Subtotal</b>																	<b>120</b>	
	Concrete Demolition																		
	Demolition Cost	Concrete demolition	024116170440	6.93 /CY	CY	15	15	0.5										21	
	Concrete's Vol. Demolished																		
	Loading and trucking Cost	Loading and Trucking	024116193080	19.37 /CY	CY										1.3			27	
	Transportation Cost																	0	
	Disposal Costs	On site disposal	024116174200	9.54 /CY	CY													48	
	<b>Subtotal</b>																	<b>172</b>	
	Concrete Demolition																		
	Demolition Cost																		
	Concrete's Vol. Demolished																		
	Loading Cost																		
	Transportation Cost																		
	Disposal Costs																		
	<b>Subtotal</b>																		
	Concrete Demolition																		
	Demolition Cost																		
	Concrete's Vol. Demolished																		
	Loading Cost																		
	Transportation Cost																		
	Disposal Costs																		
	<b>Subtotal</b>																		
	<b>Total</b>																	<b>1983</b>	

Description Ref.	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Potable Water Tank																				
Structure's Demolition Cost	Steel Bld. Large	024116130020	0.28	IOF			20	15							FT		3554	CF	550	
Structure's Vol. Demolished																				
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck																				
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel																				
Subtotal	Nielsons Construction	Nielsons	7.00	TON									480		lb/cf					1176
Equipment's Disposal Cost																				
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.63		15	15	0.5								FT					27
Concrete's Vol. Demolished																				0
Loading and trucking Cost																				0
Transportation Cost	Loading and Trucking	024116193060	19.37																	97
Disposal Costs																				0
Subtotal	On site disposal	024116174200	9.54																	45
Concrete Demolition																				172
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Total																				1348

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Process Water Tank	Steel Bld. Large	024116130020	0.28 /CF	CF	20	15									FT	0.3	3534	CF	870	
Structure's Demolition Cost																				
Structure's Vol. Demolished																				
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck			13.63 /Ton	Ton																123
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel																				
Subtotal	Nielsons Construction	Nielsons	7.00 /TON	TON									480		lb/cf					63
Equipment's Disposal Cost																				1176
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.63 /BCY	BCY	15	15	0.5								FT					37
Concrete's Vol. Demolished																				
Loading and Trucking Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal	On site disposal	024116174200	9.54 /LCY	LCY																
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Total																				1345

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter/Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost		
	Sewer Tank																				
	Structure's Demolition Cost																				
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	<b>Subtotal</b>																				
	Equipment's Disposal Cost																				
	Remove Tank	3000 gal. to 5000 gal. tank	026510300110	484.43	Ea										1 EA					484	
	Remove Sludge	3000 gal. to 5000 gal. tank	026510300300	227.23	Ea										1 EA					227	
	Disposal Costs	3000 gal. to 5000 gal. tank	026510301023	719.95	Ea										1 EA					720	
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	<b>Total</b>																				1431

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Items	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Drain Field																				
	Structure's Demolition Cost	will remain in place at reclamation																			
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	Subtotal																				
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Total																				

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Ventilation Fan																				
	Structure's Demolition Cost																				
	Structure's Vol. Demolished																				
	Robble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non-Steel Truck																				
	Transportation Cost Non-Steel Drive																				
	Disposal Cost Non-Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	<b>Subtotal</b>																				
	Equipment's Disposal Cost	Mechanical equipment heavy	15055 300 3600	641.65 /ton	ton							10				4	ton				25695
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				25666
	<b>Subtotal</b>																				
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs	Helicopter	15435603550	2600 \$ /HR	HR										10	HR					26000
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost	Concrete demolition	024116170440	6.53 /BCY	BCY	20	20	0.5													
	Concrete's Vol. Demolished																				
	Loading and trucking Cost																				
	Transportation Cost	Loading and Trucking	024119193060	19.37 /LCY	LCY																
	Disposal Costs	On site disposal	024116174200	9.54 /LCY	LCY																
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	<b>Total</b>																				51077

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Conveyor Tunnels to Coal Stockpile																				
Structure's Demolition Cost	Steel Bld. Large	024116130020	0.28 /CF	ICF	810	6	20								FT		87200	CF	27216	
Structure's Vol. Demolished																	0.3	1280	CY	
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck																				
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel																				
<b>Subtotal</b>		Nielsons Construction											480		lb/cf				1813	32599
Equipment's Disposal Cost																				
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.63 /BCY	BCY						15							15	CV	99	
Concrete's Vol. Demolished																	1.3	20	CV	
Loading and trucking Cost	Loading and Trucking	024119180080	19.37 /LCY	LCY														20	CV	
Transportation Cost																		20	CV	
Disposal Costs																		20	CV	
<b>Subtotal</b>	On site disposal	024116174200	6.64 /LCY	LCY														20	CV	131
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				
<b>Total</b>																				33286

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Conveyor ROM Stockpile to Crusher																				
	Structure's Demolition Cost	Steel Bld. Large	024116130020	0.28/DCF	DCF	675	5	10								FT	0.3	33750	CF	8450	
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck	Transportation to Nielsons Dump	Scamp	13.93/TON	TON																
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	Subtotal	Nielsons Construction	Nielsons	7.00	TON									480		lb/cf		50150		530	11807
	Equipment's Disposal Cost																				
	Disposal Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost	Concrete demolition	024116170440	6.63/BCY	BCY						15							15	15	99	
	Concrete's Vol. Demolished																				
	Loading and Trucking Cost	Loading and Trucking	024119193080	19.37/LCY	LCY													1.3	20	387	
	Transportation Cost																				
	Disposal Costs	On site disposal	024116174200	9.54/LCY	LCY																
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Total																				11884

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Conveyor Crusher to Loudout Bin																				
	Structure's Demolition Cost	Steel Bld. Large	024116130020	0.28 /CF		230	5	20									0.3	33000 /CF		5440	
	Structure's Vol. Demolished																	156 /CY			
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	Subtotal	Nielson's Construction	Nielson's	7.00 /TON										480						61100	421
	Equipment's Disposal Cost.																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost	Concrete demolition	024116170440	6.63 /BCY							15										
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost	Concrete's Vol. Demolished	024116193080	19.37 /LCY																	
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost	On site disposal	024116174200	9.54 /LCY																	
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Total																				

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Conveyor Layout Bin Truck Layout	Steel Bld. Large	024116130020	0.25/ICF	ICF	5	5	20								FT	0.3	150	6'0"		
Structure's Demolition Cost																				
Structure's Vol. Demolished																				
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck	Transportation to Nielsons Dump	Scamp	13.63/TON	TON																
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel	Nielsons Construction	Nielsons	7.00/TON	TON																
<b>Subtotal</b>																				
<b>Equipment's Disposal Cost</b>																				
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost	Concrete demolition	024116170440	6.63/BCY	BCY						15										
Concrete's Vol. Demolished																				
Loading and Trucking Cost	Loading and Trucking	024119193080	19.37/ICY	ICY																
Transportation Cost																				
Disposal Costs	On site disposal	024118174200	9.54/ICY	ICY																
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				
<b>Total</b>																				

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Reclaim Escape Tunnel Fan Fan House	Steel Bld. Large	024116130020	0.26 /CF	CF					26680								26680	CF	7556	
Currgated Steel	Steel Bld. Large	024116130020	0.28 /CF	CF					1257								1257	CF	352	
Escape Tunnel	Steel Bld. Large	024116130020	0.28 /CF	CF					84								84	CF	18	
Fan	Steel Bld. Large	024116130020	0.28 /CF	CF					512								512	CF	143	
Fan House	Structure's Vol. Demolished	024116130020	0.28 /CF	CF												0.3	319	CF		
Structure's Vol. Demolished	Rubble's Weight (exclude steel)																			
Rubble's Weight (exclude steel)	Truck's Capacity																			
Truck's Capacity	Haulage																			
Haulage	Transportation Cost Non Steel Truck																			
Transportation Cost Non Steel Truck	Transportation Cost Non Steel Drive																			
Transportation Cost Non Steel Drive	Disposal Cost Non Steel																			
Disposal Cost Non Steel	Steel's Weight																			
Steel's Weight	Truck's Capacity																			
Truck's Capacity	Haulage																			
Haulage	Transportation to Nielsons Dump	Scamp	13.63 /Ton	Ton																
Transportation Cost Steel Truck	Transportation Cost Steel Truck Drive																			
Transportation Cost Steel Truck Drive	Disposal Cost Steel	Nielsons Construction	7.00 /TON	TON																
Disposal Cost Steel	Subtotal	Nielsons											480						539	
Subtotal	Excavation and Backfill																		9628	
Excavation and Backfill	Reclaim Tunnel	312316420280	1.71 /CY	CY	380	14	10											1815	CY	3104
Reclaim Tunnel	Backfill Trench 1CY	312316133020	1.92 /CY	CY														1815	CY	5435
Backfill Trench 1CY	Excavation bulk bank 2CY	312316420280	1.71 /CY	CY	325	4	10											481	CY	833
Excavation bulk bank 2CY	Backfill Trench 1CY	312316133020	1.92 /CY	CY														481	CY	924
Backfill Trench 1CY	Subtotal																			8336
Subtotal	Concrete Demolition																			
Concrete Demolition	Demolition Cost	024116170400	6.63 /BCY	BCY						20								30	CY	133
Demolition Cost	Concrete's Vol. Demolished																	30	CY	133
Concrete's Vol. Demolished	Loading and Trucking Cost	024119193080	19.37 /LCY	LCY														1.3		504
Loading and Trucking Cost	Transportation Cost																			504
Transportation Cost	Disposal Costs																			0
Disposal Costs	Subtotal	024116174200	9.54 /LCY	LCY																248
Subtotal	Concrete Demolition																			885
Concrete Demolition	Demolition Cost																			
Demolition Cost	Concrete's Vol. Demolished																			
Concrete's Vol. Demolished	Loading Cost																			
Loading Cost	Transportation Cost																			
Transportation Cost	Disposal Costs																			
Disposal Costs	Subtotal																			
Subtotal	Concrete Demolition																			
Concrete Demolition	Demolition Cost																			
Demolition Cost	Concrete's Vol. Demolished																			
Concrete's Vol. Demolished	Loading Cost																			
Loading Cost	Transportation Cost																			
Transportation Cost	Disposal Costs																			
Disposal Costs	Subtotal																			
Subtotal	Total																			12949
Total																				12949

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Conveyer/Storage/Pile/Stacking/Tube																				
	Structure's Demolition Cost	Steel Bld. Large	024116130020	0.23	/CF			80	20							PF		25133	CF	7037	
	Structure's Vol. Demolished																	0.3	279	CY	
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck	Transportation to Nielsons Dump	Scamp	13.53	/TON																513
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel	Nielsons Construction	Nielsons	7.00	/TON																459
	<b>Subtotal</b>																				<b>8418</b>
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost	Concrete demolition	024116170440	6.53	/BCY	25	25	3								PF	1.3	90	CY	457	
	Concrete's Vol. Demolished																				
	Loading and trucking Cost	Loading and Trucking	024116193080	19.37	/LCY																1743
	Transportation Cost																				
	Disposal Costs	On site disposal	024116174200	9.54	/LCY																859
	<b>Subtotal</b>																				<b>3059</b>
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	Transportation Cost																				
	Disposal Costs																				
	<b>Subtotal</b>																				
	<b>Total</b>																				<b>11478</b>

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swall Factor	Quantity	Unit	Cost	
	Crusher Screen Plant																				
	Structure's Demolition Cost	Steel Bld, Large	024119130920	0.28 /CF	CF						12000						0.3	12000	CF	3360	
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	Subtotal	Nielsons Construction	Nielsons	7.00 /TON	TON								480								224
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost	Concrete demolition	024116170440	6.63 /BCY	BCY							20									133
	Concrete's Vol. Demolished																				
	Loading and Trucking Cost	Concrete's Vol. Demolished	024119193980	19.37 /LCY	LCY																524
	Transportation Cost	On site disposal	024116174200	9.54 /LCY	LCY																248
	Disposal Costs																				
	Subtotal																				865
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Total																				4935



Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter/ Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Coal Storage Bin	Steel Bld. Large	024116130020	0.23	CF					10000					CF	0.3	10000	CF	2300	
	Structure's Vol. Demolished																			
	Rubble's Weight (exclude steel)																			
	Truck's Capacity																			
	Haulage																			
	Transportation Cost Non Steel Truck																			
	Transportation Cost Non Steel Drive																			
	Disposal Cost Non Steel																			
	Steel's Weight																			
	Truck's Capacity																			
	Haulage																			
	Transportation Cost Steel Truck	Transportation to Nielsons Dump	Scamp	13.63	Ton															355
	Transportation Cost Steel Truck Drive																			
	Disposal Cost Steel	Nielsons Construction	Nielsons	7.00	TON										lb/cf					153
	<b>Subtotal</b>												480							3357
	<b>Equipment's Disposal Cost</b>																			
	Dismantling Cost																			
	Equipment's Vol. Demolished																			
	Loading Costs																			
	Transport Costs																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	Concrete Demolition																			
	Demolition Cost	Concrete demolition	024116170440	6.63	BCY					15										95
	Concrete's Vol. Demolished																			
	Loading and Trucking Cost	Loading and Trucking	024116190080	19.37	ILCY															387
	Transportation Cost																			
	Disposal Costs	On site disposal	024116174200	9.54	ILCY															191
	<b>Subtotal</b>																			677
	Concrete Demolition																			
	Demolition Cost																			
	Concrete's Vol. Demolished																			
	Loading Cost																			
	Transportation Cost																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	Concrete Demolition																			
	Demolition Cost																			
	Concrete's Vol. Demolished																			
	Loading Cost																			
	Transportation Cost																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	Concrete Demolition																			
	Demolition Cost																			
	Concrete's Vol. Demolished																			
	Loading Cost																			
	Transportation Cost																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	<b>Total</b>																			4002

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity Unit	Cost
	Guard Rail	Guard Rail corrugated steel	024113200100	2.53	LF	1520												1520 FT	3825
	Structure's Demolition Cost	End Sections	024113200200	37.56	Each													3	333.65
	Rubble's Weight (exclude steel)																		
	Truck's Capacity																		
	Haulage																		
	Transportation Cost Non Steel Truck																		
	Transportation Cost Non Steel Drive																		
	Disposal Cost Non Steel																		
	Steel's Weight																		
	Truck's Capacity																		
	Haulage																		
	Transportation Cost Steel Truck																		
	Transportation Cost Steel Truck Drive																		
	Disposal Cost Steel																		
	<b>Subtotal</b>																		4149.55
	Equipment's Disposal Cost																		
	Dismantling Cost																		
	Equipment's Vol. Demolished																		
	Loading Costs																		
	Transport Costs																		
	Disposal Costs																		
	<b>Subtotal</b>																		
	Concrete Demolition																		
	Demolition Cost																		
	Concrete's Vol. Demolished																		
	Loading Cost																		
	Transportation Cost																		
	Disposal Costs																		
	<b>Subtotal</b>																		
	Concrete Demolition																		
	Demolition Cost																		
	Concrete's Vol. Demolished																		
	Loading Cost																		
	Transportation Cost																		
	Disposal Costs																		
	<b>Subtotal</b>																		
	<b>Total</b>																		4149.55

Post removal is in the linear foot calculation

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swall Factor	Quantity	Unit	Cost	
	Underground Pipes	will remain in place at reclamation																			
	Structure's Demolition Cost																				
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	Subtotal																				
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Disposal Cost																				
	Transportation Cost																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Subtotal																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Total																				Left in Place

Description	Materials	Mears Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Chain Link Fence																				
Structure & Demolition Cost - 1995 format	Chain link remove 8'-10'	024115601700	3.41 /LF	1500													1500 FT		5115	
Structure's Vol, Demolished																				
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck																				
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck																				
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel																				
<b>Subtotal</b>																				<b>5115</b>
Equipment's Disposal Cost																				
Dismanling Cost																				
Equipment's Vol, Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol, Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol, Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
<b>Subtotal</b>																				
<b>Total</b>																				<b>5115</b>



Ref.	Description	Materials	Means Reference Number	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Office Bathroom Warehouse Parking																			
	Structure's Demolition Cost																			
	Structure's Vol. Demolished																			
	Rubble's Weight (exclude steel)																			
	Truck's Capacity																			
	Haulage																			
	Transportation Cost Non Steel Truck																			
	Transportation Cost Non Steel Drive																			
	Disposal Cost Non Steel																			
	Steel's Weight																			
	Truck's Capacity																			
	Haulage																			
	Transportation Cost Steel Truck																			
	Transportation Cost Steel Truck Drive																			
	Disposal Cost Steel																			
	<b>Subtotal</b>																			
	Equipment's Disposal Cost																			
	Dismantling Cost																			
	Equipment's Vol. Demolished																			
	Loading Costs																			
	Transport Costs																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	Equipment's Disposal Cost																			
	Dismantling Cost																			
	Equipment's Vol. Demolished																			
	Loading Costs																			
	Transport Costs																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	Office Area																			
	Asphalt Demolition																			
	Demolition Cost																			
	Asphalt's Vol. Demolished																			
	Loading Cost																			
	Transportation Cost																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	Equipment's Disposal Cost																			
	Dismantling Cost																			
	Equipment's Vol. Demolished																			
	Loading Costs																			
	Transport Costs																			
	Disposal Costs																			
	<b>Subtotal</b>																			
	<b>Total</b>																			

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Steel Factor	Quantity	Unit	Cost	
	Mine Parking																				
	Structure's Demolition Cost																				
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Disposal Cost Non Steel																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	Subtotal																				
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Equipment's Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Parking Lot																				
	Asphalt Demolition																				
	Demolition Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Pavement Removal 4-6"																				
	Transportation to Nielsens Dump																				
	Nielsens Construction																				
	Subtotal																				
	Total																				

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost		
	Fuel Tanks																					
	Structure's Demolition Cost																					
	Structure's Vol. Demolished																					
	Rubble's Weight (exclude steel)																					
	Truck's Capacity																					
	Haulage																					
	Transportation Cost Non Steel Truck																					
	Transportation Cost Non Steel Drive																					
	Disposal Cost Non Steel																					
	Steel's Weight																					
	Truck's Capacity																					
	Haulage																					
	Transportation Cost Steel Truck																					
	Transportation Cost Steel Truck Drive																					
	Disposal Cost Steel																					
	<b>Subtotal</b>																					
	Equipment's Disposal Cost																					
	Removal Tanks	3000 gal. to 5000 gal. tank	026510301023	719.96 Ea.	Ea.																2150	
	Remove sludge water products	3000 gal. to 5000 gal. tank	026510300300	227.22 Ea.	Ea.																552	
	Haul tank recycle center																				0	
	Transport Costs																					
	Disposal Costs																					
	<b>Subtotal</b>																					2842
	Concrete Demolition																					
	Demolition Cost																					
	Concrete's Vol. Demolished																					
	Loading Cost																					
	Transportation Cost																					
	Disposal Costs																					
	<b>Subtotal</b>																					
	Concrete Demolition																					
	Demolition Cost																					
	Concrete's Vol. Demolished																					
	Loading Cost																					
	Transportation Cost																					
	Disposal Costs																					
	<b>Subtotal</b>																					
	<b>Total</b>																					2842

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swall Factor	Quantity	Unit	Cost	
	Powder and Cap Magazine																				
	Structure's Demolition Cost																				
	Structure's Vol. Demolished																				
	Rubble's Weight (exclude steel)																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Non Steel Truck																				
	Transportation Cost Non Steel Drive																				
	Steel's Weight																				
	Truck's Capacity																				
	Haulage																				
	Transportation Cost Steel Truck																				
	Transportation Cost Steel Truck Drive																				
	Disposal Cost Steel																				
	Subtotal																				
	Equipment & Disposal Cost																				
	Dismantling Cost																				
	Equipment's Vol. Demolished																				
	Loading Costs																				
	Transport Costs																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Concrete Demolition																				
	Demolition Cost																				
	Concrete's Vol. Demolished																				
	Loading Cost																				
	Transportation Cost																				
	Disposal Costs																				
	Subtotal																				
	Total																				

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost					
	Culverts																								
DC-5	Excavation Bulk Bank 2 CY (322E)		312316420260	1.71	ICY		50	1.5													8 CY	14			
DC-5	Backfill Trench Minimal Haul 2 1/4		312316133020	1.92	ICY		50	1.5														8 CY	14		
DC-6	Excavation Bulk Bank 2 CY (322E)		312316420260	1.71	ICY		80	2														18 CY	31		
DC-6	Backfill Trench Minimal Haul 2 1/4		312316133020	1.92	ICY		80	2														18 CY	31		
DC-7	Excavation Bulk Bank 2 CY (322E)		312316420260	1.71	ICY		110	2														24 CY	41		
DC-7	Backfill Trench Minimal Haul 2 1/4		312316133020	1.92	ICY		110	2														24 CY	41		
DC-8	Excavation Bulk Bank 2 CY (322E)		312316420260	1.71	ICY		85	1.5														14 CY	24		
DC-8	Backfill Trench Minimal Haul 2 1/4		312316133020	1.92	ICY		85	1.5														14 CY	24		
DC-9	Excavation Bulk Bank 2 CY (322E)		312316420260	1.71	ICY		40	1.5														7 CY	12		
DC-9	Backfill Trench Minimal Haul 2 1/4		312316133020	1.92	ICY		40	1.5														7 CY	12		
UC-1	Excavation Bulk Bank 2 CY (322E)		312316420260	1.71	ICY		480	5														533 CY	911		
UC-1	Backfill Trench Minimal Haul 2 1/4		312316133020	1.92	ICY		480	5														533 CY	1023		
	<b>Subtotal</b>																						<b>2192</b>		
	Equipment's Disposal Cost																								
	Dismantling Cost																								
	Equipment's Vol. Demolished																								
	Loading Costs																								
	Transport Costs																								
	Disposal Costs																								
	<b>Subtotal</b>																								
	Concrete Demolition																								
	Demolition Cost	36" CMP (5)	024113400160	11.98	LF		365																365	4373	
	Demolition Cost	72" CMP (1)	024113400200	38.15	LF		480																	480	18312
	Loading Cost																								
	Transportation Cost																								
	Disposal Costs																								
	<b>Subtotal</b>																								
	Concrete Demolition																								
	Demolition Cost																								
	Concrete's Vol. Demolished																								
	Loading Cost																								
	Transportation Cost																								
	Disposal Costs																								
	<b>Subtotal</b>																								
	Concrete Demolition																								
	Demolition Cost																								
	Concrete's Vol. Demolished																								
	Loading Cost																								
	Transportation Cost																								
	Disposal Costs																								
	<b>Subtotal</b>																								
	Concrete Demolition																								
	Demolition Cost																								
	Concrete's Vol. Demolished																								
	Loading Cost																								
	Transportation Cost																								
	Disposal Costs																								
	<b>Subtotal</b>																								
	<b>Total</b>																							<b>13534</b>	

Ref.	Description	Materials	Means Reference Number	Unit Cost	Unit	Quantity	Unit	Cost
	Lila Old Fan Portals							
	Structure's Demolition Cost	Old Horse Canyon Lila Fan Portal Seal Lila North and South Portals		3000 5700	2 5			5,000 28,500
	<b>Total</b>				<b>7</b>			<b>33,500</b>

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost		
Pole Barn																					
Structure's Demolition Cost	Steel Bld. Large	024116130020	0.28 /CF		50	30	10								FT		15000 CF		4200		
Structure's Vol. Demolished																					
Rubble's Weight (exclude steel)																					
Trucks Capacity																					
Haulage																					
Transportation Cost Non Steel Truck																					
Transportation Cost Non Steel Drive																					
Disposal Cost Non Steel																					
Steel's Weight																					
Truck's Capacity																					
Haulage																					
Transportation Cost Steel Truck	Transportation to Nielsens Dump	Scamp	13.63 /Ton																	545	
Transportation Cost Steel Truck Drive																					
Disposal Cost Steel	Nielsens Construction	Nielsens	7.00 /TON																	480	
Subtotal																				5025	
Equipment's Disposal Cost																					
Dismantering Cost																					
Equipment's Vol. Demolished																					
Loading Costs																					
Transport Costs																					
Disposal Costs																					
Subtotal																					
Concrete Demolition																					
Demolition Cost	Concrete demolition	024116170440	6.63 /BCY		50	30	0.25								FT					93	
Concrete's Vol. Demolished																					
Loading and trucking Cost																					
Transportation Cost	Loading and Trucking	024119195000	19.37 /LCY																		348
Disposal Costs	On site disposal	024116174200	9.54 /LCY																		172
Subtotal																					614
Concrete Demolition																					
Demolition Cost																					
Concrete's Vol. Demolished																					
Loading Cost																					
Transportation Cost																					
Disposal Costs																					
Subtotal																					
Concrete Demolition																					
Demolition Cost																					
Concrete's Vol. Demolished																					
Loading Cost																					
Transportation Cost																					
Disposal Costs																					
Subtotal																					
Total																					5639

Description	Materials	Means Reference Number	Unit Cost	Unit	Length	Width	Height	Diameter	Area	Volume In Gallons	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
Rock Dust Silo																				
Structure's Demolition Cost			1344.4	Each			40	11	1572	28434					Each		1	Each	1344	
Structure's Vol. Demolished																				
Rubble's Weight (exclude steel)																				
Truck's Capacity																				
Haulage																				
Transportation Cost Non Steel Truck				135	hr															
Transportation Cost Non Steel Drive																				
Disposal Cost Non Steel																				
Steel's Weight																				
Truck's Capacity																				
Haulage																				
Transportation Cost Steel Truck																				
Transportation Cost Steel Truck Drive																				
Disposal Cost Steel																				
Subtotal																				1749
Equipment's Disposal Cost																				
Dismantling Cost																				
Equipment's Vol. Demolished																				
Loading Costs																				
Transport Costs																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost			6.63	/CY	15.5		15.5	1		240										59
Concrete's Vol. Demolished																				
Loading and trucking Cost			19.37	/LCY																224
Transportation Cost																				
Disposal Costs			9.54	/LCY						9										110
Subtotal																				393
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Concrete Demolition																				
Demolition Cost																				
Concrete's Vol. Demolished																				
Loading Cost																				
Transportation Cost																				
Disposal Costs																				
Subtotal																				
Total																				2142




	Means Number	Per Day Equipment Rent Cost	Hourly Operating Costs	Equipment Overhead	Operators Hourly Wage Rate	Hourly Cost	Number of Men or Eq.	Total Eq. & Lab. Costs	Units	Quantity	Production Rate	Units	Equip. ~ Labor Time/Drs.	Units	Cost
<b>Horse Canyon Mine Life Canyon Project</b>															
Grading															
Load and Haul Backfill Material															
Screener 631E	015433203700	2197.65	132.68	0.1	60.45	330.48	3	991.45 \$/HR		28978 CY	393 CY/HR		73.6 HR		15371
D9R	015433204350	2173.50	130.36	0.1	60.45	326.55	1	326.55 \$/HR					73.6 HR		24971
Subtotal															97712
<b>Spread and Compact Material</b>															
D9R	015433204360	2173.50	130.36	0.1	60.45	326.55	1	326.55 \$/HR					73.6 HR		24241
Compactor 825B	015433201200	180.00	6.76	0.1	58.20	76.84	1	76.84 \$/HR					73.6 HR		4555
Subtotal															24696
<b>Upper Road Area</b>															
Cat 769 D off road truck 40 Ton	015433205810	1569.75	99.40	0.1	48.30	167.71	1	167.71 \$/HR		5000 CY	288 CY/HR		17.3 HR		2901
888 Loader 8CY	015433204810	1738.80	111.70	0.1	60.45	187.00	4	748 \$/HR					17.3 HR		1560
CAT 325BL (10-21)(2nd604)	015433200320	1497.30	109.53	0.1	48.30	120.87	1	120.87 \$/HR					17.3 HR		1561
D9R	015433204360	2173.50	130.36	0.1	60.45	267.11	1	267.11 \$/HR		5000	128 CY/HR		41.7 HR		1113
Subtotal															4325
<b>Total</b>															188523

	Means Number	Equipment Cost	Hourly Operating Costs	Equipment Overhead	Operator's Hourly Wage Rate	Hourly Cost	Number of Men or Eq.	Total Ec. & Lab. Costs	Units	Quantity	Units	Production Rate	Units	Equip. - Labor Time/Drs	Units	Cost
Horse Canyon Mine Lila Canyon Project																
Grading																
Lead and Haul Topsoil	015433203700	2197.65	132.88	0.1	60.45	330.48	3	991.45 \$/HR		55000 CY		395 CY/HR		142.5 HR		141727
637E Scraper	015433204360	2173.50	130.36	0.1	60.45	326.65	1	326.65 \$/HR						142.5 HR		46543
Subtotal																187752
Cat 769 D off road truck																
988 Loader	015433205610	1569.75	99.40	0.1	48.30	167.71	1	167.71 \$/HR		10000 CY		285 CY/HR		34.6 HR		5403
CAT 325BL (10-21)(2nd04)	015433204810	1738.20	111.70	0.1	60.45	197.00	4	743 \$/HR						34.6 HR		25281
Subtotal	015433200320	1487.20	105.63	0.1	48.30	120.61	1	120.61 \$/HR						34.6 HR		4175
Subtotal																35552
<b>Total</b>																<b>222682</b>

	Means Number	Rent/Day Equipment Cost	Hourly Operating Costs	Equipment Overhead	Operator's Hourly Wage Rate	Hourly Cost	Number of Men or Eq.	Total Eq. & Lab. Costs	Units	Quantity	Units	Production Rate	Units	Equip. + Labor Time/Ds.	Units	Cost
Horse Canyon Mine Life Cycle Project																
Grading																
2 1/2 million water truck	015433406950	763.14	86.12	0.1	47.05	130.81	1	130.81 \$/HR						384.2	HR	5946.2
Pickup Truck Crew 4x4 1 ton (20-17) (2N04)	015433407200	71.00	14.68	0.1	53.15	62.27	1	62.27 \$/HR						384.2	HR	3184.2
Foreman Average, Outside						0	1	0 \$/HR								1212.0
<b>Total</b>																<b>10152.2</b>

Ref.	Description	Materials	Means Reference Number	Unit	Length	Width	Height	Diameter	Area	Volume	Weight	Density	Time	Number	Unit	Swell Factor	Quantity	Unit	Cost	
	Vegetation																			
	Soil Preparation																			
	Soil Prep 5' deep 95-96 Sec. 553.230																			
	Soil to be used																			
	Grading/Prep																			
	Grass 3.0 CY/AC																			
	Track Hoe 3 CY = 280CY/HR																			
	Subtotal																			
	Seeding																			
	Fertilizer Material																			
	Fertilizer Material																			
	Seeding Materials																			
	Seeding Materials																			
	Seeding Materials																			
	Seeding Materials																			
	Seeding Application																			
	Mulch Application																			
	Mulch Application																			
	Subtotal																			
	Reseeding																			
	Assume 50% reseeding rate																			
	Subtotal																			
	Total																			




RECEIVED  
 NOV 2 2013  
 DIV. OF OIL, GAS & MINING

**LILA CANYON MINE**  
 DISTURBED AREA MAP  
 DATE: SEPTEMBER 2000  
 SCALE: AS SHOWN  
 SHEET NO.: 1-2



REVISION DATE:

DATE	BY	DESCRIPTION
JAN 2008	RJM	
NOV. 2013	PJJ	




R 14 E, T 16 S

**LEGEND:**

- NATURAL DRAINAGE: (blue dashed line)
- DISTURBED AREA BOUNDARY: (pink dashed line)
- UNDISTURBED AREA BOUNDARY: (green hatched area)

G:\Current Drawings\889 Map\11-2013\Plan-2 16-001 11-20-13.dwg, Newk, 11/20/2013 9:11:48 AM



RECEIVED  
 NOV 22 2013  
 DIV. OF OIL, GAS & MINING


Section 15  
 Section 22

- LEGEND:**
- ⊙ Soil Description Sites
  - Soil Transects
  - Disturbed Area Boundary
  - Contour Interval: 5 feet
  - Contour Interval: 25 feet

- SOIL MAP UNITS:**
- SBG: Strych Bouldery fine sandy loam, 5 to 15 percent slopes (grass)
  - VBJ: Strych Very bouldery fine sandy loam, 5 to 15 percent slopes (pinyon - juniper)
  - XBS: Strych Extremely bouldery sandy loam, 10 to 45 percent slopes
  - DSH: Strych Fine sandy loam variant, 3 to 8 percent slopes
  - RBL: Rubbeland-Strych-Gerst Complex, 20 to 70 percent slopes
  - RBT: Rockland-Travessilla Complex



R 14 E, T 16 S



REVISION DATE:

DATE	BY	REASON
Jan 2008	RAM	
Dec 2010	RAM	
Nov. 2013	PAJ	

**LILA CANYON MINE**  
**DETAILED SOILS MAP OF THE MINE FACILITIES SITE**


DATE: **JULY 1999**      DESIGNED BY:

SCALE: **AS SHOWN**      **E.I.S.**

PLATE: **PLATE 2 - 2**

Cartography by: Kalla McDonald / Alyson Traffante  
 Base Map: Blackhawk Engineering

G:\Current Drawings\Map\Map\Map\Lila Canyon\11-2013\Plate 2-2\_10-010 11-20-13.dwg, Model, 11/21/2013 8:09:16 AM



RECEIVED  
 NOV 22 2013  
 DIV. OF OIL, GAS & MINING

Section 15  
 Section 22

**LEGEND:**

SOIL DESCRIPTION SITE

COAL MINE WASTE

DISTURBED AREA BOUNDARY

UNDISTURBED AREA BOUNDARY

TOPSOIL BERM

Amount of Topsoil Removed, Stored and Replaced

SBG 18"	28100 YD3	
RBL 8"	2340 YD3	
VBJ 18"	8227 YD3	
XBS 12"	14207 YD3	
DSH 18"	2809 YD3	
<b>TOTAL</b>	<b>55683 YD3</b>	

**SUBSOIL CUT & FILL:**

SBG: Strych Bouldery fine sandy loam, 5 to 15 percent slopes (grass)	AVERAGE VOLUME CUBIC YDS: CUT; 14,076 YD3, FILL 17,338 YD3
VBJ: Strych Very bouldery fine sandy loam, 5 to 15 percent slopes (pinon - juniper)	AVERAGE VOLUME CUBIC YDS: CUT; 2,662 YD3, FILL 3,492 YD3
XBS: Strych Extremely bouldery sandy loam, 10 to 45 percent slopes	AVERAGE VOLUME CUBIC YDS: CUT; 1,067 YD3, FILL 487 YD3
DSH: Strych Fine sandy loam variant, 3 to 8 percent slopes	AVERAGE VOLUME CUBIC YDS: CUT; 643 YD3

**REVISION DATE:**

DATE:	BY:	DATE:	BY:
2/4/08	RJM		
12/28/09	RJM		
12/08/10	RJM		
11/20/13	PJJ		

UTAH REGISTERED PROFESSIONAL ENGINEER

R. Jay Marshall  
 #12606  
 11/20/13

T16S, R14E

**LILA CANYON MINE**

Soil Salvage and Replacement

NOVEMBER 1999


SCALE: AS SHOWN

PLATE: 2-3

DESIGNED BY: UEI

G:\Current Drawings\MP Maps\Lila Canyon\11-2013\Plate 2-3\_10-010 11-20-13.dwg, Model: 11/21/2013 6:05:48 AM

# BLM R.O.W. #UTU-77122



**LILA CANYON MINE**

RECEIVED  
NOV 2 2013  
DIV. OF OIL GAS & MINING

**SURFACE AREA**  
Official Disturbed Boundary Map

DATE: January 2008  
DESIGNED BY: R. Jay Marshall  
SCALE: AS SHOWN  
PAGE # 5-2


RECEIVED  
NOV 2 2013  
DIV. OF OIL GAS & MINING

REGISTERED PROFESSIONAL ENGINEER  
R. JAY MARSHALL  
STATE OF UTAH

NOTE: CONTROL POINT COORDINATE SYSTEM IS U.S. STATE PLANE 1983 - UTAH CENTRAL (4302) ADJUSTED TO SEA LEVEL.

REVISION DATE:

DATE	BY	REVISION
JAN 2008	RJM	PJJ
APR 2009	PJJ	PJJ
DEC 2009	PJJ	PJJ
AUGUST 2010	PJJ	PJJ
SEPT. 2010	PJJ	PJJ
APRIL 2011	PJJ	PJJ
MAY 2011	PJJ	PJJ



- Mine Facility List**
- Office/Bathroom
  - Shop Warehouse
  - Security Shack
  - Mine Substation
  - Underground Power Lines
  - Water Treatment Plant
  - Potable Water Tank
  - Process Water tank
  - Sewer Tank
  - Drain Field
  - Ventilatin Fan
  - 60" Conveyor Tunnels to Coal Stockpile
  - (ROM) Underground Belt from Stockpile to Crusher
  - 48" Conveyor from Crusher to Loadout Bin
  - Drop from Loadout Bin to Truck Loadout
  - Reclaim Tunnel, Escape Tunnel, Fan and Fan House
  - (ROM) Storage Pile, Coal Stacking Tube
  - Crusher Screen Plant
  - Truck Scale and Loadout
  - Coal Loadout Storage Bin
  - Quartrails
  - Underground Pipes
  - Chain Link Fence
  - Non-Coal Waste Area
  - Equipment & Supplies Storage Area
  - Topsoil Pile
  - Refuse Pile
  - Sediment Pond #1
  - Slope Access Road/Portal Access Road
  - Rock Slopes
  - Truck Loadout Road
  - Office/Bathroom/Warehouse Asphalt Parking Area
  - Mine Parking
  - Diesel Fuel Tanks with concrete containment
  - Powder and Cap Magazines
  - Containment Pond #2
  - Grounding Field

CONTROL POINT ALPHA  
NORTHING: 6,962,462.96  
EASTING: 1,964,465.17  
ELEVATION: 5961.37'


CONTROL POINT BETA  
SCATTERED BRUSH AND TREES  
NORTHING: 6,961,805.36  
EASTING: 1,966,344.01  
ELEVATION: 5859.34'

CONTROL POINT GAMMA  
NORTHING: 6,960,389.91  
EASTING: 1,965,487.50  
ELEVATION: 5914.05'

**LEGEND:**

- STRUCTURAL FILL: [Symbol]
- TEMP. REFUSE PILE (COAL MINE WASTE): [Symbol]
- UNDISTURBED WITHIN THE DISTURBED AREA: [Symbol]
- DISTURBED AREA BOUNDARY: [Symbol]
- NATURAL DRAINAGE: [Symbol]
- 6' HIGH CHAIN LINK FENCE: [Symbol]
- INCIDENTAL ROCK DISTRIBUTION: [Symbol]
- STREAM BUFFER ZONE SIGNS: [Symbol]
- TOPSOIL BERM: [Symbol]
- Stream Buffer Zone: [Symbol]
- TEMPORARY FACILITIES: [Symbol]
- TEMPORARY ROADWAYS: [Symbol]
- LEASE MODIFICATION: [Symbol]
- BLM R.O.W. BOUNDARY LINE: [Symbol]

NOTES:  
(1) REFER TO PLATE 5-7A&B FOR CROSS-SECTIONS.



RECEIVED  
NOV 2 2013  
DIV. OF OIL, GAS & MINING


LILA CANYON MINE  
POST MINING TOPOGRAPHY  
JUNE 1988  
AS SHOWN

DESIGNED BY: BLACKHAWK ENG.  
PAGE # 5-6



REVISION DATE:

DATE	BY	DATE	BY
JAN 2001	BJ	Dec 2010	RAM
February 2008	RJM	Nov. 2013	PLJ
MAR 2001	BJ		
NOV 2002	RJM		
AUG 2003	RJM		
DEC 2004	RJM		
JULY 2004	PLJ		




NOTES:

- REFER TO PLATES 5-7A-1, 5-7A-2, 5-7A-3, 5-7A-4, AND 5-7B-1, 5-7B-2, AND 5-7B-3 FOR CROSS SECTION INFORMATION.
- REFER TO PLATE 5-7C FOR RECLAIMED PROFILE INFORMATION.
- SILT FENCES WILL BE INSTALLED AS NEEDED.

LEGEND:

- NATURAL DRAINAGE: (dashed blue line)
- DISTURBED DRAINAGE: (dashed red line)
- DISTURBED AREA BOUNDARY: (dashed pink line)
- UNDISTURBED AREA BOUNDARY: (dashed green line)
- RECLAIMED PROFILE SECTION: (solid blue line)
- RECLAMATION CONTOURS: (dashed orange line)
- CONCRETE STORAGE: (hatched area)



Projected Coal Outcrop

Rock Slopes

A.S.C.A. Disturbed

FINAL RECLAMATION CONCRETE STORAGE AREA

A.S.C.A. Disturbed


Existing County Road

Topsoil Storage Area

Portion of UC-1 Beneath County Road Will be Installed by the County and Left in Place After Reclamation







RECEIVED  
NOV 2 2013  
DIV. OF OIL, GAS & MINING



**LILA CANYON MINE**  
**POST MINING HYDROLOGY**  
 Phase I Bond Release

DATE: JUNE 1998  
 DRAWN BY: BLACKHAWK ENG.  
 SCALE: AS SHOWN  
 PAGE #: 7-7



REVISION DATE:

DATE	BY	DATE	BY
JAN 1999	WJ	Dec 2010	RJM
NOV 1999	BHE	Nov. 2013	PJU
SEP 2000	BHE		
MAR 2001	BJ		
NOV 2002	RJM		
NOV 2003	RJM		
JAN 2005	RJM		



R 14 E, T 16 S

Existing County Road

Topsoil Storage Area

Portion of UC-1 beneath County Road to be left in place.

NOTE:  
Sediment Pond, RD-1, RD-2, and Upper Portion UC-1 to be removed upon Phase II/Bond release.

FINAL RECLAMATION CONCRETE STORAGE AREA

A.S.C.A. Disturbed

A.S.C.A. Disturbed

NOTE:  
SILT FENCES WILL BE INSTALLED AS NEEDED.

- LEGEND:
- NATURAL DRAINAGE: (dashed blue line)
  - DISTURBED DRAINAGE: (dashed red line)
  - DISTURBED AREA BOUNDARY: (dashed pink line)
  - UNDISTURBED AREA BOUNDARY: (dashed green line)
  - Reclaimed Contours: (dotted black line)