

## Chapter 2

### SOILS {R614-301-200}

#### 2.10

##### Introduction

This chapter presents soil resource data and soil mapping for the Soldier Canyon Mine. The information has been compiled from the previously approved soil sections for the Sage Point-Dugout Canyon and Soldier Canyon Mine, ACT/007/009 and ACT/007/018, respectively, as well as new soil survey information for the nonpermitted permit boundary expansion. Soil studies were conducted in accordance with guidelines issued by the Utah Division of Oil, Gas and Mining (DOG M) which were in effect at the time each study was conducted. All surveys fulfilled the requirements established by the Soil Conservation Service (SCS). However, developmental plans for future disturbances, unless exempted by the R645 rules, will meet the standards of the National Cooperative Soil Survey and analyzed by horizon according to Table 1 of the Division's "Guidelines" for topsoil.

Mapping and data from these surveys were combined onto one final base map and report for this application to identify the locations, characteristics and areal extent of endemic soil resources within the life of mine (LOM) area at the Order III level (Exhibit 2.22-1). Soil sampling information, collected for the Soldier Canyon Mine permit application, is presented on a site-specific basis with regard to existing or proposed disturbances.

Soil resources affected by the surface facilities expansion and county road relocation, and topsoil storage site, and ~~refuse disposal site~~ were thoroughly evaluated by EarthFax Engineering, Inc., and the SCS. Their reports are presented in this chapter or referred to in the text. In areas not affected by any surface disturbance, only an Order III survey was conducted.

The Applicant will present, in this chapter, a description of the permining soil resources as specified under R614-301-221. Topsoil and subsoil to be saved under R614-301-232 will be separately removed and segregated from other material.

After removal, topsoil will be immediately redistributed in accordance with R614-301-242, stockpiled pending redistribution under R614-301-234, or if demonstrated that an alternative procedure will provide equal or more protection for the topsoil, the Applicant will seek approval from the Division.

## 2.20 Environmental Description

### Central Mine Facilities

The central mine facilities are located in Sections 18 and 7, Township 13 South, Range 12 East, S.L.B & M. The mining activities are conducted within 100 feet of the Soldier Creek Road and are within the Soldier Creek Stream buffer zone. The elevation is 6700 to 6850 MSL and the soil range type is mountain loam.

The slopes in this area range from 10% to >60%. Vegetation varies from a deciduous community along the stream channel to a mountain brush community. As shown on Exhibit (2.22-2), much of the soil resources in this area had been previously disturbed through coal mining and exploration activities, county and road development, and the installation of a gas pipeline.

### Topsoil Storage Site

This site is located in Section 25, T13S, R11E, S.L.B & M. This site is located just west, within 100 feet of the Soldier Creek Road right-of-way and approximately 2.5 miles south of the central mine facilities (Exhibit 5.21-2). The site area is located on a small gentle sloped bench at an approximate elevation of 6200 MSL (Appendix 2-A). Vegetation in the site area consists of a sagebrush-grass community (Exhibit 3.7-3/Map A). The sagebrush-grass community has a cover of approximately 35 percent. Refer to Appendix 2-F for information pertaining to the expansion of the storage area.

### Refuse Disposal Site

~~The proposed refuse disposal area is located in Section 25 & 36, Township 13 South, Range 11 East, S.L.B & M. The site is situated just west of Highway 53 approximately nine miles northeast of Wellington, Utah in Carbon County (Appendix 2-A).~~

~~More specifically, the site is located in a small drainage west of Soldier Creek at an approximate elevation of 6100 MSL (Appendix 2-A). The small drainage channel bottom slopes to the south at 4% to 30%. The perimeter sideslopes of the drainage are fairly steep sloped, from 30% to >60%.~~

~~Vegetation at the site consists of approximately 70% shrubs, 1% forbs and 29% grasses. The mean combined living ground cover for the site was estimated as approximately 31% (Mt. Nebo Scientific, 1991). Soil across the surface appears~~

~~to be relatively uniform in texture with variations in color and moisture due primarily to vegetation and relief. The local topography within the drainage is dissected by erosion and has created a badlands type terrain.~~

#### 2.21 Prime Farmland Investigation

Soil mapping was completed for the proposed LOM permit area and the resultant data forwarded to the SCS office in Salt Lake City, Utah. This information was reviewed by SCS personnel and a negative determination was given with regard to the prime farmland status of the soils overlying the proposed LOM area. A copy of this letter is presented in Appendix 2-B.

In addition, the Soil Conservation Service indicated that a small area of irrigated Prime Farmland exists within the NE 1/4 of the NE 1/4 of Section 36, T13S, R11E. The attached map (Appendix 2-B) shows that the area is located south of the ~~area designated for use associated with the proposed refuse disposal and~~ LOM area.

#### 2.22 Soil Survey

A map (Exhibit 2.22-1) delineating the different soils at an Order III level was drawn showing the areal extent of the endemic soil resources within the life of mine (LOM). Supplemental field investigations were also conducted for the facilities expansion, and topsoil storage site ~~and refuse disposal site~~ as required by the Division. These reports will supplement the existing soils report and supply baseline information for undisturbed areas that the Applicant is proposing to disturb.

With respect to the area encompassed by this proposed LOM permit, three seedbed material (topsoil, substitute topsoil and previously disturbed subgrade material) sampling efforts have been completed. Sixteen samples of soil and disturbed materials were collected and analyzed as a part of the original Soldier Canyon Mine permit document (ACT/007/018). The raw data results from the initial mine sampling program is shown in Table 2.22-1 with soil locations shown on Exhibits 3.7-2 and 5.21-1. These soils were analyzed at Utah State University's Soil Laboratory, an approved soils and agricultural laboratory.

With regard to Table 2.22-1 sample number 1 was taken from the existing soil stockpile. Sample 2 was collected from the sediment pond storage pad fill while sampled 3 and 4 were from undisturbed soils bordering the sediment pond. Samples

characteristics of the soils. Table 2.22-2 lists the location, date, identification number or field evaluation, and the report (Illustration) pertaining to each investigation.

Topsoil Storage Site and Refuse Disposal Site

The initial field exploration program, conducted in May, 1990, consisted of a detailed inspection of the site to evaluate topographic relief, vegetation type and percent cover, surficial evidence of soil distribution and exploration of Old Test-Pits 1, 2, 3 & 4 (OTP 1-4) (Figure 1, App. 2-A) to provide a detailed log of the soil profile for each series present and collection of representative samples from each series for laboratory analysis. A supplemental field investigation was conducted in April, 1991. During the supplemental investigation six stream bank sections, seven test pits and ten auger holes were installed, logged and samples. The additional soils investigations were conducted to further characterize the physical and chemical characteristics of the soils present in the bottom of the drainage area. These supplemental investigation includes Test-Pits 1-4, Auger Holes 1-10 and Stream Channel Sections 1-5.

Figure 1, presented in Appendix 2-A, delineates the soil map unit boundaries as mapped in the field. General soil unit descriptions are defined below.

### Hernandez Soil

The 4.5 acre topsoil storage portion of the terrace immediately east of and contiguous to the proposed refuse disposal area (~~never to be constructed, 9/05/03~~) is classified as the Hernandez Soil. This area is represented by OTP #1.

### ~~Gerst-Badland Complex~~

~~The hillslopes and upper elevations of the refuse disposal area are covered by the Gerst-Badland Complex. OTP #2 and #4 are representative of this soil complex.~~

### Haverdad Soil

The soils within the confines of the valley floor have been classified as the Haverdad Soil and is represented by OTP #3. In addition, TP 1-4, AH 1-10 and Stream Channel Cross-sections (SCC) 1-5 also represents the Haverdad soil unit.

### Soil Description

This section presents the results of the soil baseline investigation completed for the Soldier Canyon Mine LOM permit area. Factors important in the development of soils overlying the permit area are discussed. Descriptions are included with respect to the soil map units (Appendix 2-B) and soil series mapped within the permit boundary (Exhibit 2.22-1). The map unit descriptions describe the physiographic setting of the unit, soil characteristics, overlying vegetation communities, and related information. Soil series descriptions give a more detailed description of soil characteristics in terms of soil horizonation. A soil map unit legend is included (Table 2.22-3).

Soil productivity of map units within the proposed LOM boundary are listed. Laboratory data resulting from the collection and analysis of soils and disturbed seeded materials are also presented in this section. The characteristics of soils in the permit area are determined by the interaction of the following five principal soil factors.

Parent Material: The soils above the drainageways on the large, gently sloping pediment surfaces, steep sides of hills, and bottoms away from the streams have formed in colluvial material. This material is a weathering product of the Mancos Shale and Flagstaff Formation. These soils are generally gravelly, stony, and bouldery in the interbedded sandstone, and channery

## Topsoil Storage Site ~~and Refuse Disposal Site~~

### Soil Description for Topsoil Storage and Refuse Disposal Site

Many portions of the following soils descriptions were taken, in large measure, from the Soil Survey of Carbon Area, Utah (Soil Conservation Service, June 1988). ~~Some text modifications have been made to represent the exact field conditions encountered at the refuse disposal site.~~ Detailed soils descriptions are located in Appendix 2-B.

#### Gerst-Badland

This series consists of shallow, well drained, moderately permeable soils on the sides of mesas, benches, terraces and canyons and on mountain slopes and hillslopes. These soils are formed in residuum and colluvium derived from shale and sandstone. The slope averages 30%-70%. Elevation ranges from 5,200 to 8,000 feet. Average annual precipitation ranges from 8 to 14 inches and average annual air temperature ranges from 45 to 50 degrees F. The soils are loamy, mixed (calcareous) mesic shallow Ustic Torriorthents.

The surface soils are light brownish gray to dark brown, moist, extremely stony loams. They have a weak medium subangular blocky structure and are slightly hard, friable and slightly plastic. Intermediate horizons are light brownish gray to grayish brown, moist Channery silt loams. Structure is massive and the soil is hard, friable, and plastic. Very fine roots are common. The subsoil contains 15% shale fragments and are strongly calcareous. Deeper horizons are partly weathered Mancos Shale with a paralithic contact depth at 18-20 inches.

#### Haverdad

The Haverdad soils are deep, well drained, moderately permeable soils on fan terraces and valley floors. These soils formed in stratified alluvium derived from sandstone and shale. Slopes average 1 to 8 percent. Elevation ranges from 5,500 to 6,900 feet above mean sea level, Average annual precipitation ranges from 8 to 14 inches, and average annual air temperature ranges from 45 to 49 degrees F. The soils are fine-loamy, mixed (calcareous) mesic Ustic Torrifuvents

The surface soils are typically light brownish gray to dark grayish brown, moist loams. Structure is weak platy to fine granular, hard, friable and plastic. The soil contains numerous pores and is moderately carbonaceous. The intermediate horizons are light yellowish brown to yellowish brown, moist loams. A weak subangular, blocky structure is typical. The soils are hard, friable and plastic. The soil is moderately calcareous and contains numerous pores. Deep horizons are

pale brown to yellowish brown, moist loams. The structure is massive and very hard, friable, and plastic. Pores are common and the soil is moderately calcareous.

#### **Hernandez**

The Hernandez unit consists of very deep, well drained soils developed on fan terraces. These soils form in alluvium derived from sandstone and shale. Slopes are 1 to 8 percent. Elevation is 5,600 to 7,100 feet. Average annual precipitation is 10 to 14 inches, and average annual air temperature is 45 to 49 degrees F. The soil is fine loamy, mixed, mesic Ustollic Calciorthids.

The surface soil is typically brown to dark brown, moist loams. The structure is weak fine granular, slightly hard, friable, and slightly plastic. It contains few very fine, common fine and few medium roots; many fine and few medium pores and is moderately calcareous. The intermediate horizons are brown to light brown, moist loams. These soil horizons exhibit a weak to moderate medium subangular blocky with few very fine, fine and medium roots. Also these horizons commonly have fine to medium pores and are moderately to strongly alkaline. The deep horizon is a moist, massive, hard, firm and plastic loam. It is strongly alkaline with few fine roots and common fine pores. Calcium Carbonate coats the faces of the peds.

#### Present and Potential Productivity

Table 2.22-4 depicts the potential productivities of soil mapping units occurring within the proposed LOM boundary. Potential values vary for map units between oven-dry and air-dry productivities were taken from SCS Soils 5 Soil Interpretation Records for the Carbon Soil Survey Area. Potential oven-dry productivities were extracted from the previously accepted Sage Point/Dugout Canyon Mine permit application.

~~The soil units occurring at the refuse disposal site limit the present and potential productivity for the area.~~

The Gerst soil is in capability class VIIe nonirrigated and the Badland is in capability class VIIIe. The Haverdad loam unit is in capability class VIe, non irrigated. The Hernandez nonirrigated soil is in capability subclass VIe. Class VI soils have severe limitations that make them generally unsuitable for cultivation. Class VII soils have very severe limitations that make them unsuitable for cultivation. Class VIII soils have limitations that preclude their use for crop production. The capability subclass with a letter designation of "e" shows a significant limitation in use due to risk of erosion, unless,

Soils are mapped at the Order III level on the permit area. An Order II survey was not required for disturbed areas since all areas to be disturbed during the proposed mining had been affected by operations conducted prior to the passage of current mining laws and regulations. Soil reports were prepared by Ford, Bacon, and Davis, Inc. and by EarthFax Engineering, Inc. to supplement information contained in Section 8.0 of the original permit application.

In 1985, Cedar Creek Associates, Inc., was retained by the Applicant to conduct a soil survey on two sections of land adjacent to the Sage Point-Dugout Canyon and Soldier Canyon mines. These were Sections 5 and 6, T135 and R12E, SLM. This survey (as well as the Soldier Canyon Mine survey) relied exclusively on existing information. These areas had previously been surveyed by the SCS at an Order III level. (Soil mapping and map unit descriptions have been completed and approved for this area but are as yet unpublished.) Because no surface disturbance is scheduled to occur in Sections 5 and 6, an Order III soil survey was deemed sufficient to characterize the soil resource. Cedar Creek was also retained to integrate the soil information from the Sage Point-Dugout Canyon Mine and Soldier Canyon Mine surveys, as well as the new soil resource information, into this permit application.

New soil resource information for SC3's surface facilities expansion is provided to supplement the existing soils information for these areas. A 1st Order Soil Survey was conducted on those areas to be disturbed.

Soil surveys were performed by the SCS on 10/16/89 and 5/23/91, to identify any soil complexes within the soil mapping units. These investigations were required by the Division to adequately describe the soils that will be disturbed or potentially disturbed, as a result of, the surface facilities expansion and county road relocation. Illustrations 10.6.3-1 and 10.6.3-2 provide SCS's findings.

For the topsoil storage ~~and refuse disposal site~~, EarthFax Engineering, Inc. was contracted to perform the necessary field investigations. All field investigations were conducted and test-pits were logged in accordance with USDA Soil Conservation Service procedures as defined in the National Soils Handbook and the Soil Survey Manual. The soils were mapped to the phase of the series. Individual mapping unit boundaries were delineated in the field. Thus, allowing the area to be mapped under a "1st Order Soil Survey". The Gerst-Badland is a soil complex which cannot be separated into individual mapping units because of the intimately mixed nature of the two soil units.

#### 2.24 Substitute Topsoil

### Refuse Disposal Site

~~Because of the limited thickness or total absence of the O, A and B horizons in the Haverdad Series and the Gerst-Badland Complex, the subsoil will be used as substitute topsoil. Sufficient samples were collected to assess the physical and chemical capabilities of the materials (Appendix 2-D). Once stockpiled, the soil will be prepared for revegetation to aid in stabilizing the soils until subsequent use. The revegetation will act as a test area to further define the capabilities of the substitute soil.~~

## 2.30 Operation Plan

### 2.31.1 Methods for Removing and Storing Topsoil, Substitute Topsoil and Landscape Boulders/rip rap

The following is a list of equipment to be used for removal of vegetation, boulders and topsoil and for loading the topsoil, substitute topsoil and landscape boulders/riprap.

1. Track Hydraulic Excavator
2. 966 Wheel Loader
3. D8 Dozer
4. 953 Track Loader
5. 12 yd<sup>3</sup> Dump Trucks
6. Belly Dumps

The safest and most efficient means of performing this operation will be used to ensure the safety of the equipment operators. Topsoil will be loaded into the dump trucks and hauled to the Applicant's topsoil storage site. Substitute topsoil will be sorted and hauled to the topsoil site and placed in its designated location at the topsoil site. Landscape boulders/riprap will also be hauled and placed in its designated location at the topsoil storage site.

### 2.31.2

The suitability of topsoil substitutes is described in section 2.24 of this application

### 2.31.3

Testing plan for evaluating the results of topsoil handling and reclamation procedures related to revegetation are as described in section 2.41 of this application. Sampling techniques are described in detail in this section. Soil nutrients and amendments will be added based on these tests.

### 2.31.4

The Applicant has an approved topsoil storage site to accommodate the storage of topsoil, substitute topsoil and landscape boulders/riprap associated with the surface facilities expansion and road relocation. The topsoil storage site encompasses 4.5 acres, of which 2.3 acres is presently approved for the stockpiling of the above mentioned material. ~~The remainder or 2.2 acres, will be used for storing the topsoil and substitute topsoil removed from the proposed refuse disposal site.~~

Presently the topsoil storage site is arranged as shown on Exhibit 5.21-2. The area designated as topsoil/substitute topsoil storage will not be stripped of topsoil, but will be cleared of any vegetative cover prior to placement of other topsoil. ~~However, the expanded area of the site that will facilitate the storage~~

~~of topsoil/substitute topsoil from the refuse disposal site, will be stripped of topsoil prior to placement of the material.~~ The area designated as landscape boulders/riprap storage will be stripped of topsoil to a depth of 17 inches prior to placement of boulders. Vegetation that is removed will be burned, buried or hauled off to the nearest landfill for disposal.

Topsoil and substitute topsoil will be placed on a stable gradually sloping site with enough compactive effort applied during placement to maintain competence of the embankment. Any further placement of topsoil, after the initial piles are revegetated and stabilized, will necessitate the formation of new topsoil piles to eliminate disturbance to the established piles. Vegetation will be established to limit erosion. The topsoil/substitute topsoil will be protected from excessive erosion and instability by the following means:

- \* Placed on a stable site with proper identification signs
- \* Construction of runoff control and diversion measures around the site
- \* Completing necessary annual interim reclamation measures to ensure that an adequate stand of vegetation cover is maintained.
- \* Not be moved until required for redistribution unless approved by the Division.

Landscape boulders/riprap will be placed on a 0.30 acre parcel of the topsoil site. Prior to any boulder placement, the 0.30 acre parcel will be stripped of topsoil to a depth of 17 inches. The total yardage of topsoil to be removed will be approximately 590 yd<sup>3</sup>s. The topsoil to be removed will be placed as shown on Exhibit 5.21-2. After topsoil removal, approximately 1675 yd<sup>3</sup>, of landscape boulders/riprap will be hauled from the mine site and placed until reclamation.

Prior to the establishment of the topsoil storage site, only one other site at the central mine facilities accommodated the storage of topsoil; the central mine facilities topsoil storage pile. This topsoil stockpile is located on the southeast portion of the sediment pond area and is adequately protected from runoff, water and wind erosion and instability. The stockpile was placed on the insitu and fill soils downstream of the incised sediment pond. The west portion of the pile butts directly against the pre-existing hillslope. The northern most portion of the stockpile has a flat top with a 6 in. protective gravel cover. (This portion of the stockpile along with the sediment pond embankment soils were incorporated into a small storage yard which is covered with gravel and enclosed by a wire mesh fence). Liquids or materials which might provide a source of toxic or hazardous materials are restricted from the area. The exposed southeast facing slope of the topsoil stockpile has moderate slopes 1 V:2.5 H, and is well vegetated. The exposed face has mulch tacked down by anchored jute netting. The topsoil stockpile has approximately 85% vegetative cover with the remainder of the area being covered by the mulch and jute netting.

The area is protected from runoff by the sediment pond and road diversions. Protection from water and wind erosion is provided by the 6 in. gravel cap on top and the well vegetated southeast facing slopes. The soil was emplaced on a stable foundation utilizing acceptable engineering practices to achieve the appropriate level of compaction to insure slope stability.

The area is well marked and identified as a topsoil stockpile. The protection measures previously mentioned ensure the long term stability and protection of these topsoil resources.

#### Refuse Disposal Site

~~Topsoil and substitute topsoil resources (subsoil) which could potentially be covered by refuse material will be salvaged prior to placement of the material. Detailed plans are outlined in the following sections.~~

~~A combination of large earthmoving equipment, potentially including backhoes, dozers, loaders, scrapers and dump trucks, will be used to remove and haul the topsoil materials from their present location to the proposed storage area. Plans for the removal and sequence of removal are contained in Section 5.28 of this application.~~

~~The topsoil and subsoils, which will be salvaged, stockpiled and redistributed during reclamation, are the best available materials present at the site. With the exception of fertilizer and mulch, no other topsoil substitutes or supplements will be added to the soil materials.~~

~~A seed mix made up of species similar to those within the vegetation reference will be used to establish vegetation on the stockpiled topsoil. The vegetative cover on the topsoil stockpile will be monitored to ensure that an adequate cover of vegetation is maintained and also to ensure that the prescribed seed mix is acceptable.~~

~~The salvaged soils from the initial disturbance from construction of the haul roads, preparation of the temporary topsoil storage area, preparation of the proposed refuse disposal area and appurtenant facilities will be stockpiled in the designated location within the temporary topsoil storage area. Separate topsoil stockpiles will be maintained for the soils collected from each of the three distinct soil units.~~

#### 2.32 Topsoil and Subsoil Removal

##### Central Mine Facilities

As a result of soil thickness surveys and SCS's recommendation, the Applicant

Topsoil Storage Site - Topsoil removal was performed only in those areas affected by the construction of the access road and landscape boulders/riprap stockpile. The top 17" of topsoil was segregated in those areas (see Section 2.31.4). Topsoil material was used in the construction of the berms, where it will be revegetated upon completion of the site.

Refuse Disposal Site

~~SCC will attempt to remove all soil from the area of the refuse disposal site that is proposed to be disturbed. As indicated in section 2.24, because of the lack of topsoil in many areas of the site (i.e., less than six inches thick), SECC plans on salvaging both the small amount of topsoil present and a portion of the subsoil materials as a mixture. This mixture will be treated as a separate layer and will be segregated. Before removal of any soils, the vegetation will be burned or cleared and buried. Any rock excavated from the soil salvage area will be placed either on the durable rock fill area of the temporary topsoil stockpile area or the previously filled area of the refuse disposal site. A combination of large earthmoving equipment, potentially including backhoes, dozers, scrapers and dump trucks, will be used to remove and haul the soil materials from their present location to the proposed temporary topsoil storage area.~~

~~The salvaged soils from the initial disturbance from construction of the haul roads, preparation of the temporary topsoil storage area, preparation of the proposed refuse disposal area and appurtenant facilities will be stockpiled in the designated location within the temporary topsoil storage area. Separate topsoil stockpiles will be maintained for the soils collected from each of the three distinct soil units.~~

~~An excavation of 17 inches of topsoil will occur within the area of the temporary topsoil stockpile area and from the access roads. Within the refuse disposal area, an average of 18 inches of soil salvage excavation will occur. In the upper reach of the disposal area drainage, the soil is anticipated to be limited in quantity and depth. This is due to the geomorphic process of headward cutting of the drainage, near the upper contact with the Mancos Shale. The alluvial fill lower down in the drainage is likely to be much thicker than 18 inches, perhaps as deep as 36 inches. Where deeper soils of suitable quality exist additional volumes may be salvaged, if Soldier Creek Coal Company officials find additional soils are needed, to aid in reclamation.~~

~~All soil that could be potentially disturbed or covered by refuse disposal~~

~~activities will be removed and salvaged, unless it would be unsafe or impractical because of slope or rockiness or limited depth of soil. The excavation of the soil resources will take place sequentially, removing only the amount of soil from the area required for disposal of refuse quantities. This will prevent undue exposure of soil and allow vegetation to remain in place until the area is required for refuse placement, which will aid in erosion control. Sequential excavation also will aid in maintaining the existing physical and chemical characteristics of the undisturbed soils. Initially, the soil from the areas to be used for access roads will be stripped and stockpiled, as well as two small work areas within the disposal area. These are areas near the upper portion in the headwaters of the drainage for refuse disposal and an area in the lower portion of the drainage for the construction of the sediment pond.~~

~~Once the refuse pile is operational, future sequential soil salvage will be based on the refuse storage needs for the forthcoming operation periods. These storage volumes will be determined based on the planned production of the coal mine and the anticipated coal quality. Based on these storage needs, the required area for refuse will be staked in the field and cleared of all vegetation and rock, if any, as described above. The soil will be removed, without segregation of the soil horizons, and placed in the designated portion of the temporary topsoil stockpile facility.~~

~~SC<sup>3</sup> is planning to salvage soil from the steeper sideslopes of the disposal area drainage. As indicated in Appendix 2-D, the rock fragment percentage is high. Additionally, salvage operations will continue until SC<sup>3</sup> finds that the salvage operations become unsafe or impractical due to slope or rockiness of the slope soils. SC<sup>3</sup> will confer with the DOGM for approval of the decision to cease soil salvage on the steep slopes.~~

~~Section 5.37 presents the volume of soil required for redistribution on the regraded and covered refuse. SECC will ensure that at least this volume of soil materials will be cumulatively stripped from the refuse disposal area. As discussed above, during the soil salvage operations in the upper portions of the drainage, the salvaged soil volumes will be limited due to the limited extent and depth of the soil materials. Once the refuse pile extends into the lower portions of the drainage, considerably more soil material will be available.~~

~~Although minor disturbances are not envisioned at this time, Soldier Creek Coal Company requests permission to exclude the removal of topsoil from minor disturbances that might be associated with power poles, signs, and fences. It is understood that this provision is allowable since the minor disturbance does~~

~~not significantly affect the vegetation nor cause erosion.~~

~~The salvaged soil from all three soil units found within the disposal area will be stockpiled separately. However, because of the limited thickness of the upper horizons and the rugged nature of the topography, the individual soil horizons within each soil unit will not be segregated into separate storage areas.~~

~~Once the soil materials required have been stripped from an area proposed for storage of refuse material, SC<sup>7</sup> plans to excavate the subsoil materials. These materials will be used as fill to cover the refuse before redistribution and placement of the soil materials. As with the soils, the depth of subsoil in the upper portions of the disposal area drainage will be thinner than in the lower portions of the drainage. Section 5.37 presents estimates of both the required volume of fill for covering the refuse and available volume of fill materials. Based on these estimates, there is sufficient fill available to cover the refuse.~~

### 2.33 Topsoil Substitute and Supplements

Selected overburden materials may be substituted for, or used as, a supplement to topsoil if the operator demonstrates to the Division that the resulting soil medium is equal to, or more suitable for, sustaining vegetation on non-prime farmland areas than the existing topsoil, and results in a soil medium that is the best available in the permit area to support revegetation.

Section 2.24 (Substitute Topsoil) addresses the substitute topsoils and their respective locations. As stated in section 2.24, the majority of the surface disturbance occurred prior to the passage of SMCRA. Exhibit 2.22-2 shows the extent of the pre-SMCRA disturbances. As such, soil salvage was not conducted as a part of normal operating procedures. Therefore, topsoil materials available for revegetation are limited.

Test plots constructed under the previous Soldier Canyon Mine permit will test the efficacy of the substitute materials (section 2.24). The Applicant will use the vegetation growth on the substitute topsoil stockpile, constructed of stream channel soils, to test the efficacy of that particular substitute material. The applicant has established test plots as mentioned in Section 2.24. The vegetation growth on the stockpiled stream channel solid will test the efficacy of that substitute material.

### Refuse Disposal Site

~~As indicated above, all of the soils present in the area of the proposed refuse~~

~~disposal site have limited thickness of the O, A, or B horizons. Therefore, SC<sup>3</sup> proposes to use the underlying horizons (subsoils), mixed with the thin layers of topsoil present, as substitute topsoil. All three soil units found in the disposal area do not have enough material meeting the DCGM definition of topsoil to provide material suitable for salvage of a six inch thickness.~~

~~The topsoil and subsoils, which will be salvaged, stockpiled and redistributed during reclamation, are the best available materials present at the site. Laboratory analytical data for all three soil units are provided in Appendix 2-D. While it is understood that some chemical parameters have higher concentrations than are typically desirable for reclamation, these soils are also the best available materials. However, as observed during the field investigations for both the soils and vegetation report, the area has been able to establish adequate vegetative cover. Therefore, imported substitute topsoil will not be required, as the best available soil resources from the site will be salvaged. Except for fertilizer and organic matter, no other topsoil substitutes or supplements will be added to the soil materials.~~

~~Concurrent reclamation of previously filled cells within the refuse disposal facility provide an excellent "field site trial" to judge the success of the proposed reclamation activities. This on-going reclamation activity will allow the effectiveness of the vegetative seed mix, soil nutrients and supplements, and other proposed reclamation measures to be judged. Thus, if any of the reclamation parameters need to be changed or if supplements need to be added, they can easily be added or corrected during future reclamation activities.~~

#### 2.34 Topsoil Storage

Materials removed under R614-232.100, R614-301-232.2 and R614-301-232.300 will be segregated and stockpiled when it is impractical to redistribute such materials promptly on regraded areas. The stockpiled material will:

- \* Be selectively placed on a stable site within the present permit area
- \* Be protected from contaminants and any unnecessary compaction that would interfere with revegetation.
- \* Be protected from wind and water erosion through prompt establishment and maintenance of an effective, quick growing vegetative cover or through other measures approved by the Division.
- \* Not be moved until required for redistribution unless approved by the Division.

The Applicant's permitted Topsoil Storage Site (Exhibit 5.21-2) was constructed according to the R614 coal mining regulations. This approved site allows for the stockpiling of soil material and landscape boulders/riprap to prevent any damage to the quality or quantity of those materials. Figures 2 and 3 in Appendix 2E also show stockpile quantities, locations and cross-sections. Soils salvaged

have approximately 2h:1v outslopes and surrounded by soil berms. Placement of the stockpiles will take place after the vegetation is removed or incorporated into the salvaged topsoil from the host site (topsoil storage site). Topsoil from the host site will be salvaged to a depth of 17" and stockpiled to prevent any potential for contamination by the material to be stockpiled. Those areas where the central mine topsoil and substitute topsoil were placed did not require stripping prior to their placement. This activity was approved by the Division during the initial permitting of the site.

~~Placement of the soils from the refuse disposal site will require salvaging of the host site prior to their placement. Each distinct soil unit (i.e., Haverdad or Hernandez) will be segregated and stabilized as a distinct soil unit.~~

Any further placement of soil stockpiles, after the initial piles are revegetated and stabilized, will necessitate the formation of new topsoil or subsoil piles to eliminate disturbance to the established piles. Vegetation will be established to limit erosion.

Runoff control for the topsoil storage site is presented in Section 7.32 of this application.

#### 2.40 Reclamation Plan

#### 2.41 General Requirements

The permit application includes plans for redistribution of soils, use of soil nutrients and amendments and stabilization of soils.

#### 2.42 Soil Redistribution

Topsoil will be replaced on graded areas in a manner and at a time that 1) achieves an approximate uniform, stable thickness consistent with the approved postmining land use, contours, and surface water drainage systems; 2) Prevents excess compaction of the materials; 3) Protects the material from wind and water erosion before and after seeding and planting.

Topsoil will be applied in lifts as thick as possible to decrease compaction potential. Replacement will occur along the contour, where safety factors permit, to minimize erosion and instability. Replacement will occur within 30 days prior to seeding.

#### Central Mine Facilities Area

The Applicant does not plan to redistribute the topsoil in any area until that area is backfilled, recontoured and scarified (1.5 ft.). Immediately after the

disturbance. The backfill material will come from the berms and once graded, the area will be revegetated.

### 3. Access Road

Immediately after the access road is no longer needed for operations, reclamation, or environmental monitoring, it will be restored. The gravel road surface and subgrade material will be removed and used as backfill at the mine site or at the proposed waste rock site. The topsoil off the outcrops will be removed and temporarily stockpiled in an area at the road construction beginning. The compacted roadway will then be scarified to a minimum of two feet to ensure adequate bonding between soils. The topsoil material from the temporary stockpile will then be evenly spread over the area, disced and seeded.

### Refuse Disposal Site

~~When the refuse storage capacity of a portion of the site is exhausted, the area will be prepared for final reclamation. The surface of the filled section of the refuse disposal area will be prepared for re-distribution of the topsoil. The area will be graded and smoothed to the final topographic configuration (see Plate 5-2). The refuse, consisting of cobble size fragments of shale, sandstone and siltstone will be re-worked at the surface to break down larger pieces and then compacted with at least three passes of a compactor or other piece of construction equipment with comparable load distribution. Construction staking during this process will assure that proper grades are being maintained.~~

~~Once the site area has been regraded, the fill material cover will be placed over the refuse. SC<sup>2</sup> plans to place a fill cover of 24 to 30 inches and 6-12 inches of topsoil over the refuse. As no acid or toxic forming refuse is planned to be placed in the pile, this cover thickness is felt to be adequate. In the event that acid or toxic forming materials are identified, then they will be covered with a minimum of 4 feet of the best available, nontoxic and noncombustible material. Care will be taken to ensure a uniform thickness of fill material will be placed on the refuse. During the placement of the fill, the area will be adequately compacted to provide a stable fill cover and to prevent slippage of the fill materials.~~

~~Following the placement of the fill materials, the soils will be placed. Care will be taken to provide a uniform thickness over the entire fill area. Random excavations will be taken of the topsoil fill to ensure compliance. Upon completion of the final grading, random samples will be collected in appropriate sample containers for use in final laboratory analyses. The soil will be scarified to a depth of at least 10 inches. The appropriate ratios of seed, fertilizer and mulch will be applied, as indicated in Chapter 3 of this~~

application.

~~Once the final segment of the phase construction of the site is filled, the material stored at the temporary topsoil storage area will be used to cover and topsoil this segment. The old soil stockpile site also will be reclaimed. The surfaces of both areas will be scarified. The refuse pile segment will be scarified to a depth of 10 inches, while the stockpile site will be scarified to a depth of 12 inches. This will remediate the effects of excessive soil compaction induced by both the surcharge weight of the stockpile and reclamation equipment traffic. Once the materials are loosened to a satisfactory degree for planting, the appropriate seed, fertilizer and mulch will be applied and disced into the original surface. This will be conducted according to the reclamation plans presented in Chapter 3 of this application.~~

~~Original runoff control facilities for both the disposal and stockpile areas will be maintained and sequencing of reclamation will be used to reduce the potential for erosion of the newly planted surfaces. The remedial measures will stay in affect until such time as the natural vegetative cover is well established and can naturally control excessive erosion.~~

#### 2.43 Soil Nutrients and Amendments

Seedbed materials will be sampled following gradings and prior to seeding to assess the success of grading and to determine fertilizer requirements. Fertilizer will be added to regraded areas as per recommendations resulting from sample analysis. The following specifications will be followed to collect seedbed material samples.

The laboratory selected to analyze samples will be contacted at least 30 days in advance of each sampling period to aid in coordinating sample analyses with the implementation of subsequent revegetation procedures.

##### Specific Procedures

Two samples, representing the 0-6 and 6-18 in. depths, will be taken at a rate of one sample per 5 ac of disturbed area for each type of disturbed site. Sites less than 5 ac in size will also be represented by one set of samples. Seedbed materials exhibiting surface characteristics (e.g. color, texture, parent material) or topsoil replacement depths significantly different from adjacent areas will be sampled as separate entities under the 5 ac rule. For each sample, the average slope and estimated coarse fragment content by volume will be estimated. Each sample will be analyzed by the laboratory for:

### Refuse Disposal Site

~~The nutrient levels for the soils will be enhanced to aid in revegetation. The nitrogen concentrations will be supplemented by applying 88 pounds per acre of sulfur coated urea, 45-0-0, a slow release fertilizer. Treble superphosphate, 0-46-0, will be used, at a rate of 65 pounds per acre, to supplement the phosphate levels. Potassium levels are within the desirable levels for successful revegetation. Thus, no potassium will be added to the soil.~~

~~Fertilizer will be applied in the fall of the year when reclamation is occurring. Fertilizer will be applied by broadcasting, drilling or hydroseeding.~~

#### 2.44 Soil Stabilization

All exposed surface areas will be protected and stabilized to effectively control erosion and air pollution attendant to erosion.

Suitable mulch and other soil stabilizing practices will be used on all areas that have been regraded and covered by topsoil or substitute topsoil. Section 3.41 of this document will fully address the methods by which the Operator will use to stabilize redistributed soils.

Rills and gullies, which form in areas that have been regraded and topsoiled and which either:

Disrupt the approved postmining land use or the reestablishment of the vegetative cover; Cause or contribute to a violation of water quality standards for receiving streams will be filled, regraded, or otherwise stabilized, topsoil will be replaced and the areas will be reseeded or replanted.

#### 2.50 Performance Standards

All topsoil, subsoil and topsoil substitutes or supplements will be removed, maintained and redistributed according to the plan given under R614-301-230 and R614-301-240.

#### 2.52

All stockpiled topsoil, subsoil and topsoil substitutes or supplements will be located, maintained and redistributed according to plans given under R614-301-230 and R614-301-240.

## Chapter 3

### BIOLOGY {R614-301-300}

#### 3.10 Introduction

This chapter presents a description of the biological resources found within the life of mine permit area.

The sections addressed in this chapter are: the vegetative, fish and wildlife resources; the potential impacts to vegetative, fish and wildlife resulting from the proposed operations, and the mitigation plans and measures to minimize the impacts; and the reclamation plan to restore the vegetative, fish and wildlife resources to a condition suitable to the postmining land use.

#### 3.20 Environmental Description

#### 3.21 Vegetation Information

The vegetation study and floral characteristics described in this application were derived from a complex of previous studies for the two previously approved documents; Sage Point-Dugout Canyon (ACT/007/009) and Soldier Canyon Mine (ACT/007/018), and new information collected to address the new life of mine (LOM) areas. This information is designed to satisfy federal and state requirements for baseline vegetation data and reference area establishment.

The LOM area primarily exists within the steeply incised canyons of the Book Cliffs, but also includes portions of the upland benches along the West Tavaputs Plateau. The sewage lagoons and topsoil storage area and refuse disposal areas are located on the toe-slopes of the Book Cliffs. Soils range from extremely poor in areas that are steep and rocky or formed from Mancos shale to relatively deep productive soils which formed at the base of north-facing slopes high in the Book Cliffs. Precipitation varies with elevation but is generally low, typical of the Great Basin desert. According to Kuchler (1975), the potential natural climax vegetation communities of the proposed LOM area include (from lowest in elevation to highest): Saltbush-Greasewood (Atriplex - Sarcobatus), Pinyon Juniper Woodland (Juniperus - Pinus), Mountain Mahogany-Oak Scrub (Cercocarpus - Quercus), Great Basin Sagebrush (Artemisia), and Douglas Fir Forest (Pseudotsuga). However, in actuality, inclusions of several other communities can be found within the proposed LOM area. In all, thirteen floral communities were delineated and include, from the lowest elevation to the highest: Greasewood-Galleta, Black Sagebrush-Greasewood, Black Sagebrush-Shadscale, Shrub-Gras-Juniper, Pinyon-Juniper, Deciduous Streambank, Sagebrush, Mountain Brush, Mixed Conifer-Mountain Brush, Mixed Conifer, Ponderosa Pine, Douglas Fir, and

Quaking Asper (Exhibit 3.7-1).

All previous vegetation sampling occurred within the proposed LOM area or the old Sage Point-Dugout Canyon LOM area on those communities which could potentially be disturbed as well as on reference areas and vegetation adjacent to areas which already have been disturbed. These data are presented within this section of the application and are identified with regard to their source: old Soldier Canyon Permit (SC) or Sage Point-Dugout Canyon Permit (SPDC). In addition, new information was collected in the fall of 1988 and the summer of 1990 and 1991 to further describe the vegetation within the surface facilities expansion and road relocation, topsoil storage and ~~refuse disposal areas~~ and the new LOM area. Reference areas were also established for areas to be affected by surface disturbance.

Vegetation reference areas were established for communities previously affected by surface disturbances and, as indicated above, were established for communities to be affected by future surface disturbances. These areas will be used during the final stages of reclamation to assess the success of revegetation in accordance with the ultimate goal of restoring areas disturbed by mine related facilities. These reference areas will be managed properly and will be periodically monitored to assess the effects of this management.

The methodology used in gathering the required vegetation information and a description of the vegetation communities are addressed in Appendix 3-A for the existing mine permit, and in Appendix 3-B for the intake portals, road relocation, permit area expansion and the topsoil storage ~~and refuse disposal~~ areas.

### 3.21.2 Productivity of the Land Prior to Mining

Productivity and range conditions estimates for the proposed disturbed and reference areas will be performed by the U.S. Soil Conservation Service, Price, Utah. A copy of the estimates are included as Appendix 3-C. Also, included in Appendix 3-C is the existing range conditions of the Mountain Brush and Deciduous Streambank Reference Areas.

### 3.22 Fish and Wildlife Information

Fish and wildlife information for the Soldier Canyon Mine LOM permit area is presented in Appendix 3-D. Soldier Creek Coal Company (SC<sup>3</sup>) contacted the Division of Wildlife Resources (DWR) regarding the impacts to raptors that may result from an expansion of the mining permit area for the Soldier Canyon Mine. During the Spring of 1991, the DWR flew the expansion area to look for raptor nests and for those areas that could not be surveyed from the air, Environmental Industrial Services of Elmo (EIS) was contracted to perform ground surveys of

those areas. Appendix 3-D-1 contains the DWR's conclusion from these survey's along with EIS's report.

A raptor and bird survey of the permit and adjacent areas was conducted during May, June and July. The results of this study are in Appendix 3-G "1992 Avian Survey."

#### 3.22.10 Scope and Level of Detail

The scope and level of detail will be sufficient to design the protection and enhancement of the fish and wildlife in the area of the Soldier Canyon Mine LOM permit area required under R6145-301-333.

#### 3.22.20 Site-Specific Resource Information

The permit area serves primarily as rangeland for livestock and wildlife habitat. A wide variety of wildlife species utilize habitats within and adjacent to the permit area. Among the more economically important and high interest species are mule deer, elk, mountain lion, coyote, blue grouse, ruffled grouse, sage grouse, snowshoe hare, mountain cottontail, desert cottontail, and a variety of raptor species.

Details and methodology of the investigations are addressed in Appendices 3-D and 3-D-1.

#### 3.22.21 Listed or Proposed Endangered or Threatened Species of Plants or Animals

Three species federally listed as "endangered" by the U.S. Fish and Wildlife Service are potential inhabitants of the general region of the project area: the black-footed ferret, bald eagle, and peregrine falcon (Table 3.22-1).

The rarity of the black-footed ferret as well as their nocturnal and subterranean habits, contribute to their undetermined status in Utah. The only time ferrets may be seen with any regularity is in late summer when the young are active above ground (Clark, 1978). The range of the black-footed ferret closely coincides with that of prairie dogs. Ferrets utilize prairie dog burrows for living and rearing their young (Boner et al., 1977) and, thus, areas supporting prairie dogs on or adjacent to proposed permit area are potential habitat for the black-footed ferret. There have been no confirmed sightings of ferrets in Carbon County. The most recent unconfirmed sighting was by a local UDWR Conservation Officer on February 10, 1980 and occurred near East Carbon City.

A search to the east and southeast of the Soldier Canyon Coal Mine area was conducted in April and May, 1980. No prairie dogs or prairie dog colonies are

Seven species of nongame fish may occur in Anderson reservoir (Dalton, 1980). These fish species, which may occupy aquatic habitat in the project area, include the Utah chub (Gila atraria), Red shiner (Notropis lutrensis), Fathead minnow (Pimephales promelas), Speckled dace (Rhinichtys osculus), Redside shiner (Richardsonius baiteatus), Bluehead sucker (Catostomus discobulus) and Flannelmouth sucker (Catostomus discobulus). In addition, a few of these species may migrate from the Price River into the intermittent streams in the project area when water flow conditions are high. However, no fish have been observed in any of the streams in the proposed permit area during hydrologic studies conducted over the past five years (Anderson, 1980). Dead fish (unidentified as to species) have been observed in the reservoir (Anderson, 1980). Due to drought conditions in 2001 through 2003, Anderson Reservoir has been dry by late fall, no fish species have survived.

#### 3.22.22 Habitat of High Value

Mule Deer The northeast portion of the LOM area provides summer habitat for mule deer while most of the remaining portions represent transitional range. Only the sewage lagoons and topsoil storage site and proposed refuse disposal site are located within mule deer winter range. The actual area of disturbance from these facilities will be approximately 72 acres, or roughly 0.6% of the winter range currently designated as critical. The critical winter range, as designated by DWR, currently encompasses an estimated 11,750 acres, extending from Fish Creek on the east to Mead's Wash on the west (Exhibit 3.10-4).

~~The construction of the proposed refuse disposal site will have an effect on area wildlife, however, the impact should be minimal.~~

~~As presently envisioned, the active refuse disposal area will be limited in size and will range from 4 to 8 acres disturbed at any time. Each parcel will be reclaimed, once the desired fill elevation is obtained.~~

#### 3.22.23 Specially Protected Species and Habitats Identified by State or Federal Agency

The critical winter range has also been described by state agencies as "crucial-critical winter range for the mule deer population.

The sensitive plant species Hedysarum occidentale var. canone (Sweet Canyon Vetch) has been noted within the permit area. Another sensitive plant species, Cryptantha creutzfeldtii, has been noted to occur adjacent to the permit area. In accordance with the BLM, a survey of proposed disturbed areas for these plant species, is required (see Appendix 3-A).

#### 3.23 Maps and Aerial Photographs

Vegetation mapping was done by walking the area and using contour maps and aerial photographs.

#### 3.23.10 Location and Boundary of Reference Area

Exhibit 3.7-2 shows the vegetation and reference area for the Mountain Brush and Deciduous Streambank. Exhibit 3.7-3/Map A shows the vegetation and reference area for the topsoil storage ~~and refuse disposal~~ site.

#### 3.23.20 Elevation and Location of Fish and Wildlife Monitoring Stations

Exhibits 3.10-1 through 3.10-4 show the elevation and location of monitoring stations.

#### 3.23.30 Facility Used to Protect and Enhance Habitat

The Applicant ensures that all electric power lines and other transmission facilities are constructed to minimize electrocution hazards.

Fencing, installed at the topsoil storage site, is constructed to DWR standards as shown on Figure 3.23-1 for the protection of wildlife.

The landscape boulders/riprap stockpile at the topsoil storage site will provide shelter for the smaller animals.

### 3.30 Operation Plan

The Applicant has prepared a plan to mitigate any adverse effects on vegetation, fish or wildlife. Along with the mitigative measures in this plan, the Applicant participated in a wildlife mitigation plan as detailed in Illustration 10.8.2-1, thus, providing an additional 79.2 acres of improve rangeland. This plan to mitigate the loss of critical valued deer winter range was developed by the Utah Division of Wildlife Resources (Illustration 10.8.2-2).

#### 3.31 Interim Revegetation and Stabilization

Several area exist and will exist on operational areas that will require temporary stabilization until permanent revegetation is initiated. Such disturbances include topsoil stockpile sites, temporary road locations, and sites within the Soldier Canyon Mine facilities which were or will be disturbed for construction or temporary operations but will not need to be disturbed on a continuing basis. All measures will be taken to disturb the smallest practicable area at any one time. These sites will be qualitatively monitored for at least

the first two years for revegetation success. Remedial action, if necessary, will be determined during the monitoring investigation.

Revegetation methodologies to be used to temporarily stabilize these sites are those listed under Sec. 3.41.22 according to degree of slope angle and accessibility. The seed mixture to be used is presented in Appendix 3-E, entitled Intermediate Seed Mixture - All Areas.

Temporary revegetation will likely entail, at least on a limited basis, stabilization of small, isolated and perhaps irregular disturbances which do not lend themselves to methodologies identified in Sec. 3.41.22. In such cases, revegetation will be completed manually. Grading and seedbed preparation will be completed by raking. ~~Fertilizer will be broadcast by hand. The seedbed will again be raked, disturbing the soil to the maximum depth possible to increase fertilizer incorporation efficiency.~~ Seed will be broadcast by hand and the site raked a second time, lightly, to cover the seed. Straw or hay mulch will then be spread evenly over the site at the approximate rate of 2 t/ac. The straw will then be anchored ~~either by crimping with shovels or tacked plastic netting~~. No irrigation is planned for use on the permit area.

### 3.32 Impacts on Renewable Resources

This is addressed in Section 5.25 of this application.

### 3.33 Fish and Wildlife Plan

Potentially adverse impact on wildlife and related environmental values will be avoided or minimized through the implementation of mitigation measures. The Applicant will operate and maintain all transportation systems and support facilities under their control in a manner that minimized impacts to fish and wildlife. Restoration or enhancement of wildlife habitat on reclaimed areas within the permit area will be achieved where practicable and where it is consistent with the approved post-mining use. The applicant reserves the right to amend the fish and wildlife plan.

Wildlife habitat and range land is the current and predominant land use occurring on and about the LOM permit area. The area presents habitat for a variety of wildlife species normally associated with the semi-arid Great Basin ecoregion. ~~As identified in baseline investigations, more important wildlife inhabiting the area include mule deer, a few raptorial species, an occasion mountain lion, and limited numbers of small game species.~~ Baseline studies determine that no fisheries are present in or around the project area.

Before collecting and stockpiling topsoil, some rock and woody vegetation will be removed and piled in undisturbed areas. These piles will provide cover for small mammals and upland game. Protection from adverse weather and predators is vital to many species of animals and is critical factor in habitat selection by species. These structures also provide perches for songbirds and small raptor species. Perches elevated above surrounding vegetation or providing an extended view of an area are critical to territorial establishment of many breeding songbirds. Actual location of rock and brush piles will be left to the discretion of the Applicant.

#### Timing of Major Disturbances

During May and June, blasting and massive earthwork in the area will be avoided wherever possible from one hour before sunrise and sunset to two hours after sunrise and sunset. These times are critical periods for wildlife during the breeding season.

#### Education of Mine Personnel

An education program will be present in conjunction with the MSHA training program to minimize the potential negative impact of employees upon wildlife. Appropriate communications with employees will describe the rationale of habitat restoration procedure, company hunting policies, penalties for infractions of company policy or state law, and the purpose of reclamation. An awareness of mine employees of their potential impact on wildlife will help prevent or reduce many impacts.

#### Reporting of Threatened or Endangered Species

Reporting of threatened or endangered wildlife is a requirement of OSM and DOGM regulations. If suspected sightings are made, the applicant will contact appropriate state and federal agencies.

#### Impact to Raptor Nests through Subsidence

If significant subsidence occurs, or is about to occur, during the April to July period of any year, a nesting survey will be completed to determine if any nesting raptors are in the potential area of impact. If active nests are found, the Division of Wildlife Resources and DOGM will be notified, so as to ensure that all appropriate actions are taken.

#### Construction of Power Lines

The applicant will request that power lines be constructed per OSM and DOGM regulations in accordance with guidelines set forth in Environmental Criteria for Electric Transmission Systems (USDA, 1970) or with alternate guidelines approved by the regulatory authority. These guidelines are designed to avoid or minimize lethal aspects to songbirds and raptors, which frequently utilize power poles as perch sites.

#### Impact to Livestock and Wildlife Through Subsidence

In the unlikely event that livestock are killed or injured as a result of surface subsidence, the Applicant will adequately compensate said owner. Furthermore, any subsidence caused surface cracks which are of a size or nature to cause injury or death to livestock or wildlife will be repaired by the Applicant.

#### Location and Operation of Haul and Access Roads

Proposed locations of primary and ancillary roads within the permit area have been carefully assessed to determine if they will present significant problems to wildlife. If, after mining activity commences, an area is identified as apparently causing undue mortality to wildlife, then appropriate mitigation measures will be taken such as erecting "deer crossing" signs, or reducing speed limits. UDWR has determined that most of the mule deer wintering in the vicinity of the project area migrate via canyons west of Fish Creek. Only a few animals utilize Fish Creek or Dugout Canyon as migratory routes.

#### Regulation of Firearms and Activity Within Mine Boundaries

State and federal wildlife regulations will be enforced on the Applicant's properties within the permit area.

The presence of unauthorized people and companion animals is prohibited in areas controlled by the Applicant. Harassment of wildlife by excessive observation, disturbance of nesting birds and young animals, and chasing wildlife in vehicles (such as snowmobiles), will be discouraged by the Applicant. The unauthorized use of off-road vehicles on land controlled by the Applicant will be prohibited.

#### Replacement of High Value Habitat

Following mining, revegetation will be primarily concerned with replacing the pre-mining habitats. High value habitats including pinion-juniper, and riparian areas will be restored to pre-mining or better condition.

#### Regulation of Pesticides

~~Efforts will be taken to carefully regulate the use of pesticides when needed to prevent insects from destroying newly established revegetation. These chemicals can have serious consequences to wildlife, therefore, before a pesticide is utilized, the type and the appropriate concentration will be approved by the Regulatory Authority.~~

3.40 Reclamation Plan

3.41 Revegetation Plan

#### Introduction

The following revegetation plan has been developed to address all disturbed areas

requiring reseeding associated with the Soldier Canyon Mine. At the central mine facilities area, this includes all disturbances with the exception of those associated with Soldier Creek Road and the REI properties (Exhibit 5.21-1). At the sewage lagoons area, all disturbances will be revegetated with the exception of the access roads. These roads will be returned to public use and access.

The short-term goal of this revegetation plan is the immediate stabilization of the disturbed sites through erosion control. This objective will be achieved through controlled grading practices, proper seedbed preparation to encourage rapid plant establishments, inclusion of rapidly establishing species in seed mixtures to be planted and mulch applications.

The long-term goals are to establish useful, productive range and wildlife habitat and create an aesthetically acceptable site. These goals will be attained through the selection and placement of desirable and productive plant species, the return of the best available seedbed material to graded areas, and a commitment to monitor and maintain revegetated areas throughout the bond liability period.

#### Material Specifications

The following specifications are presented to identify the quality of materials that will be purchased to complete revegetation activities. All efforts will be made to follow these specifications although deviations may be required depending upon the commercial availability of these materials within the region.

#### Fertilizer

~~All fertilizer materials will be purchased in waterproof or water-resistant bags. Each bag to be marked with the weight and manufacturers guaranteed analysis of the contents showing the percentage of each ingredient contained. No cyanamid compounds will be permitted in mixed fertilizers.~~

#### Commercially Purchased Seed

Seed will be purchased in standard containers with seed name; lot number; percentages of purity, germination, hard seed; and percentages of maximum weed seed content clearly marked for each type of seed. Seed supplies will not contain the seeds of any state-recognized noxious weed species. ~~A certificate stating that each seed lot has been tested by a laboratory with respect to the above requirements should be delivered with the seed.~~

Only certified seed of named varieties will be used where varieties are specified and can be obtained. ~~Sources for "common" seed should be those with climatic and elevational characteristics as close to site characteristics as possible. Legume seed will be inoculated with the correct rhizobium.~~

### Seedlings

All accepted stock will be **bare root or** containerized and true to type and name. ~~All stock will have well-formed tops and root systems will be free from injurious insects and plant diseases. Plants will also be free from: (1) serious abrasions to roots, stems and branches, (2) dried root systems, (3) thin root systems, (4) mold, dry, loose, or damaged soil mass, (5) root-bound conditions, (6) broken or malformed containers, and (7) sun scald, wind, or freezing damage. Seedlings cut back from larger sizes to meet specified sizes will not be accepted. All stock will be "hardened off" prior to shipment so that stock is physiologically prepared for out-planting.~~

### Cuttings

~~Cuttings will be collected from young, actively growing plants free from disease. All cuttings will be of stem material and be approximately 8 to 12 in. long. Stem material, 2 to 4 yrs old at the maximum will be considered acceptable for use. The basal cut will be made immediately below a node.~~

### Straw or Hay Mulch

~~Straw or hay mulch will not be musty, moldy, caked or decayed and will be free of noxious weeds or noxious weed seeds. It will be delivered in an air-dry condition. The majority of stems should be 10 to 12 in. long or longer prior to application when anchoring will be completed by crimping. When anchored by netting or chemical tackifier, a majority of stems should be 6 in. long.~~

### Wood Fiber Mulch (Hydromulch)

~~Wood fiber mulch will be a natural, **shortlong**-fiber product produced from clean, whole wood chips. The fiber should disperse readily in water to form a homogenous slurry. The fiber, dye and any tackifying agent to be used will be non-toxic to plant and animal species. The pH of the fiber material will be greater than 6.0. The mulch will be capable of remaining in uniform suspension in water under agitation. The supplier will be required to deliver mulch in standard manufacturer's packaging.~~

### Erosion Control Matting

~~Matting will be composed of a blanket of interlocking curled wood fibers overlain with polypropylene plastic netting as an integral component of the mat. The matting will be of uniform thickness with curled wood fibers spread evenly over the mat. **Should matting be necessary** components will be not-toxic to vegetation and the blanket smolder-resistant. The matting will not be moldy or decayed. The supplier will deliver the matting in standard manufacturer's packaging.~~

### Plastic Netting and Staples

~~Plastic netting will be composed of black or green polypropylene or other equivalent plastic material that has been extruded to form a net. The netting~~

~~will be purchased in rolls and must show little or no shrinkage after application. Staples will be U-shaped and made of 11 to 12 gage heavy steel wire. Staple lengths should be 6 to 8 in. for use in firm soils and not less than 12 in. for use in loose soils.~~

#### Care of Delivered Materials

All fertilizer, seed and mulch material will be retained in shipping bags until used. These seed materials will be stored in a protected place to prevent them from coming in contact with precipitation or surface water.

Commercially purchased seedlings will be ~~delivered to the site~~ obtained as close to the time of planting as possible. ~~Upon receipt of shipment, plants will be inspected for moisture status and condition. All seedlings will be watered upon arrival. Watering will be repeated every 2 to 4 days as needed following this date until planting. No fertilizer materials will be applied to stored plants.~~ Plants will be stored properly to:

- \* avoid or reduce moisture stress;
- \* avoid excessive heat or cold;
- \* protect plants from wind and mechanical damage, and
- ~~\* provide a staging area for subsequent planting.~~

~~Should the storage of willow cuttings be necessary, cuttings will be placed in a plastic bag with a wet paper towel wrapped around the stem bases to prevent desiccation. Cuttings will be stored under refrigerated conditions for a maximum of 12 hrs.~~

#### 3.41.10 Revegetation Schedule

Revegetation will begin for each site component during the fall planting season following component closure, dismantlement or abandonment. All seeding will be completed by the Applicant during the fall planting season (Table 3.41-1).

#### 3.41.21 Revegetation Seed Mixtures

The following seed mixtures will be used to revegetate areas disturbed by mining and all associated activities. These seed mixtures have been developed for this mine with respect to a number of considerations. The climate of the area was reviewed to assess the need for drought-tolerance in species selected. The vegetation report was evaluated to determine seed mixture constituents in light of production, cover, and diversity requirements. The soils report was reviewed to assess potential seedbed quality, among other things, and select species adapted to these assumed physical and chemical conditions. Plant species appropriate for enhancing wildlife habitat were selected on the basis of known wildlife needs and requirements. In addition, the operations plan was reviewed to determine the need for species with quick establishment, rapid spreading, and

high erosion control potentials. The exact schedule will be determined during the revegetation year.

One temporary and five permanent seed mixtures are listed (Appendix 3-E). The temporary or "Intermediate" mixture will be used on those sites which are to be temporarily reclaimed, such as: topsoil storage areas, temporary road locations and unused disturbances associated with the Soldier Canyon Mine facilities that will be totally reclaimed at the conclusion of operations. Permanent mixtures will be seeded following seedbed preparations at the locations listed below. All grass and forb seed rates are given in lbs/ac pure live seed (PLS) for ~~drill~~ seeding. When the grass and forbs seeds are to be broadcast, the rates will be doubled. Rates for shrub species are given in lbs/ac PLS for broadcasting. ~~Shrub seed will not be drilled.~~ All seeds will be broadcast and/or incorporated with a small amount of mulch and applied by hydroseeding equipment. Hydroseeding will be accomplished in two applications, the first being the application of the seed to the soil and the second an application of mulch and tackifier on top of the seed.

#### 3.41.22-24 Revegetation Methodology

~~The following techniques will be used to revegetate the Soldier Canyon Mine facilities based on the slope angle of the final graded surface. Technique specifications contained herein may be modified as required based on regional equipment and material availability. However, all efforts will be made to follow these specifications. All operations, where possible, will be conducted along the contour. No irrigation is planned for use in the permit area.~~

The area will be graded to final contours, and then ripped to relieve compaction (see Exhibit 7.60-1). Ripping will be completed to a maximum depth of 2 feet. Final ripping depths will be determined by the materials being ripped, to prevent incorporation of less desirable soil/rock into more productive materials.

Following ripping, stockpiled soil will be applied to the ripped surface and left in a extreme roughened state. Prior to seeding, one ton per acre of certified noxious weed free hay will be incorporated by gouging into the soils. Except as noted all areas will be seeded the same.

Soil samples will be collected and sent to the laboratory for analysis to determine if amendments are necessary(see Section 2.43). Nutrients will be applied in a single application. The area will be broadcast fertilized with the recommended fertilizer using a hand held "cyclone-type" seeder in smaller areas, applied in a hydroseeding mixture or with a rotary implement attached to the revegetation tractor in larger areas. Where possible, a ripper equipped tractor or other appropriate equipment will be used to incorporate the fertilizer into the soil. On slopes too steep to accommodate the use of a tractor or other

appropriate equipment the fertilizer will be incorporated with the track hoe bucket teeth or other Division approved technology. All nutrients will be applied in a single application.

On slopes greater than 3:1, the rough, disturbed surface will be treated by traversing a dozer perpendicular to the slope contour to incorporate the nutrients.

All seeds will be broadcast and/or incorporated with a small amount of mulch and applied by hydroseeding equipment.

**Mulching Techniques.** Following seeding, the disturbed areas will be mulched with an organic mulching material. Organic mulch will be applied at the rate of 2000 pounds per acre and anchored with a tackifier.

**Irrigation, Pest and Disease Control.** No irrigation is planned and pesticides will not be used unless previously approved by the Division.

Level to Gentle Slopes (<3:1 or 4:1)

~~The area will be graded to the final contours shown on Exhibit 7.60-1. The graded area will then be ripped to relieve compaction. Ripping will be completed by a dozer equipped with a single or twin set of ripper shanks. Ripping will be completed to a depth of 2 ft or to bedrock on approximately 4 ft centers. Ripping will be completed at a speed which maximizes the action of the ripper shanks and promotes spoil material disruption to the required depth.~~

~~Following ripping, topsoil and substitute topsoil seedbed material will be applied to the ripped surface. Seedbed material samples will then be collected as specified in Sec. 2.43. Samples will be sent to the laboratory for analysis to determine fertilizer requirements.~~

~~Following receipt of fertilizer amendments recommendations, the seedbed will be prepared and the disturbed site fertilized. The disturbed area will be broadcast fertilized using a rotary broadcast implement attached to the revegetation tractor. The seeder will be equipped with a metering device. Fertilizer will be applied at rates commensurate with recommendations resultant from seedbed material sample analysis. All nutrients will be applied in a single application. The most soluble phosphorus fertilizer will be selected for use. A slow-release type fertilizer is preferred for a source of nitrogen. Additionally, fertilizer materials with the lowest salt index obtainable will be selected for use. Fertilizer broadcasting operations will not be conducted when wind velocities would interfere with the even distribution of the material.~~

~~A disc will be attached to the revegetation tractor applying fertilizer. The~~

~~disc will be used to prepare the seedbed for seeding and incorporate the broadcast fertilizer into the soil. Offset disc implements will be preferred for use.~~

~~When fertilizers have been applied and the seedbed is prepared, the area will be seeded. Seeding for grasses, shrubs and forbs will be accomplished by broadcast/hydroseeding drilling. Shrub seed will be broadcast in conjunction with drill seeding. Drilling will be completed using a drill implement preferably equipped with the following features.~~

- ~~\_\_\_\_\_ \* depth bands (to allow seeding at the proper depth),~~
- ~~\_\_\_\_\_ \* seedbox agitator (to promote thorough seed mixing during planting),~~
- ~~\_\_\_\_\_ \* seedbox baffles (to aid in even seed distribution among rows),~~
- ~~\_\_\_\_\_ \* seed metering device (to promote even seed distribution within rows),~~
- ~~\_\_\_\_\_ \* furrow openers (to permit proper seed placement from seed spouts (single disc or hoe openers preferred), and~~
- ~~\_\_\_\_\_ \* drag chains (to aid in seed coverage).~~

~~A rangeland drill will be preferred for use if available. To complete the drilling operation, seed boxes will be loaded with the seed mixture and the seeding rate calibrated. Rice hulls or other inert material can be added to the mixture to promote the proper seeding rate. The drill will be adjusted to plant the seed to a depth of approximately 0.5 in. Drill rows spacing will be set at 8 in. The drill will then be towed across the prepared seedbed to complete the planting operation.~~

~~To complete shrub seed broadcasting, a rotary broadcast seeder will be mounted on the tractor/drill equipment. The seeder will be equipped with a metering device. Shrub seed will be broadcast in conjunction with seed drilling. Drag chains attached to the rear of the drill will lightly cover the broadcast shrub seed with topsoil. All efforts will be made to attain an even distribution of seed.~~

~~Following seeding, the disturbed area will be mulched, with straw or hay. Straw will be spread in an even manner over the site to be mulched by hand or mechanical spreader. When working over slopes, application will be initiated at the top of the slope, working downhill. Straw will not be spread when wind velocities would prohibit even distribution. Mulch will be applied at the rate of approximately 2t/ac.~~

~~Mulch will be anchored by crimping. Crimping will be completed by using discs with dull and preferably notched, round-edged blades. (Commercial-type mulch~~

~~crimpers are also acceptable for use if available.) Crimping will be completed by traversing the mulched area and anchoring the mulch, by rows, 2 to 4 in. into the soil.~~

Steep Slopes (>3:1 or 4:1)

~~The slopes will be graded to the final contours shown on Exhibit 7.60-1 and ripped on the contour to relieve compaction. Where contour ripping is not possible due to slope degree or size of disturbed area, this technique will be omitted. A dozer equipped with single or twin ripper shanks will complete ripping to a depth of 2 ft or bedrock, whichever is shallower, on approximately 4-ft centers.~~

~~The surface will be left in a roughened condition. Sampling of seedbed material (see Section 2.43 for methodology) will then be completed and the samples sent to a laboratory for analysis and fertilizer recommendations.~~

~~Following receipt of fertilizer recommendations, fertilizer will be broadcast over the disturbed surface. Fertilizer will be broadcast using hand-operated "cyclone-type" seeders or rotary broadcast equipment attached to construction or revegetation machinery. Broadcasting by hand will be completed on small, isolated sites. All equipment used will be equipped with metering devices. Broadcasting will not be conducted when wind velocities would interfere with even material distribution. Fertilizer will be applied at rates commensurate with sample analysis recommendations. All nutrients will be applied in a single application. The most soluble phosphorus fertilizer material available will be selected for use. As a source of nitrogen, a slow release form will be preferred. Fertilizer materials with the lowest salt index obtainable will be broadcast.~~

~~Immediately following fertilizing the seedbed will be broadcast seeded. Broadcast seeding will be accomplished using hand-operated "cyclone-type" seeders or rotary broadcast equipment attached to construction or revegetation machinery. All machinery used will be equipped with metering devices. Broadcasting by hand will be acceptable on small isolated sites. When broadcast seeding, passes will be made over the site to be seeded such that an even distribution of seed is attained. When using hopper-type equipment, seed will be frequently mixed within the hopper to hamper seed settling and uneven planting distribution of species. Broadcast seeding will not be conducted when wind velocities would prohibit even seed distribution. (On lesser slopes a drag may be pulled across the slope, along the contour, to cover the seed.)~~

~~The rough, seeded disturbed surface will be treated by dozer tracking to incorporate the fertilizer and seeds into the seedbed. This technique is considered an acceptable technique for steep slopes inaccessible to agricultural~~

~~machinery. Dozer tracking will be accomplished by traversing a dozer perpendicular to the slope contour over the graded slope such that the imprint of track cleats are formed parallel to the slope contour. Dozer tracking will be considered successfully completed when  $\geq 85\%$  of the site exhibits the surface configuration resultant from this technique. (Lesser slopes may be treated following seeding by pulling a drag across the slope along the contour.)~~

~~Straw or hay mulch at a rate of 2t/ac will be spread over the disturbed site following seeding. Mulch will be spread in an even manner over the site by hand or mechanical blower. When spreading over slopes, application will be initiated at the top of the slope, working downhill, where possible. Straw will not be spread when wind velocities would prohibit even distribution.~~

~~Plastic netting will be used to anchor applied straw mulch on these slopes. Netting will be applied immediately following mulch application in the following manner. All rock and debris that would inhibit proper netting installation will be removed from the slope prior to mulching. The netting will be applied over the straw smoothly but loosely, without stretching, from the top to the bottom of the slope. The top edge of the netting will be buried in a narrow trench 6 in. deep with staples anchoring the netting within the trench. Where netting ends meet, the upslope end will overlap the downslope end by approximately 4 in. Where lateral roll edges meet, an overlap from either side of 4 in. will be made. Staples will be inserted on a 1 ft spacing along the top and bottom ends of the netting. Staples will be inserted every 4 ft down each edge and the center of the netting so that staples alternate between edges and the center to form an x-shaped pattern. All staples will be inserted flush with the seedbed.~~

#### Revegetation Methodology - Topsoil Storage Site/Sewage Lagoons Area

~~Methodologies used to revegetate these disturbed areas will parallel those used to revegetate the central mine facilities area according to slope resultant from final grading. All operations, to the extent possible, will be conducted along the slope contour.~~

~~As shown in Exhibit 5.42-3 the proposed final slopes of the topsoil stockpile area and sewage lagoons are  $\leq 3:1$  or  $4:1$  (Exhibit 5.42-2). There is no topsoil stockpile at the sewage lagoons because the topsoil was utilized in the embankments. Therefore these sites will be revegetated using the methods and technique sequence described in for Level to Gentle Slopes ( $<3:1$  or  $4:1$ ) immediately following topsoil redistribution and dismantling of the lagoons. No irrigation is planned for use on the permit area.~~

#### Revegetation Methodology - Refuse Disposal Site

~~Due to the incremental nature of the refuse pile construction, as described in section 5.28 of this application, the revegetation of the reclaimed section of the refuse pile will, also, be conducted in an incremental manner. Revegetation for each site component will be conducted during the fall planting season following segment closure, as indicated in Table 3.41-1. All seeding on a given segment will be completed by the Applicant during the fall planting season, while cutting and seedling planting will be conducted in the spring of the following year.~~

~~Reclamation of the final disturbance will be conducted according to the slope angle of the final graded surface. This reclamation activity shall include: regrading and covering of the final refuse pile segment, construction of the intermediate sections of the reclaimed channels, and removal of the access road and culverts.~~

~~The sedimentation pond shall remain in place until adequate vegetative cover is established. Following the establishment of this cover, the pond will be removed and the area will be regraded and the final section of reclaimed stream channels will be constructed and protected. No irrigation is planned for use on the permit area.~~

#### Revegetation Methodology - Riparian Area

The riparian zone to be reclaimed on the mine site exists at the central mine facilities area and covers approximately 2.4 ac. The area will be graded, resoiled, sampled, fertilized, seeded and mulched. ~~as cited under Steep Slopes (>3:1 or 4:1).~~ The need for ripping will be assessed at the time of revegetation. ~~(Ripping is included in bond calculations for the purposes of this plan.)~~ The seed mixture to be planted is listed under Sec. 3.41.21. In addition, willow (Salix) and cottonwood (Populus) ~~cuttings along with cottonwood seedlings~~ will be planted. Figure 3.41-1 depicts typical ~~cutting and seedling planting plan layout site locations.~~ **Cuttings/transplants/seedlings** will be planted in the following manner.

**Seedlings/transplants will be planted by first clearing a circle of 12 to 24 inches in diameter from which mulch materials and grasses will be cleared. The hole will be dug 4 to 6 inches deeper than the seedling roots to accommodate positioning of the seedling. Fertilizer will either be mixed with the loose soil from the hole or a fertilizer tablet will be planted with each seedling. After seedling placement, the hole will be backfilled with soil and fertilizer then lightly tamped. A gently sloped basin will be formed around the seedling to catch water. The basin will be mulched to aid in moisture retention.**

~~Cuttings will be collected immediately prior to planting. Cuttings will be~~

~~planted through the applied mulch by pushing the proximal end of the cutting into the soil so that the majority of the stem is inserted below the ground line. Ideally, 1 to 2 in. of the cutting will be above the surface of the seedbed. The proximal end of the cutting will be dusted with indolebutyric acid (IBA) prior to planting to aid in root formation.~~

~~Seedling planting will occur following mulch anchoring. Seedling planting will occur during early spring, after ground thaw.~~

~~At each individual planting site, a circular area (planting circle) will be cleared of mulch materials or inhibiting debris. The size of the circle will be approximately 12 in. in diameter. The receiving hole will then be dug with the depth of the hole extending 2 to 4 in. deeper than necessary for planting. The hole will be of sufficient size to allow positioning the seedling and tamping the backfill. After the hole has been formed, it will be partially backfilled with loose soil to allow planting at the proper depth. (A small amount of phosphorus fertilizer can be mixed with the backfill materials, at the supervisor's discretion, considering the amount previously applied during broadcast fertilization). The seedling will then be place in the hole and the hole one-half backfilled. The hole will then be filled with water and the remainder of the seedbed material backfilled into the hole as rapidly as possible without displacing water from the hole. The backfill will be firmly tamped around the seedling. Planting will be accomplished to the same depth as the seedling was grown in the container.~~

~~A basin, which slopes gently from the outside of the planting circle to the seedling stem, will be formed of seedbed material to aid in water catchment and retention. The surrounding mulch will be respread over the planting area and anchored with gravel and seedbed material. Planting holes may be dug by hand or power auger. No irrigation is planned for use on the permit area.~~

#### 3.41.25 Reference Areas

~~Three reference areas (Exhibits 3.7-2 and 3.7-3/Map A), established in undisturbed near-natural conditions, and adjacent to existing or future mine operations are described in Appendices 3-A and 3-B of this application. These reference areas, under proper management, are designed to facilitate the determination of successful revegetation and resultant final bond release for the Applicant.~~

#### Revegetation and Stabilization Success Determination

As identified within the revegetation plan, the Applicant will stabilize and revegetate sites disturbed by mine related activities. Rangeland is the primary

mixtures planted, and the approved postmining land use. This evaluation of species composition/diversity is necessarily a subjective analysis as the state-of-the art revegetation planning and success determination presented in this application does not lend itself to a purely quantitative evaluation. As technology advances over the years, diversity testing may become more quantitative and at such time the Applicant will, if appropriate, attempt to include these techniques in the revegetation success determination. Presently, approved quantitative measures are shown in Appendix B of the Division's "Vegetative Information and Monitoring Guidelines." Therefore, the evaluation of species diversity of a reclaimed area up for release of bond will be based on a review of cover data obtained in response to the testing program identified above. These data will be evaluated in terms of: richness (number of species present); evenness (relative contribution of each species to the community); the ability and potential of reclaimed species to perpetuate themselves: the influence of volunteer species; and the capability of the reclaimed community to support the postmining land use.

Also, at the point of requesting interim bond release, the Applicant will show that revegetated lands are capable of supporting the postmining land use of rangeland if the postmining landowners intend to graze livestock. Otherwise, proof that revegetated areas can sustain grazing pressure will be unnecessary. To show this capability, newly revegetated areas will be subjected to grazing at properly controlled levels prior to the implementation of the previously discussed qualitative and quantitative evaluations of revegetation success.

Livestock will be introduced onto newly revegetated land only when it is able to sustain the impact. This determination will be made by a qualified range ecologist and is anticipated to occur between years 3 and 8 of the 10 year responsibility period. ~~If grazing is allowed too soon or occurs at too great an intensity, the delicate early successional community may lose significant diversity, cover and productivity.~~

~~Because newly revegetated areas are early successional communities, they must be treated carefully. Grazing during the 10 year responsibility period cannot be as intense as grazing on mature climax communities. Therefore, if grazing is to occur on revegetated areas, the intensity will be determined as follows:~~

~~FIRST - The productivity of reclaimed vegetation will be determined by species in an unbiased manner.~~

~~SECOND - The productivity values for each species will be adjusted by a percentage utilization factor based on currently published research or accepted standards. These utilization factors will take into account accepted harvest levels such that vigor and reproduction potential of each species is not~~

~~adversely affected.~~

~~THIRD — The total useable production will be calculated on a pounds per acre basis to give a total carrying capacity figure.~~

~~FOURTH — The stocking rate will then be determined by allowing one Animal Unit Month (AUM) per 800 lbs of useable production.~~

~~FIFTH — Because of the early successional status of newly reclaimed vegetation and its susceptibility to adverse impact due to grazing, the stocking rate determined in step four above will be reduced by 50%.~~

~~Once proper grazing intensity is determined, the timing of grazing becomes important. Livestock will be allowed to graze revegetated communities only during those periods of the year when the vegetation can absorb the impact. In addition, the grazing rotation will allow each area to be "rested" every third year.~~

#### Monitoring of Reclaimed Areas Prior to Bond Release

Prior to bond release success determination, reclaimed areas will be monitored to determine seedling survivability and the general success of revegetation efforts. Such monitoring will be performed during years 1, 2, 3, and 5 of the bond responsibility period, and will provide information with respect to whether or not remedial action will be necessary. Monitoring will consist of a mixture of qualitative observations and quantitative measurements during these four years.

During the first year, only qualitative observations will be made except for the determination of seedling survival in the area to be reclaimed to riparian vegetation. Qualitative observations will consist of an ocular evaluation of seeding success. All areas not exhibiting planted species establishment will be identified for future evaluation and possible remedial treatment. Areas exhibiting extensive noxious weed establishment will be identified for immediate remedial treatment. Within the 2.4 ac area to be reclaimed to riparian vegetation as many of the planted seedlings as can be found will be examined to determine whether or not they have survived the first season. All remaining live plants will be enumerated and a wood stake driven beside the first 50 plants. Only these 50 plants will be checked in the three subsequent monitoring years.

During the second, third, and fifth years of the bond responsibility period the 50 marked riparian seedlings will be revisited to determine survival and vigor. Information collected in this manner will allow an evaluation of overall seedling survivability and whether remedial action will be necessary for reestablishing

woody plant density. If, during year one, any areas were found without planted species establishment (barren areas), they will again be visited. If these areas are still barren or exhibit noxious weed growth, they will be identified for immediate remedial treatment. Following these less formal evaluations, a quantitative technique will be employed to determine whether or not adequate ground cover is reestablishing. During each of the last three monitoring years 10 permanent cover transects within each revegetated community will be measured for ground cover. These transects will involve the point-intercept technique (100 intercepts per transect) and data will indicate ground cover by species. Data collected in this manner will allow tracking of revegetation establishment over time and allow a projection of potential revegetation success. If poor establishment becomes apparent from review of this data, remedial action can occur.

Monitoring of Field Trial Sites

To determine the revegetation potential of the project area following decommissioning of the mine, the applicant established three field trial sites about the mine area. The first site was established immediately east of the sewage lagoon during the fall of 1982. The second site was established on the down slope of the R.E.I. storage area (topsoil stockpile) during the early fall of 1982. The third and last site was established on the north side of the new exhaust fan and substation site during the late spring of 1984. These sites are indicated on Exhibit 5.21-1 and 5.42-2.

The details of establishment, seedbed preparation, topsoil application, seed mix used, method of seeding, type and rate of mulching, type of protection, etc., are indicated below for each field trial site. *Per faxed memo dated Oct 18, 1993, Paul Baker, UDOGM - monitoring of Fan Site Test Plot discontinued 1994, Sewage Lagoon and Topsoil Storage Area Test Plots, discontinued 1997.*

Sewage Lagoon Field Trial

- 1) Established - Fall 1982 (approximately 0.7 ac)
- 2) Seedbed preparation - Regrading by dozer (uncompacted soil depth 3-9")
- 3) Topsoil application - None (in place material used)
- 4) Seed mix used (as approved by BLM)

Grasses	-	Western Wheatgrass	1.5 #PLS
		Indian Ricegrass	1.5
		Crested Wheatgrass	1.5
Forbs	-	Yellow Sweetclover	1.0
		Utah Sweetvetch	0.5
		Ranger Alfalfa	1.0

	Small Burnet	1.0
Shrubs	- True Mountain Mahogany	1.0
	Utah Serviceberry	0.5
	Fourwing Saltbush	<u>2.0</u>
		11.5

- 5) Method of seeding - Drill seeding
- 6) Type and rate of mulch used - None
- 7) Type and rate of fertilizer used - Ammonium nitrate @100 lbs/ac
- 8) Type of protection - None
- 9) Monitoring occurrence - mid-July 1983, 1984, 1985, 1986, 1987, 1992, 1997, ..., ~~(repeated every 5 yrs throughout the life of the trial).~~

#### Topsoil Stockpile Site Field Trial

- 1) Established - Early Fall 1982 (approximately 0.1 ac)
- 2) Seedbed preparation - Stockpiled by loader (uncompacted soil depth 6-12")
- 3) Topsoil application - Entire trial site topsoil
- 4) Seed mix used (as approved by OGM)

Grasses	- Western Wheatgrass	3.0 #PLS
	Intermediate Wheatgrass	4.0
	Crested Wheatgrass	3.0
	Orchard Grass	4.0
	Smooth Brome	2.0
Forbs	- Yellow Sweetclover	2.0
	Ranger Alfalfa	<u>1.0</u>
		19.0

- 5) Method of seeding - Hand broadcast and raking
- 6) Type and rate of mulch used - Straw crimped into soil @2 t/ac and netted with jute matting stapled into soil
- 7) Type and rate of fertilizer used - None
- 8) Type of protection - Berming with straw bales
- 9) Monitoring occurrence - mid-July 1983, 1984, 1985, 1986, 1987, 1992, 1997, ..., ~~(repeated every 5 yrs throughout the life of the trial).~~

#### New Fan Site Field Trial

- 1) Established - Late Spring 1984 (approximately 0.1 ac)
- 2) Seedbed preparation - Material disturbed during fan construction (uncompacted soil depth 6")

- 3) Topsoil application - Entire trial site topsoil substitute material
- 4) Seed mix used (as developed by the applicant)

Grasses	-	Western Wheatgrass	2.0 #PLS
		Bluebunch Wheatgrass	2.0
		Crested Wheatgrass	4.0
		Great Basin Wildrye	2.0
Forbs	-	Yellow Sweetclover	1.0
		Lewis Flax	1.0
		Ladak Alfalfa	1.0
		Small Burnet	1.0
		Globemallow	1.0
Shrubs	-	Bitterbrush	2.0
		Rabbitbrush	1.0
		Mountain Big Sagebrush	1.0
		Fourwing Saltbush	<u>2.0</u>
			21.0

- 5) Method of seeding - Hand broadcast and raking
- 6) Type and rate of mulch used - Straw crimped into soil @2 t/ac
- 7) Type and rate of fertilizer used - 40 lbs/ac sulfur coated urea 45-0-0, 30 lbs/ac treble super phosphate 0-46-0
- 8) Type of protection - Fencing
- 9) Monitoring occurrence - mid-July 1985, 1986, 1987, 1989, 1994, 1999-  
~~...., (repeated every 5 yrs throughout the life of the trial).~~

A stipulation on the previous Soldier Canyon permit (ACT/007/018) required periodic monitoring of revegetated test plots located at various sites about the operation. A letter from J.T. Paluso, to D. Wayne Hedberg, Permit Supervisor for the OGM, September 25, 1984 identified the details and methodology to be used for this monitoring program. However, after review of these methods during the repermitting efforts, the Applicant has opted to upgrade the methodology in 1986 and thereafter, to provide more meaningful information. The upgraded methodology was verbally approved by OGM representatives (Lynn Kunzler on October 28, 1985, and Holland Shepherd on July 8, 1986) prior to use during the 1986 sampling season. Details of this upgraded methodology (and where it differs from the previous methods) are presented below.

1) The field trial study sites will be monitored from early to mid-July of the first, second, third, and fifth years and every fifth year after the initial planting season for the life of the field trial site. A report with the results of the monitoring will be submitted to OGM at the end of each monitored year. These reports will be appended to this sub-section of the application.

2) All sites will be systematically sampled (not randomly as previously

performed) along 10 permanent transects of 10 m length. These permanent transects are marked at the three field trial sites with No. 4 rebar driven into the ground at each end of each transect.

3) Cover by species is determined by placing a pin frame (10 pins at 10 cm intervals) along each transect at each meter interval. First contacts by each pin are recorded as well as all subsequent contacts as the pin is lowered through the vegetation canopy. All contacts are utilized to determine total cover by species, while only the first contact is utilized to determine total floral cover, litter cover, rock cover and bare ground exposure.

4) Woody plant density will be determined as in previous years - by totally enumerating all plants within the field trial site. Woody plants on the sewage lagoon trial site will only be enumerated in the 35 x 45 ft site which contains the 10 permanent transects.

5) Estimated site productivity will be performed by estimating the total amount of production in pounds per acre by life form (as opposed to estimating production for each species) for the entire trial site. This estimate after 1986 will be performed solely by representatives of the SCS.

Monitoring data (1985) from the field trial sites and riparian reference area using the old monitoring methods are presented in Illustration 3-1. This information was forwarded to OGM in October, 1985. Monitoring data collected in 1986 and subsequent years from the field trial sites using the upgraded methods are presented in Table 3.41-2.

### 3.42 Fish and Wildlife Requirements

The fish and wildlife control plan is a set of specifications and procedures to avoid potential adverse impacts to wildlife and their habitat.

Following mining, revegetation will be primarily concerned with replacing the pre-mining habitats. High value habitats (~~pinion-juniper, agricultural and riparian areas~~) will be restored; ~~in many cases, they will be enhanced beyond their pre-mining condition.~~

#### 3.42.10 Enhancement Measures Used During the Reclamation and Postmining Phase

The Applicant proposes to restore the Soldier Creek stream channel and riparian vegetation, established vegetation for wildlife food and cover, place large landscape boulders for use as shelter and perches.

3.42.20 Plant Species used for Habitat for Reclaimed Areas

The goals of the Applicant are to establish useful, productive range and wildlife habitat and create an aesthetically acceptable site. These goals will be attained through the selection and placement of desirable and productive plant species, the return of the best available seedbed material to graded areas, and a commitment to monitor and maintain revegetated areas throughout the bond liability period.

~~The seed mixtures to be used are located in Appendix 3-E.~~

3.42.30 Cropland Postmining Land Use

~~Soil and land use investigations indicate that an area adjacent to the proposed refuse disposal area could be considered cropland (Appendix 2B). Most of the cropland in the area requires irrigation and is used for growing feed crops for cattle and sheep. There are not any croplands within the Applicants existing or proposed permit area. Therefore, crop production is not one of the proposed postmining land uses.~~

3.42.40 Residential, Public Service or Industrial Postmining Land Use

Due to limitations imposed by topography, climate, soil conditions, inadequate water supply and other natural features, use of the land within the area has been limited primarily to livestock grazing, wildlife habitat and outdoor recreational activities.

3.50 Performance Standards

3.51 General Requirements

~~Soldier Creek Coal Company (SC<sup>C</sup>) commits to conduct all operations associated with the proposed refuse disposal area in accordance with the plans submitted in sections R614-301-330 through R614-301-340 of the permit application. Additionally, SC<sup>C</sup> feels that the plans in sections 3.30 through 3.42 comply with the revegetation and wildlife protection performance standards as indicated in R61445-301-353. through -358.~~

3.52 Contemporaneous Reclamation

~~As described in sections 3.41.10 and 5.28, SC<sup>C</sup> will reclaim each completed segment of the refuse pile on a contemporaneous basis. This will result in a minimal disturbed area during the life of the facility.~~

No contemporaneous reclamation is planned, except the 10 X 20 foot area north of the No.2 Fan.

3.53                    Revegetation: General Requirements

SC<sup>3</sup> will establish on regraded and all other disturbed areas, vegetation cover that is in accordance with the approved permit and reclamation plan.

3.53.10                Vegetative Cover

The vegetative cover will be diverse, effective and permanent. **Refer to Section 3.41.21 for additional information.** ~~The seed mixtures for the area were selected with respect to a number of considerations. The climate of the area was reviewed to assess the need for drought tolerance in species selected. The vegetation report was evaluated to determine seed mixture constituents in light of production, cover, and diversity requirements. The soils report was reviewed to assess potential seedbed quality and select species adapted to these assumed physical and chemical conditions. In addition, the operations plan was reviewed to determine the need for species with quick establishment, rapid spreading, and high erosion control potentials.~~

3.53.12                Comprised of Native Plant Species

The revegetation species will be comprised of species native to the area and purchased from suppliers who will certify their percentages of purity, germination, hard seed; and percentages of maximum weed seed content. ~~Seed supplies will not contain the seeds of any state-recognized noxious weed species. A certificate stating that each seed lot has been tested by a laboratory with respect to the above requirements should be delivered with the seeds.~~

~~Only certified seed of named varieties will be used where varieties are specified and can be obtained. Sources for "common" seed should be those with climatic and elevation characteristics as close to site characteristics as possible. Legume seed will be inoculated with the correct rhizobium.~~

3.53.13                Equal in Cover to Natural Vegetation

The revegetation species will be equal or greater than the natural cover of the surrounding area. ~~Reference areas, under proper management, are designed to facilitate the determination of successful revegetation. The testing parameters for equal cover are discussed in Section 3.41.25.~~

3.53.14                Revegetation Stabilizing Capabilities

The operations plan was reviewed to determine the need for species with quick establishment, rapid spreading, and high erosion control potentials. Species were chosen specifically for their high erosion control potentials.

3.53.20 Reestablished Plant Species

The Applicant proposes to return the disturbed land to the general land uses of the area (rangeland, wildlife habitat and recreational use). This will be accomplished by reestablishing the original vegetation (See Section 3.41.21). The vegetation will be similar if not identical to the original vegetation (unless specified otherwise). The revegetation species will have the same growing season as the adjacent areas.

~~SE<sup>2</sup> will meet the requirements concerning applicable Utah and federal seed, poisonous and noxious plant and introduced species laws or regulations.~~

3.54 Revegetation: Timing

The applicant will follow the recommended guidelines for revegetation as discussed in Section 3.41.10.

3.55 Revegetation: Mulching and Other Soil Stabilization Practices

Mulching techniques are found in Section 3.41 and 3.41.23. Soil will be stabilized using the "intermediate" seed mixture in Section 3.31.

3.56 Revegetation: Standards for Success

The standard for revegetation success are detailed in Section 3.41.25.

3.56.10 Reference Area Coverage and Effectiveness for Postmining Land Use

Refer to Section 3.53.

3.56.20 Application of Standards for Success

Prior to bond release success determination, reclaimed areas will be monitored to determine seedling survivability and the general success of revegetation efforts. Such monitoring will be performed during years 1, 2, 3, and 5 of the bond responsibility period, and will provide information with respect to whether or not remedial action will be necessary. Refer to Section 3.41.25, subsection entitled "Monitoring of Reclaimed Areas Prior to Bond Release" for additional information. ~~Monitoring will consist of a mixture of qualitative observations and quantitative measurements during these four years.~~

~~During the first year, only qualitative observations will be made except for determination of seedling survival. Qualitative observations will consist of an ocular evaluation of seeding success. All areas not exhibiting planted species~~

~~establishment will be identified for future evaluation and possible remedial treatment. Areas exhibiting extensive noxious weed establishment will be identified for immediate remedial treatment.~~

~~During the second, third, and fifth year areas that were found lacking planted species establishment during the first year will be revisited. If these areas are still barren or exhibit noxious weed growth, they will be identified for immediate remedial treatment. Following these less formal evaluations, a quantitative technique will be employed to determine whether or not adequate ground cover is reestablishing. During each of the last three monitoring years, ten permanent cover transects within each revegetated community will be measure for ground cover. These transects will involve the point intercept techniques (100 intercepts per transect) and data will indicate ground cover by species. Data collected in this manner will allow tracking of revegetation establishment over time and allow a projection of potential revegetation success. If poor establishment becomes apparent from review of these data, remedial action can occur.~~

Standards of success will be met in accordance with the approved postmining land use. Any area which was previously disturbed will be revegetated in accordance with Utah Coal Mining Regulations.

#### 3.56.30 Siltation Structures

Siltation structures will remain in place until removal is authorized by the Division, but no sooner than two years after the last augmented seeding.

#### 3.56.40 Siltation Structure Revegetation

Revegetation will occur following the removal of all siltation structures in accordance with the reclamation plan R61#45-301-353 through R61#45-301-357.

#### 3.57 Revegetation: Extended Responsibility Period

SC<sup>3</sup> commits to provide extended responsibility for a period of ten years following reclamation and will submit *if necessary*, a detailed plan for extended responsibility three years prior to the planned cessation of operations.

#### 3.58 Protection of Fish, Wildlife, and Related Environmental Values

SC<sup>3</sup> will minimize disturbances and adverse impacts on fish, wildlife and related environment as outlined in Section 3.33.

#### 3.58.10 Endangered or Threatened Species

## Chapter 2

### SOILS {R614-301-200}

#### 2.10

##### Introduction

This chapter presents soil resource data and soil mapping for the Soldier Canyon Mine. The information has been compiled from the previously approved soil sections for the Sage Point-Dugout Canyon and Soldier Canyon Mine, ACT/007/009 and ACT/007/018, respectively, as well as new soil survey information for the nonpermitted permit boundary expansion. Soil studies were conducted in accordance with guidelines issued by the Utah Division of Oil, Gas and Mining (DOG M) which were in effect at the time each study was conducted. All surveys fulfilled the requirements established by the Soil Conservation Service (SCS). However, developmental plans for future disturbances, unless exempted by the R645 rules, will meet the standards of the National Cooperative Soil Survey and analyzed by horizon according to Table 1 of the Division's "Guidelines" for topsoil.

Mapping and data from these surveys were combined onto one final base map and report for this application to identify the locations, characteristics and areal extent of endemic soil resources within the life of mine (LOM) area at the Order III level (Exhibit 2.22-1). Soil sampling information, collected for the Soldier Canyon Mine permit application, is presented on a site-specific basis with regard to existing or proposed disturbances.

Soil resources affected by the surface facilities expansion and county road relocation, and topsoil storage site, were thoroughly evaluated by EarthFax Engineering, Inc., and the SCS. Their reports are presented in this chapter or referred to in the text. In areas not affected by any surface disturbance, only an Order III survey was conducted.

The Applicant will present, in this chapter, a description of the permining soil resources as specified under R614-301-221. Topsoil and subsoil to be saved under R614-301-232 will be separately removed and segregated from other material.

## 2.20 Environmental Description

### Central Mine Facilities

The central mine facilities are located in Sections 18 and 7, Township 13 South, Range 12 East, S.L.B & M. The mining activities are conducted within 100 feet of the Soldier Creek Road and are within the Soldier Creek Stream buffer zone. The elevation is 6700 to 6850 MSL and the soil range type is mountain loam.

The slopes in this area range from 10% to >60%. Vegetation varies from a deciduous community along the stream channel to a mountain brush community. As shown on Exhibit (2.22-2), much of the soil resources in this area had been previously disturbed through coal mining and exploration activities, county and road development, and the installation of a gas pipeline.

### Topsoil Storage Site

This site is located in Section 25, T13S, R11E, S.L.B & M. This site is located just west, within 100 feet of the Soldier Creek Road right-of-way and approximately 2.5 miles south of the central mine facilities (Exhibit 5.21-2). The site area is located on a small gentle sloped bench at an approximate elevation of 6200 MSL (Appendix 2-A). Vegetation in the site area consists of a sagebrush-grass community (Exhibit 3.7-3/Map A). The sagebrush-grass community has a cover of approximately 35 percent. Refer to Appendix 2-F for information pertaining to the expansion of the storage area.

## 2.21 Prime Farmland Investigation

Soil mapping was completed for the proposed LOM permit area and the resultant data forwarded to the SCS office in Salt Lake City, Utah. This information was reviewed by SCS personnel and a negative determination was given with regard to the prime farmland status of the soils overlying the proposed LOM area. A copy of this letter is presented in Appendix 2-B.

In addition, the Soil Conservation Service indicated that a small area of irrigated Prime Farmland exists within the NE 1/4 of the NE 1/4 of Section 36, T13S, R11E. The attached map (Appendix 2-B) shows that the area is located south of the LOM area.

## 2.22 Soil Survey

A map (Exhibit 2.22-1) delineating the different soils at an Order III level was drawn showing the areal extent of the endemic soil resources within the life of mine (LOM). Supplemental field investigations were also conducted for the

facilities expansion, and topsoil storage site as required by the Division. These reports will supplement the existing soils report and supply baseline information for undisturbed areas that the Applicant is proposing to disturb.

With respect to the area encompassed by this proposed LOM permit, three seedbed material (topsoil, substitute topsoil and previously disturbed subgrade material) sampling efforts have been completed. Sixteen samples of soil and disturbed materials were collected and analyzed as a part of the original Soldier Canyon Mine permit document (ACT/007/018). The raw data results from the initial mine sampling program is shown in Table 2.22-1 with soil locations shown on Exhibits 3.7-2 and 5.21-1. These soils were analyzed at Utah State University's Soil Laboratory, an approved soils and agricultural laboratory.

With regard to Table 2.22-1 sample number 1 was taken from the existing soil stockpile. Sample 2 was collected from the sediment pond storage pad fill while samples 3 and 4 were from undisturbed soils bordering the sediment pond. Samples 5, 6 and 11 were taken from the parking lot fill and samples 7, 8 and 9 were from the upper storage area. Sample 10 was collected from the crib wall. Samples 12, 13 and 14 were collected from the sewage lagoon site. Samples 15 and 16 were collected at the No. 2 fan site. These samples were analyzed for percent organic matter, saturation percentage, pH, electrical conductivity, sodium adsorption ratio, available water capacity, texture, percent coarse fragments (> 2 mm), moist consistency, and water erodability (K-factor).

All samples collected for the Soldier Canyon Mine proper were rated "good" in terms of saturation percentage, sodium adsorption ratio, texture, and water erodibility. Sample suitability for the percent organic matter and electrical conductivity parameters ranged from "good" to "fair" with the majority of samples in the "good" category for both parameters. The higher organic matter values for some of the disturbed seedbed materials were likely due to the inclusion of coal fines. The pH values of all samples collected were "fair" except for the crib wall sample which was rated "good". Similarly, available water capacity was rated "fair" for all samples but one which was rated "poor". The "poor" rating was from a soil sample taken from the fan site. The value was 4.8 which is slightly under the lowest possible "fair" (5.0) rating. Coarse fragment content values ranged from "poor" to "good". Three of the 16 samples taken were in the "poor" category. These samples were collected from the parking lot, upper storage area, and crib wall. The ratings for the moist consistency parameter ranged from "fair" to "good" with the majority of samples rated as "good". These sampling efforts indicate that potential revegetation problems linked to soil characteristics are limited. High coarse fragment content of certain soils associated with disturbed mine facility sites is the most obvious concern at the

mine proper. This condition, however, is not wide-spread and can be mitigated through the proper application of revegetation techniques and the selection of species to be planted. The predominance of "fair" ratings for the pH and available water capacity parameters is also notable. These ratings are not considered to be detrimental in terms of limiting revegetation success. Native plant species adapted to these conditions can be used to overcome secondary pH and available water capacity limitations. The use of sulfur-coated urea fertilizer may aid in reducing pH values to somewhat lower levels.

#### Central Mine Facilities

During the permitting of the surface facilities expansion, county road relocation, culvert installation, and new portal development, additional soil investigations were conducted to further characterize the physical and chemical characteristics of the soils. Table 2.22-2 lists the location, date, identification number or field evaluation, and the report (Illustration) pertaining to each investigation.

#### Topsoil Storage Site

The initial field exploration program, conducted in May, 1990, consisted of a detailed inspection of the site to evaluate topographic relief, vegetation type and percent cover, surficial evidence of soil distribution and exploration of Old Test-Pits 1, 2, 3 & 4 (OTP 1-4) (Figure 1, App. 2-A) to provide a detailed log of the soil profile for each series present and collection of representative samples from each series for laboratory analysis. A supplemental field investigation was conducted in April, 1991. During the supplemental investigation six stream bank sections, seven test pits and ten auger holes were installed, logged and samples. The additional soils investigations were conducted to further characterize the physical and chemical characteristics of the soils present in the bottom of the drainage area. These supplemental investigation includes Test-Pits 1-4, Auger Holes 1-10 and Stream Channel Sections 1-5.

Figure 1, presented in Appendix 2-A, delineates the soil map unit boundaries as mapped in the field. General soil unit descriptions are defined below.

TABLE 2.22-2

LOCATION	DATE SAMPLED	SAMPLE I.D.	ILLUSTRATION APPENDIX 10
Disturbed Soil (Pipeline)	11/11/88 and submitted for analyses on 1/5/89	#3	10.6.5-1 and 10.6.5-4
Slope below pipeline	11/11/88 and submitted for analyses on 1/5/89	#4	10.6.5-1 and 10.6.5-4
Undisturbed Soils	11/11/88 and submitted for analyses on 1/5/89	1-1, 1-2 & 2-1 2-2	10.6.5-2 ✓ 10.6.5-3 ✓ and 10.6.5-5 and 10.6.5-6 ✓
Exploration Cut	5/8/89	Overburd. comp. Underburd. comp.	10.2.6-2 ✓
Yard Expansion	5/11/89	#1 (0-6") #1 (0-12")	10.2.14-2 ✓
Exploration Cut	9/30/89	Overburden Underburden	10.2.6-2 ✓
Soil below topsoil pile	10/16/89 5/23/91	SCS Field Evaluation	10.6.3-2 and 10.6.3-1 ✓
Soil Thickness Survey (steam bank/ridge)	12/10/90 5/23/91	15 auger holes to determine topsoil depth	10.2.12-1 ✓ (revised 5/1/91) and 10.6.3-1 ✓
Stream Channel	2/26/91	#1, #2 Composites	10.2.14-1 ✓
Portal Development	2/26/91	#3 Composite	10.2.6-1 ✓
Soil below and adjacent to topsoil pile	5/1/91 5/23/91	9 auger holes to determine topsoil depth	10.2.12-1 ✓ and 10.6.3-1 ✓
Potent. areas of disturbance Area 1 Area 2 Area 3	5/1/91 5/23/91	14 auger holes to determine topsoil depth and SCS field evaluation	10.2.12-1 ✓ and 10.6.3-1 ✓
#3 Fan Site (proposed)	10/15/91	SCS Field Evaluation	10.6.3-3 ✓

Three soil mapping units were identified during the field investigation and subsequent report preparation. They are the Hernandez, the Gerst-Badland Complex, and the Haverdad.

Hernandez Soil

The 4.5 acre topsoil storage portion of the terrace immediately east of and contiguous to the proposed refuse disposal area (never to be constructed, 9/05/03) is classified as the Hernandez Soil. This area is represented by OTP #1.

Haverdad Soil

The soils within the confines of the valley floor have been classified as the Haverdad Soil and is represented by OTP #3. In addition, TP 1-4, AH 1-10 and Stream Channel Cross-sections (SCC) 1-5 also represents the Haverdad soil unit.

Soil Description

This section presents the results of the soil baseline investigation completed for the Soldier Canyon Mine LOM permit area. Factors important in the development of soils overlying the permit area are discussed. Descriptions are included with respect to the soil map units (Appendix 2-B) and soil series mapped within the permit boundary (Exhibit 2.22-1). The map unit descriptions describe the physiographic setting of the unit, soil characteristics, overlying vegetation communities, and related information. Soil series descriptions give a more detailed description of soil characteristics in terms of soil horizonation. A soil map unit legend is included (Table 2.22-3).

2-2) as shown on Exhibit 2.22-2. Inspection of test pits (#3 and #4) conclusively proved that the soil in the area was previously disturbed by activities associated with the installation of a buried gas line. Therefore, it was not possible to identify or log any distinct soil profiles or horizons. The soil appeared to be well mixed from the surface down to bedrock (0.0' to 3.0'). Thus only the upper foot of soil was sampled and submitted to ChemTech on January 5, 1989 for analysis of the required physical and chemical parameters (Illustration 10.6.5-1). Inspection of test pits (1-1, 1-2 and 2-1, 2-2) show a definite break in the soil horizons with the appropriate soil samples submitted for analyses (Illustration 10.6.5-2 and 10.6.5-3).

The soils in the area of the portal expansion are a sandy loam to loam with up to 22% gravel and cobble fragments. Field notes for test pits #3 and #4 are shown on Illustration 10.6.5-4. The undisturbed soils (1-1, 1-2 and 2-1, 2-2) are a gravelly sandy loam with up to 20%-25% gravel in the A Horizon with a gravelly sandy loam with up to 20% cobbles in the B Horizon. Field notes for (1-1, 1-2 and 2-1, 2-2) are shown on Illustration 10.6.5-5 and 10.6.5-6. Soil samples 1-1, 1-2 and 2-1, 2-2 were taken when the Applicant had originally made plans to place the new portals southeast (Portal Gulch) of their present locations. Because of the geologic conditions of the coal seam in the Portal Gulch area, the Applicant was forced to relocate the portals.

Due to the decision to realign the County road, the Applicant had additional studies performed on the soils to be disturbed. On October 16, 1989, Carol Franks (Soil Scientist) for the SCS examined the topsoil material adjacent to the present topsoil stockpile. From her examination of the topsoil material, the Applicant should save the material down to the very stony layer (Illustration 10.6.3-2), since this material is similar to the topsoil already stockpiled. On May 23, 1991 Leland Sasser (Soil Scientist) for the SCS examined additional soils outside the disturbed area that are subject to be and may be disturbed as a result of the road relocation and surface facilities expansion. (Illustration 10.6.3-1).

As per discussions and agreements with Priscilla Burton of DOGM, a topsoil thickness survey was performed by Rhett Brooks on a small area to be disturbed by the road alignment located a short distance away from the above sampled areas. Because this area is located within the same soil mapping unit and is of similar material, only a thickness survey was needed and the results are shown in Illustration 10.2.12-1

#### **Topsoil Storage Site**

#### **Soil Description for Topsoil Storage**

Many portions of the following soils descriptions were taken, in large measure, from the Soil Survey of Carbon Area, Utah (Soil Conservation Service, June 1988).

Detailed soils descriptions are located in Appendix 2-B.

#### **Gerst-Badland**

This series consists of shallow, well drained, moderately permeable soils on the sides of mesas, benches, terraces and canyons and on mountain slopes and hillslopes. These soils are formed in residuum and colluvium derived from shale and sandstone. The slope averages 30%-70%. Elevation ranges from 5,200 to 8,000 feet. Average annual precipitation ranges from 8 to 14 inches and average annual air temperature ranges from 45 to 50 degrees F. The soils are loamy, mixed (calcareous) mesic shallow Ustic Torriorthents.

The surface soils are light brownish gray to dark brown, moist, extremely stony loams. They have a weak medium subangular blocky structure and are slightly hard, friable and slightly plastic. Intermediate horizons are light brownish gray to grayish brown, moist Channery silt loams. Structure is massive and the soil is hard, friable, and plastic. Very fine roots are common. The subsoil contains 15% shale fragments and are strongly calcareous. Deeper horizons are partly weathered Mancos Shale with a paralithic contact depth at 18-20 inches.

#### **Haverdad**

The Haverdad soils are deep, well drained, moderately permeable soils on fan terraces and valley floors. These soils formed in stratified alluvium derived from sandstone and shale. Slopes average 1 to 8 percent. Elevation ranges from 5,500 to 6,900 feet above mean sea level, Average annual precipitation ranges from 8 to 14 inches, and average annual air temperature ranges from 45 to 49 degrees F. The soils are fine-loamy, mixed (calcareous) mesic Ustic Torrifuvents

The surface soils are typically light brownish gray to dark grayish brown, moist loams. Structure is weak platy to fine granular, hard, friable and plastic. The soil contains numerous pores and is moderately carbonaceous. The intermediate horizons are light yellowish brown to yellowish brown, moist loams. A weak subangular, blocky structure is typical. The soils are hard, friable and plastic. The soil is moderately calcareous and contains numerous pores. Deep horizons are pale brown to yellowish brown, moist loams. The structure is massive and very hard, friable, and plastic. Pores are common and the soil is moderately calcareous.

## **Hernandez**

The Hernandez unit consists of very deep, well drained soils developed on fan terraces. These soils form in alluvium derived from sandstone and shale. Slopes are 1 to 8 percent. Elevation is 5,600 to 7,100 feet. Average annual precipitation is 10 to 14 inches, and average annual air temperature is 45 to 49 degrees F. The soil is fine loamy, mixed, mesic Ustollic Calciorthids.

The surface soil is typically brown to dark brown, moist loams. The structure is weak fine granular, slightly hard, friable, and slightly plastic. It contains few very fine, common fine and few medium roots; many fine and few medium pores and is moderately calcareous. The intermediate horizons are brown to light brown, moist loams. These soil horizons exhibit a weak to moderate medium subangular blocky with few very fine, fine and medium roots. Also these horizons commonly have fine to medium pores and are moderately to strongly alkaline. The deep horizon is a moist, massive, hard, firm and plastic loam. It is strongly alkaline with few fine roots and common fine pores. Calcium Carbonate coats the faces of the peds.

### Present and Potential Productivity

Table 2.22-4 depicts the potential productivities of soil mapping units occurring within the proposed LOM boundary. Potential values vary for map units between oven-dry and air-dry productivities were taken from SCS Soils 5 Soil Interpretation Records for the Carbon Soil Survey Area. Potential oven-dry productivities were extracted from the previously accepted Sage Point/Dugout Canyon Mine permit application.

The Gerst soil is in capability class VIIe nonirrigated and the Badland is in capability class VIIIe. The Haverdad loam unit is in capability class VIe, non irrigated. The Hernandez nonirrigated soil is in capability subclass VIe. Class VI soils have severe limitations that make them generally unsuitable for cultivation. Class VII soils have very severe limitations that make them unsuitable for cultivation. Class VIII soils have limitations that preclude their use for crop production. The capability subclass with a letter designation of "e" shows a significant limitation in use due to risk of erosion, unless, close-growing plant cover is used and maintained.

Under current and envisioned future management conditions, the productivity of the soil will not increase. The high salt contents, lack of available water supply, proximity of crucial-critical wildlife habitat are significant factors

completed with the help of the SCS in Price, Utah, the Utah State Soil Laboratory, and Mr. Robert Thompson, a private consultant.

Soils are mapped at the Order III level on the permit area. An Order II survey was not required for disturbed areas since all areas to be disturbed during the proposed mining had been affected by operations conducted prior to the passage of current mining laws and regulations. Soil reports were prepared by Ford, Bacon, and Davis, Inc. and by EarthFax Engineering, Inc. to supplement information contained in Section 8.0 of the original permit application.

In 1985, Cedar Creek Associates, Inc., was retained by the Applicant to conduct a soil survey on two sections of land adjacent to the Sage Point-Dugout Canyon and Soldier Canyon mines. These were Sections 5 and 6, T135 and R12E, SLM. This survey (as well as the Soldier Canyon Mine survey) relied exclusively on existing information. These areas had previously been surveyed by the SCS at an Order III level. (Soil mapping and map unit descriptions have been completed and approved for this area but are as yet unpublished.) Because no surface disturbance is scheduled to occur in Sections 5 and 6, an Order III soil survey was deemed sufficient to characterize the soil resource. Cedar Creek was also retained to integrate the soil information from the Sage Point-Dugout Canyon Mine and Soldier Canyon Mine surveys, as well as the new soil resource information, into this permit application.

New soil resource information for SC3's surface facilities expansion is provided to supplement the existing soils information for these areas. A 1st Order Soil Survey was conducted on those areas to be disturbed.

Soil surveys were performed by the SCS on 10/16/89 and 5/23/91, to identify any soil complexes within the soil mapping units. These investigations were required by the Division to adequately describe the soils that will be disturbed or potentially disturbed, as a result of, the surface facilities expansion and county road relocation. Illustrations 10.6.3-1 and 10.6.3-2 provide SCS's findings.

For the topsoil storage, EarthFax Engineering, Inc. was contracted to perform the necessary field investigations. All field investigations were conducted and test-pits were logged in accordance with USDA Soil Conservation Service procedures as defined in the National Soils Handbook and the Soil Survey Manual. The soils were mapped to the phase of the series. Individual mapping unit boundaries were delineated in the field. Thus, allowing the area to be mapped under a "1st Order Soil Survey". The Gerst-Badland is a soil complex which cannot be separated into individual mapping units because of

## 2.30 Operation Plan

### 2.31.1 Methods for Removing and Storing Topsoil, Substitute Topsoil and Landscape Boulders/rip rap

The following is a list of equipment to be used for removal of vegetation, boulders and topsoil and for loading the topsoil, substitute topsoil and landscape boulders/riprap.

1. Track Hydraulic Excavator
2. 966 Wheel Loader
3. D8 Dozer
4. 953 Track Loader
5. 12 yd<sup>3</sup> Dump Trucks
6. Belly Dumps

The safest and most efficient means of performing this operation will be used to ensure the safety of the equipment operators. Topsoil will be loaded into the dump trucks and hauled to the Applicant's topsoil storage site. Substitute topsoil will be sorted and hauled to the topsoil site and placed in its designated location at the topsoil site. Landscape boulders/riprap will also be hauled and placed in its designated location at the topsoil storage site.

### 2.31.2

The suitability of topsoil substitutes is described in section 2.24 of this application

### 2.31.3

Testing plan for evaluating the results of topsoil handling and reclamation procedures related to revegetation are as described in section 2.41 of this application. Sampling techniques are described in detail in this section. Soil nutrients and amendments will be added based on these tests.

### 2.31.4

The Applicant has an approved topsoil storage site to accommodate the storage of topsoil, substitute topsoil and landscape boulders/riprap associated with the surface facilities expansion and road relocation. The topsoil storage site encompasses 4.5 acres, of which 2.3 acres is presently approved for the stockpiling of the above mentioned material.

Presently the topsoil storage site is arranged as shown on Exhibit 5.21-2. The area designated as topsoil/substitute topsoil storage will not be stripped of

topsoil, but will be cleared of any vegetative cover prior to placement of other topsoil. The area designated as landscape boulders/riprap storage will be stripped of topsoil to a depth of 17 inches prior to placement of boulders. Vegetation that is removed will be burned, buried or hauled off to the nearest landfill for disposal.

Topsoil and substitute topsoil will be placed on a stable gradually sloping site with enough compactive effort applied during placement to maintain competence of the embankment. Any further placement of topsoil, after the initial piles are revegetated and stabilized, will necessitate the formation of new topsoil piles to eliminate disturbance to the established piles. Vegetation will be established to limit erosion. The topsoil/substitute topsoil will be protected from excessive erosion and instability by the following means:

- \* Placed on a stable site with proper identification signs
- \* Construction of runoff control and diversion measures around the site
- \* Completing necessary annual interim reclamation measures to ensure that an adequate stand of vegetation cover is maintained.
- \* Not be moved until required for redistribution unless approved by the Division.

Landscape boulders/riprap will be placed on a 0.30 acre parcel of the topsoil site. Prior to any boulder placement, the 0.30 acre parcel will be stripped of topsoil to a depth of 17 inches. The total yardage of topsoil to be removed will be approximately 590 yd<sup>3</sup>s. The topsoil to be removed will be placed as shown on Exhibit 5.21-2. After topsoil removal, approximately 1675 yd<sup>3</sup>, of landscape boulders/riprap will be hauled from the mine site and placed until reclamation.

Prior to the establishment of the topsoil storage site, only one other site at the central mine facilities accommodated the storage of topsoil; the central mine facilities topsoil storage pile. This topsoil stockpile is located on the southeast portion of the sediment pond area and is adequately protected from runoff, water and wind erosion and instability. The stockpile was placed on the insitu and fill soils downstream of the incised sediment pond. The west portion of the pile butts directly against the pre-existing hillslope. The northern most portion of the stockpile has a flat top with a 6 in. protective gravel cover. (This portion of the stockpile along with the sediment pond embankment soils were incorporated into a small storage yard which is covered with gravel and enclosed by a wire mesh fence). Liquids or materials which might provide a source of toxic or hazardous materials are restricted from the area. The exposed southeast facing slope of the topsoil stockpile has moderate slopes 1 V:2.5 H, and is well vegetated. The exposed face has mulch tacked down by anchored jute netting. The topsoil stockpile has approximately 85% vegetative cover with the remainder of the area being covered by the mulch and jute netting.

The area is protected from runoff by the sediment pond and road diversions. Protection from water and wind erosion is provided by the 6 in. gravel cap on top and the well vegetated southeast facing slopes. The soil was emplaced on a stable foundation utilizing acceptable engineering practices to achieve the appropriate level of compaction to insure slope stability.

The area is well marked and identified as a topsoil stockpile. The protection measures previously mentioned ensure the long term stability and protection of these topsoil resources.

#### 2.32 Topsoil and Subsoil Removal

##### Central Mine Facilities

As a result of soil thickness surveys and SCS's recommendation, the Applicant will remove the material down to the very stoney layer. Therefore, where topsoil is less than six inches thick, it and the unconsolidated material immediately below will be treated as topsoil.

The stripping depths and quantity of topsoil to be removed prior to any surface disturbances associated with the facilities expansion and road relocation was determined by EarthFax Engineering (Illustration 10.2.12-1). Three areas of potential disturbance (Area 1, Area 2, Area 3) that may arise, as a result of sight-fitting the facilities were also evaluated for their topsoil recovery potential and are within our proposed limits of disturbance.

A summary of the topsoil and substitute topsoil yardage previously salvaged, to be salvaged and possibly salvaged are shown below.

FROM	PRESENT LOCATION	YARDAGE
Steam Culvert Extension (substitute)	North of storage yard (SALVAGED)	3794 yd3
Topsoil removed during initial culvert installation	Topsoil Pile-east side of Soldier Creek (SALVAGED)	660 yd3
Streambank/Ridge Zone 1 Zone 2	South of #2 Fan-east of culvert extension (SALVAGED)	2310 yd3
In-situ soils below & adjacent to Topsoil pile	East side of Soldier Creek-side slope (SALVAGED)	
Area 1-Topsoil from potential disturbance (0.35 Ac)	West and North of storage yard	735 yd3*
Area 2-Topsoil from potential disturbance (0.09 Acres)	West of storage yard	175 yd3*
Area 3-Potential disturbance for silos and pad construction (0.16 Ac)	North of storage yard	335 yd3*
TOTAL		8009 yd3
TOTAL excluding potential disturbances (Areas 1, 2 and 3)		6764 yd3

\*Note: Of the total acreage within each area, topsoil will only be salvaged where the disturbance will occur. Therefore, the topsoil quantity may be much less.

The quantities shown are a worst case, assuming the total area is disturbed. When the facilities are constructed, the actual areas of disturbance will be shown and the actual quantity of topsoil salvaged calculated. The salvaged soils have been placed at the Applicant's Topsoil Storage Site (Exhibit 5.21-2). Cross-sections used in determining volumes for each stockpiles are shown on Figures 2 and 3 in Appendix 2E. Soils salvaged (620 yd<sup>3</sup>) from the proposed #3 Fan project are also shown.

The total disturbance, including two previous incidental boundary changes and the potential areas of disturbance is 6.4 acres. The following chart gives a break down of the total acreage requiring topsoil redistribution.

Description	Area	Acres	Yardage - 1 foot Replacement depth
Total disturbance		6.40	
Does not need topsoil replacement	Pipeline Road	0.56	
Does not need topsoil replacement	County Road	0.74	
Does not need topsoil replacement	Stream Channel	2.25	
Total Acreage Requiring Topsoil		2.76	4453 yd <sup>3</sup>
Potential Limits of Disturbance	Area 1	0.35	
Potential Limits of Disturbance	Area 2	0.09	
Potential Limits of Disturbance	Area 3	0.16	
Total Area Requiring Topsoil if Area 1, Area 2 and Area 3 are not disturbed		2.16	3485 yd <sup>3</sup>

Using the 2.16 acres as the area in need of topsoil redistribution at a depth of 1 foot, 3485 yd<sup>3</sup>s of topsoil will need to be stockpiled for reclamation. If all the potential areas of disturbance are disturbed (worst case), then 4453 yd<sup>3</sup>s of topsoil will need to be stockpiled.

As can be seen from the two charts, the Applicant will stockpile more than enough topsoil and substitute topsoil to adequately reclaim any permitted disturbances, as a result of the facilities expansion and road relocation. The remaining topsoil material will be used in reclaiming pre-SMCRA disturbances (Exhibit 2.22-2), where topsoil was not salvaged. The Applicant will not remove topsoil for minor disturbances which occur at the site of small structures, such as power poles, signs, or fence lines; or that will not destroy the existing vegetation and will not cause erosion.

All material to be removed under R614-301-232 will be removed after the vegetative cover that would interfere with its salvage is cleared from the area to be disturbed, but before any drilling, blasting, mining, or other surface disturbance takes place.

Topsoil Storage Site - Topsoil removal was performed only in those areas affected by the construction of the access road and landscape boulders/riprap stockpile. The top 17" of topsoil was segregated in those areas (see Section 2.31.4). Topsoil material was used in the construction of the berms, where it will be revegetated upon completion of the site.

### 2.33 Topsoil Substitute and Supplements

Selected overburden materials may be substituted for, or used as, a supplement to topsoil if the operator demonstrates to the Division that the resulting soil medium is equal to, or more suitable for, sustaining vegetation on non-prime farmland areas than the existing topsoil, and results in a soil medium that is the best available in the permit area to support revegetation.

Section 2.24 (Substitute Topsoil) addresses the substitute topsoils and their respective locations. As stated in section 2.24, the majority of the surface disturbance occurred prior to the passage of SMCRA. Exhibit 2.22-2 shows the extent of the pre-SMCRA disturbances. As such, soil salvage was not conducted as a part of normal operating procedures. Therefore, topsoil materials available for revegetation are limited.

Test plots constructed under the previous Soldier Canyon Mine permit will test the efficacy of the substitute materials (section 2.24). The Applicant will use the vegetation growth on the substitute topsoil stockpile, constructed of stream channel soils, to test the efficacy of that particular substitute material. The applicant has established test plots as mentioned in Section 2.24. The vegetation growth on the stockpiled stream channel solid will test the efficacy of that substitute material.

### 2.34 Topsoil Storage

Materials removed under R614-232.100, R614-301-232.2 and R614-301-232.300 will be segregated and stockpiled when it is impractical to redistribute such materials promptly on regraded areas. The stockpiled material will:

- \* Be selectively placed on a stable site within the present permit area

- \* Be protected from contaminants and any unnecessary compaction that would interfere with revegetation.
- \* Be protected from wind and water erosion through prompt establishment and maintenance of an effective, quick growing vegetative cover or through other measures approved by the Division.
- \* Not be moved until required for redistribution unless approved by the Division.

The Applicant's permitted Topsoil Storage Site (Exhibit 5.21-2) was constructed according to the R614 coal mining regulations. This approved site allows for the stockpiling of soil material and landscape boulders/riprap to prevent any damage to the quality or quantity of those materials. Figures 2 and 3 in Appendix 2E also show stockpile quantities, locations and cross-sections. Soils salvaged (620 yd<sup>3</sup>) during #3 Fan exploration project are also shown.

The stockpiling of materials at the topsoil storage site will not permanently diminish the capability of the topsoil of the host site. The stockpiles will have approximately 2h:1v outslopes and surrounded by soil berms. Placement of the stockpiles will take place after the vegetation is removed or incorporated into the salvaged topsoil from the host site (topsoil storage site). Topsoil from the host site will be salvaged to a depth of 17" and stockpiled to prevent any potential for contamination by the material to be stockpiled. Those areas where the central mine topsoil and substitute topsoil were placed did not require stripping prior to their placement. This activity was approved by the Division during the initial permitting of the site.

Any further placement of soil stockpiles, after the initial piles are revegetated and stabilized, will necessitate the formation of new topsoil or subsoil piles to eliminate disturbance to the established piles. Vegetation will be established to limit erosion.

Runoff control for the topsoil storage site is presented in Section 7.32 of this application.

#### 2.40 Reclamation Plan

##### 2.41 General Requirements

The permit application includes plans for redistribution of soils, use of soil nutrients and amendments and stabilization of soils.

## 2.42 Soil Redistribution

Topsoil will be replaced on graded areas in a manner and at a time that 1) achieves an approximate uniform, stable thickness consistent with the approved postmining land use, contours, and surface water drainage systems; 2) Prevents excess compaction of the materials; 3) Protects the material from wind and water erosion before and after seeding and planting.

Topsoil will be applied in lifts as thick as possible to decrease compaction potential. Replacement will occur along the contour, where safety factors permit, to minimize erosion and instability. Replacement will occur within 30 days prior to seeding.

### Central Mine Facilities Area

The Applicant does not plan to redistribute the topsoil in any area until that area is backfilled, recontoured and scarified (1.5 ft.). Immediately after the preceding measures are completed in an area, that area will be staked on 100 ft centers to ensure a uniform distribution of topsoil, over the area to be resoiled. Upon completion of the redistribution, the soil will be randomly sampled to ensure that the appropriate depth has been attained and to obtain composite samples for analyses to determine the current requirements for soil nutrients and amendments. Exhibit 7.60-1 shows the final reclaimed contours. Topsoil replacement depths presented in Section 5.42 of this application.

The central facilities sediment pond will be recontoured and revegetated after revegetation requirements have been met, and quality of the drainage entering the pond meets the applicable Federal and State water quality standards. Since the embankment of this structure is composed of topsoil, redistribution of the embankment material will be used to cover the sediment pond and achieve the proposed postmining contours. The depths of backfilling and topsoil replacement are shown on Exhibit 7.60-1 and addressed in Section 5.42.

### Sewage Lagoons

The soils used to construct the sewage lagoons embankment will also be used for reclamation. The disturbed area associated with the sewage lagoons will be reclaimed by removing all structures and by redistributing the embankment materials into the lagoon to achieve the propose final contours (Exhibit 5.42-2.) and complete the resoiling process.

### Topsoil Storage Site

1. Soil Stockpiles and Landscape Boulders/Riprap Stockpile

Upon reclamation, the soil stockpiles will be taken to their respective sites and redisturbed. A dozer with a ripper bar will scarify the compacted areas, to a depth of 2 feet to produce proper seedbed conditions. Thereafter, the topsoil storage area will be graded to the proposed final contours (Exhibit 5.42-3), disced and reseeded according to revegetation plan.

2. Containment Berm and Overland Flow Structures

The containment berm will be recontoured and revegetated after the soil stockpiles have been removed. Exhibits 5.42-3 shows the final contours to be achieved following reclamation. Topsoil and subsoil used in the construction of the embankment will be used as backfill material to achieve final grading. The overland flow structures (berms, and culverts) will also be removed at this time. The Applicant will use a method of removal that will minimize area disturbance. The backfill material will come from the berms and once graded, the area will be revegetated.

3. Access Road

Immediately after the access road is no longer needed for operations, reclamation, or environmental monitoring, it will be restored. The gravel road surface and subgrade material will be removed and used as backfill at the mine site or at the proposed waste rock site. The topsoil off the outslopes will be removed and temporarily stockpiled in an area at the road construction beginning. The compacted roadway will then be scarified to a minimum of two feet to ensure adequate bonding between soils. The topsoil material from the temporary stockpile will then be evenly spread over the area, disced and seeded.

2.43 Soil Nutrients and Amendments

Seedbed materials will be sampled following gradings and prior to seeding to assess the success of grading and to determine fertilizer requirements. Fertilizer will be added to regraded areas as per recommendations resulting from sample analysis. The following specifications will be followed to collect seedbed material samples.

The laboratory selected to analyze samples will be contacted at least 30 days in advance of each sampling period to aid in coordinating sample analyses with the implementation of subsequent revegetation procedures.

### Specific Procedures

Two samples, representing the 0-6 and 6-18 in. depths, will be taken at a rate of one sample per 5 ac of disturbed area for each type of disturbed site. Sites less than 5 ac in size will also be represented by one set of samples. Seedbed materials exhibiting surface characteristics (e.g. color, texture, parent material) or topsoil replacement depths significantly different from adjacent areas will be sampled as separate entities under the 5 ac rule. For each sample, the average slope and estimated coarse fragment content by volume will be estimated. Each sample will be analyzed by the laboratory for:

- 1) pH
- 2) texture
- 3) percent organic matter
- 4) NH<sub>4</sub>-N (ppm) and NO<sub>3</sub>-N (ppm)
- 5) phosphorus (ppm)
- 6) potassium (ppm)
- 7) electrical conductivity
- 8) sodium absorption ratio

Accompanying each set of samples will be a brief discussion of the area from which samples were collected. The discussion will include comments concerning:

- 1) plant species to be established
- 2) type of seedbed preparation techniques to be implemented
- 3) types of mulches to be applied
- 4) approximate final slope
- 5) any special problems or conditions
- 6) past and future land use considerations

### Topsoil Storage Site

The nutrient levels for the soils are presented in Table 4. For the soils encountered to the proposed level of disturbance (17") the nutrients are quite similar and within acceptable ranges. As described previously, the percent organic matter had not been determined at the time this report was prepared.

The Nitrate-nitrogen levels range from 101 to 510 ppm which is considered low. Consequently 40 pounds per acre of Nitrogen will be added to the soil. This will be accomplished by using 88 pounds per acre of sulfur coated urea 45-0-0, a slow release fertilizer.

Phosphorus levels range from 0.22 to 2.74 ppm. These levels are also considered low for ideal plant development. Therefore, 30 pounds per acre of phosphorous will be added using 65 pounds per acre of treble superphosphate, 0-46,0.

Potassium levels range from 4.5 to 62 ppm. These levels are within acceptable limits. Mixing of the soils during placement will result in uniform distribution of potassium throughout the soil profile.

Fertilizer will be applied in the fall of the year when reclamation is occurring. Fertilizer will be applied by broadcasting, drilling or hydroseeding.

TABLE 2.42-1  
CURRENT SOIL NUTRIENT LEVEL

SOIL	DEPTH (in)	OM (%)	N (%)	P (ppm)	K (ppm)
Hernandez	0-2.0"	1.42	0.0510	2.74	29.0
Hernandez	2.0"-12.0"	1.25	0.0333	1.00	62.0
Hernandez	12.0"-30.0"	0.98	0.0193	0.29	5.5
Hernandez	30.0"-54.0"	0.84	0.0101	0.22	4.5
Hernandez	54.0"-72.0"	0.60	0.0133	0.51	38.0

#### 2.44 Soil Stabilization

All exposed surface areas will be protected and stabilized to effectively control erosion and air pollution attendant to erosion.

Suitable mulch and other soil stabilizing practices will be used on all areas that have been regraded and covered by topsoil or substitute topsoil. Section 3.41 of this document will fully address the methods by which the Operator will use to stabilize redistributed soils.

Rills and gullies, which form in areas that have been regraded and topsoiled and which either:

Disrupt the approved postmining land use or the reestablishment of the vegetative cover; Cause or contribute to a violation of water quality standards for receiving streams will be filled, regraded, or otherwise stabilized, topsoil will be replaced and the areas will be reseeded or replanted.

2.50 Performance Standards

All topsoil, subsoil and topsoil substitutes or supplements will be removed, maintained and redistributed according to the plan given under R614-301-230 and R614-301-240.

2.52

All stockpiled topsoil, subsoil and topsoil substitutes or supplements will be located, maintained and redistributed according to plans given under R614-301-230 and R614-301-240.

## Chapter 3

### BIOLOGY {R614-301-300}

#### 3.10 Introduction

This chapter presents a description of the biological resources found within the life of mine permit area.

The sections addressed in this chapter are: the vegetative, fish and wildlife resources; the potential impacts to vegetative, fish and wildlife resulting from the proposed operations, and the mitigation plans and measures to minimize the impacts; and the reclamation plan to restore the vegetative, fish and wildlife resources to a condition suitable to the postmining land use.

#### 3.20 Environmental Description

#### 3.21 Vegetation Information

The vegetation study and floral characteristics described in this application were derived from a complex of previous studies for the two previously approved documents; Sage Point-Dugout Canyon (ACT/007/009) and Soldier Canyon Mine (ACT/007/018), and new information collected to address the new life of mine (LOM) areas. This information is designed to satisfy federal and state requirements for baseline vegetation data and reference area establishment.

The LOM area primarily exists within the steeply incised canyons of the Book Cliffs, but also includes portions of the upland benches along the West Tavaputs Plateau. The sewage lagoons and topsoil storage area are located on the toeslopes of the Book Cliffs. Soils range from extremely poor in areas that are steep and rocky or formed from Mancos shale to relatively deep productive soils which formed at the base of north-facing slopes high in the Book Cliffs. Precipitation varies with elevation but is generally low, typical of the Great Basin desert. According to Kuchler (1975), the potential natural climax vegetation communities of the proposed LOM area include (from lowest in elevation to highest): Saltbush-Greasewood (Atriplex - Sarcobatus), Pinyon Juniper Woodland (Juniperus - Pinus), Mountain Mahogany-Oak Scrub (Cercocarpus - Quercus), Great Basin Sagebrush (Artemisia), and Douglas Fir Forest (Pseudotsuga). However, in actuality, inclusions of several other communities can be found within the proposed LOM area. In all, thirteen floral communities were delineated and

include, from the lowest elevation to the highest: Greasewood-Galleta, Black Sagebrush-Greasewood, Black Sagebrush-Shadscale, Shrub-Gras-Juniper, Pinyon-Juniper, Deciduous Streambank, Sagebrush, Mountain Brush, Mixed Conifer-Mountain Brush, Mixed Conifer, Ponderosa Pine, Douglas Fir, and Quaking Asper (Exhibit 3.7-1).

All previous vegetation sampling occurred within the proposed LOM area or the old Sage Point-Dugout Canyon LOM area on those communities which could potentially be disturbed as well as on reference areas and vegetation adjacent to areas which already have been disturbed. These data are presented within this section of the application and are identified with regard to their source: old Soldier Canyon Permit (SC) or Sage Point-Dugout Canyon Permit (SPDC). In addition, new information was collected in the fall of 1988 and the summer of 1990 and 1991 to further describe the vegetation within the surface facilities expansion and road relocation, topsoil storage and the new LOM area. Reference areas were also established for areas to be affected by surface disturbance.

Vegetation reference areas were established for communities previously affected by surface disturbances and, as indicated above, were established for communities to be affected by future surface disturbances. These areas will be used during the final stages of reclamation to assess the success of revegetation in accordance with the ultimate goal of restoring areas disturbed by mine related facilities. These reference areas will be managed properly and will be periodically monitored to assess the effects of this management.

The methodology used in gathering the required vegetation information and a description of the vegetation communities are addressed in Appendix 3-A for the existing mine permit, and in Appendix 3-B for the intake portals, road relocation, permit area expansion and the topsoil storage areas.

#### 3.21.2 Productivity of the Land Prior to Mining

Productivity and range conditions estimates for the proposed disturbed and reference areas will be performed by the U.S. Soil Conservation Service, Price, Utah. A copy of the estimates are included as Appendix 3-C. Also, included in Appendix 3-C is the existing range conditions of the Mountain Brush and Deciduous Streambank Reference Areas.

### 3.22 Fish and Wildlife Information

Fish and wildlife information for the Soldier Canyon Mine LOM permit area is presented in Appendix 3-D. Soldier Creek Coal Company (SC<sup>3</sup>) contacted the Division of Wildlife Resources (DWR) regarding the impacts to raptors that may result from an expansion of the mining permit area for the Soldier Canyon Mine. During the Spring of 1991, the DWR flew the expansion area to look for raptor nests and for those areas that could not be surveyed from the air, Environmental Industrial Services of Elmo (EIS) was contracted to perform ground surveys of those areas. Appendix 3-D-1 contains the DWR's conclusion from these survey's along with EIS's report.

A raptor and bird survey of the permit and adjacent areas was conducted during May, June and July. The results of this study are in Appendix 3-G "1992 Avian Survey."

#### 3.22.10 Scope and Level of Detail

The scope and level of detail will be sufficient to design the protection and enhancement of the fish and wildlife in the area of the Soldier Canyon Mine LOM permit area required under R645-301-333.

#### 3.22.20 Site-Specific Resource Information

The permit area serves primarily as rangeland for livestock and wildlife habitat. A wide variety of wildlife species utilize habitats within and adjacent to the permit area. Among the more economically important and high interest species are mule deer, elk, mountain lion, coyote, blue grouse, ruffled grouse, sage grouse, snowshoe hare, mountain cottontail, desert cottontail, and a variety of raptor species.

Details and methodology of the investigations are addressed in Appendices 3-D and 3-D-1.

#### 3.22.21 Listed or Proposed Endangered or Threatened Species of Plants or Animals

Three species federally listed as "endangered" by the U.S. Fish and Wildlife Service are potential inhabitants of the general region of the project area: the black-footed ferret, bald eagle, and peregrine falcon (Table 3.22-1).

The rarity of the black-footed ferret as well as their nocturnal and subterranean habits, contribute to their undetermined status in Utah. The only time ferrets may be seen with any regularity is in late summer when the young are active above ground (Clark, 1978). The range of the black-footed ferret closely coincides with that of prairie dogs. Ferrets utilize prairie dog burrows for living and rearing their young (Boner et al., 1977) and, thus, areas supporting prairie dogs on or adjacent to proposed permit area are potential habitat for the black-footed ferret. There have been no confirmed sightings of ferrets in Carbon County. The most recent unconfirmed sighting was by a local UDWR Conservation Officer on February 10, 1980 and occurred near East Carbon City.

A search to the east and southeast of the Soldier Canyon Coal Mine area was conducted in April and May, 1980. No prairie dogs or prairie dog colonies are known to exist on the proposed area.

Peregrine falcons are year-long residents of Carbon County, but no sightings are known to have been made on or adjacent to the proposed area, and no aeries are known or suspected within 40 miles (UDWR, 1979a, Appendix 3-A). Peregrines nest on cliffs, usually near water, and forage widely for waterfowl, shorebirds, and peregrines (Johnson, 1978). Preferred nesting and hunting does not exist in the proposed area.

There are no federally listed threatened or endangered fish species inhabiting the limited aquatic habitat.

The field investigations of the Soldier Canyon and Sage Point-Dugout Canyon areas did not identify or locate any threatened or endangered plant species (Section 3.7.4, Appendix 3-A). One sensitive species was observed in the area, but was classified 3c by the U.S. Fish and Wildlife Service. In the January 27, 1992 DOGM technical deficiency review, Paul Baker (Biologist) states that the plant species referred to in Sec. 3.7.4, App.3-A is no longer considered a category 3C plant.

The areas were surveyed on a grid-type system for sensitive plant species by Mt. Nebo Scientific (June 1990, Page 8, Appendix 3-B). No threatened and endangered plant species were found on the reference or proposed disturbed areas.

Table 3.22-1

Federally Listed Endangered and Threatened Species Which May Occur in Utah \*

Mammals

Black-footed Ferret ( <u>Mustela nigripes</u> )	No recent confirmed sightings in Utah.
Utah prairie dog ( <u>Cynomys parvidens</u> )	

Birds

American peregrine falcon ( <u>Falco peregrinus</u> anatum)	Nests in Utah.
Arctic peregrine falcon ( <u>Falco peregrinus</u> tundrius)	Migrates through Utah, no resident population.
Bald eagle ( <u>Haliaeetus leucocephalus</u> )	Nests in Utah.
Whooping Crane ( <u>Grus americana</u> )	Migrates through Utah, no resident population.

Fish

Colorado squawfish ( <u>Ptychocheilus lucius</u> )	
Bonytail Chub ( <u>Gila elegans</u> )	
Humpback Chub ( <u>Gila cypha</u> )	
Woundfin ( <u>Plagopterus argentissimus</u> )	
<u>Lahontan</u> cutthroat trout ( <u>Salmo clarki</u> henshawi)	

\* Compiled from information dated 8/8/86

Seven species of nongame fish may occur in Anderson reservoir (Dalton, 1980). These fish species, which may occupy aquatic habitat in the project area, include the Utah chub (Gila atraria), Red shiner (Notropis lutrensis), Fathead minnow (Pimephales promelas), Speckled dace (Rhinichtys osculus), Redside shiner (Richardsonius baiteatus), Bluehead sucker (Catostomus discobulus) and Flannelmouth sucker (Catostomus discobulus). In addition, a few of these species may migrate from the Price River into the intermittent streams in the project area when water flow conditions are high. However, no fish have been observed in any of the streams in the proposed permit area during hydrologic studies conducted over the past five years (Anderson, 1980). Dead fish (unidentified as to species) have been observed in the reservoir (Anderson, 1980). Due to drought conditions in 2001 through 2003, Anderson Reservoir has been dry by late fall, no fish species have survived.

#### 3.22.22 Habitat of High Value

Mule Deer The northeast portion of the LOM area provides summer habitat for mule deer while most of the remaining portions represent transitional range. Only the sewage lagoons and topsoil storage site are located within mule deer winter range. The critical winter range, as designated by DWR, currently encompasses an estimated 11,750 acres, extending from Fish Creek on the east to Mead's Wash on the west (Exhibit 3.10-4).

#### 3.22.23 Specially Protected Species and Habitats Identified by State or Federal Agency

The critical winter range has also been described by state agencies as "crucial-critical winter range for the mule deer population.

The sensitive plant species Hedysarum occidentale var. canone (Sweet Canyon Vetch) has been noted within the permit area. Another sensitive plant species, Cryptantha creutzfeldtii, has been noted to occur adjacent to the permit area. In accordance with the BLM, a survey of proposed disturbed areas for these plant species, is required (see Appendix 3-A).

#### 3.23 Maps and Aerial Photographs

Vegetation mapping was done by walking the area and using contour maps and aerial

photographs.

#### 3.23.10 Location and Boundary of Reference Area

Exhibit 3.7-2 shows the vegetation and reference area for the Mountain Brush and Deciduous Streambank. Exhibit 3.7-3/Map A shows the vegetation and reference area for the topsoil storage site.

#### 3.23.20 Elevation and Location of Fish and Wildlife Monitoring Stations

Exhibits 3.10-1 through 3.10-4 show the elevation and location of monitoring stations.

#### 3.23.30 Facility Used to Protect and Enhance Habitat

The Applicant ensures that all electric power lines and other transmission facilities are constructed to minimize electrocution hazards.

Fencing, installed at the topsoil storage site, is constructed to DWR standards as shown on Figure 3.23-1 for the protection of wildlife.

The landscape boulders/riprap stockpile at the topsoil storage site will provide shelter for the smaller animals.

#### 3.30 Operation Plan

The Applicant has prepared a plan to mitigate any adverse effects on vegetation, fish or wildlife. Along with the mitigative measures in this plan, the Applicant participated in a wildlife mitigation plan as detailed in Illustration 10.8.2-1, thus, providing an additional 79.2 acres of improve rangeland. This plan to mitigate the loss of critical valued deer winter range was developed by the Utah Division of Wildlife Resources (Illustration 10.8.2-2).

#### 3.31 Interim Revegetation and Stabilization

Several area exist and will exist on operational areas that will require temporary stabilization until permanent revegetation is initiated. Such disturbances include topsoil stockpile sites, temporary road locations, and sites within the Soldier Canyon Mine facilities which were or will be disturbed for

construction or temporary operations but will not need to be disturbed on a continuing basis. All measures will be taken to disturb the smallest practicable area at any one time. These sites will be qualitatively monitored for at least the first two years for revegetation success. Remedial action, if necessary, will be determined during the monitoring investigation.

Revegetation methodologies to be used to temporarily stabilize these sites are those listed under Sec. 3.41.22 according to degree of slope angle and accessibility. The seed mixture to be used is presented in Appendix 3-E, entitled Intermediate Seed Mixture - All Areas .

Temporary revegetation will likely entail, at least on a limited basis, stabilization of small, isolated and perhaps irregular disturbances which do not lend themselves to methodologies identified in Sec. 3.41.22. In such cases, revegetation will be completed manually. Grading and seedbed preparation will be completed by raking. Seed will be broadcast by hand and the site raked a second time, lightly, to cover the seed. Straw or hay mulch will then be spread evenly over the site at the approximate rate of 2 t/ac. The straw will then be anchored by crimping with shovels . No irrigation is planned for use on the permit area.

### 3.32 Impacts on Renewable Resources

This is addressed in Section 5.25 of this application.

### 3.33 Fish and Wildlife Plan

Potentially adverse impact on wildlife and related environmental values will be avoided or minimized through the implementation of mitigation measures. The Applicant will operate and maintain all transportation systems and support facilities under their control in a manner that minimized impacts to fish and wildlife. Restoration or enhancement of wildlife habitat on reclaimed areas within the permit area will be achieved where practicable and where it is consistent with the approved post-mining use. The applicant reserves the right to amend the fish and wildlife plan.

Wildlife habitat and range land is the current and predominant land use occurring on and about the LOM permit area. The area presents habitat for a variety of wildlife species normally associated with the semi-arid Great Basin ecoregion. Baseline studies determine that no fisheries are present in or around the project

area.

Before collecting and stockpiling topsoil, some rock and woody vegetation will be removed and piled in undisturbed areas. These piles will provide cover for small mammals and upland game. Protection from adverse weather and predators is vital to many species of animals and is critical factor in habitat selection by species. These structures also provide perches for songbirds and small raptor species. Perches elevated above surrounding vegetation or providing an extended view of an area are critical to territorial establishment of many breeding songbirds. Actual location of rock and brush piles will be left to the discretion of the Applicant.

#### Timing of Major Disturbances

During May and June, blasting and massive earthwork in the area will be avoided wherever possible from one hour before sunrise and sunset to two hours after sunrise and sunset. These times are critical periods for wildlife during the breeding season.

#### Education of Mine Personnel

An education program will be present in conjunction with the MSHA training program to minimize the potential negative impact of employees upon wildlife. Appropriate communications with employees will describe the rationale of habitat restoration procedure, company hunting policies, penalties for infractions of company policy or state law, and the purpose of reclamation. An awareness of mine employees of their potential impact on wildlife will help prevent or reduce many impacts.

#### Reporting of Threatened or Endangered Species

Reporting of threatened or endangered wildlife is a requirement of OSM and DOGM regulations. If suspected sightings are made, the applicant will contact appropriate state and federal agencies.

#### Impact to Raptor Nests through Subsidence

If significant subsidence occurs, or is about to occur, during the April to July period of any year, a nesting survey will be completed to determine if any nesting raptors are in the potential area of impact. If active nests are found, the Division of Wildlife Resources and DOGM will be notified, so as to ensure that all appropriate actions are taken.

#### Construction of Power Lines

The applicant will request that power lines be constructed per OSM and DOGM regulations in accordance with guidelines set forth in Environmental Criteria for Electric Transmission Systems (USDA, 1970) or with alternate guidelines approved by the regulatory authority. These guidelines are designed to avoid or minimize lethal aspects to songbirds and raptors, which frequently utilize power poles as perch sites.

#### Impact to Livestock and Wildlife Through Subsidence

In the unlikely event that livestock are killed or injured as a result of surface subsidence, the Applicant will adequately compensate said owner. Furthermore, any subsidence caused surface cracks which are of a size or nature to cause injury or death to livestock or wildlife will be repaired by the Applicant.

#### Location and Operation of Haul and Access Roads

Proposed locations of primary and ancillary roads within the permit area have been carefully assessed to determine if they will present significant problems to wildlife. If, after mining activity commences, an area is identified as apparently causing undue mortality to wildlife, then appropriate mitigation measures will be taken such as erecting "deer crossing" signs, or reducing speed limits. UDWR has determined that most of the mule deer wintering in the vicinity of the project area migrate via canyons west of Fish Creek. Only a few animals utilize Fish Creek or Dugout Canyon as migratory routes.

#### Regulation of Firearms and Activity Within Mine Boundaries

State and federal wildlife regulations will be enforced on the Applicant's properties within the permit area.

The presence of unauthorized people and companion animals is prohibited in areas controlled by the Applicant. Harassment of wildlife by excessive observation, disturbance of nesting birds and young animals, and chasing wildlife in vehicles (such as snowmobiles), will be discouraged by the Applicant. The unauthorized use of off-road vehicles on land controlled by the Applicant will be prohibited.

#### Replacement of High Value Habitat

Following mining, revegetation will be primarily concerned with replacing the pre-mining habitats. High value habitats including pinion-juniper, and riparian areas will be restored to pre-mining or better condition.

3.40 Reclamation Plan

3.41 Revegetation Plan

#### Introduction

The following revegetation plan has been developed to address all disturbed areas requiring reseeding associated with the Soldier Canyon Mine. At the central mine facilities area, this includes all disturbances with the exception of those associated with Soldier Creek Road and the REI properties (Exhibit 5.21-1). At the sewage lagoons area, all disturbances will be revegetated with the exception of the access roads. These roads will be returned to public use and access.

The short-term goal of this revegetation plan is the immediate stabilization of the disturbed sites through erosion control. This objective will be achieved through controlled grading practices, proper seedbed preparation to encourage rapid plant establishments, inclusion of rapidly establishing species in seed mixtures to be planted and mulch applications.

The long-term goals are to establish useful, productive range and wildlife habitat and create an aesthetically acceptable site. These goals will be attained through the selection and placement of desirable and productive plant species, the return of the best available seedbed material to graded areas, and a commitment to monitor and maintain revegetated areas throughout the bond liability period.

#### Material Specifications

The following specifications are presented to identify the quality of materials that will be purchased to complete revegetation activities. All efforts will be made to follow these specifications although deviations may be required depending upon the commercial availability of these materials within the region.

#### Commercially Purchased Seed

Seed will be purchased in standard containers with seed name; lot number; percentages of purity, germination, hard seed; and percentages of maximum weed seed content clearly marked for each type of seed. Seed supplies will not contain the seeds of any state-recognized noxious weed species.

Only certified seed of named varieties will be used where varieties are specified and can be obtained.

### Seedlings

All accepted stock will be bare root or containerized and true to type and name. Stock will be "hardened off" prior to shipment so that stock is physiologically prepared for out-planting.

### Straw or Hay Mulch

Straw or hay mulch will be free of noxious weeds or noxious weed seeds. It will be delivered in an air-dry condition.

### Wood Fiber Mulch (Hydromulch)

Wood fiber mulch will be a natural, long-fiber product. The fiber, dye and any tackifying agent to be used will be non-toxic to plant and animal species. The supplier will be required to deliver mulch in standard manufacturer's packaging.

### Erosion Control Matting

Should matting be necessary components will be not-toxic to vegetation and the blanket smolder-resistant. The supplier will deliver the matting in standard manufacturer's packaging.

### Care of Delivered Materials

All seed and mulch material will be retained in shipping bags until used. The seed will be stored in a protected place to prevent them from coming in contact with precipitation or surface water.

Commercially purchased seedlings will be obtained as close to the time of planting as possible. Plants will be stored properly to:

- \* avoid or reduce moisture stress;
- \* avoid excessive heat or cold;
- \* protect plants from wind and mechanical damage.

#### 3.41.10 Revegetation Schedule

Revegetation will begin for each site component during the fall planting season following component closure, dismantlement or abandonment. All seeding will be completed by the Applicant during the fall planting season (Table 3.41-1).

#### 3.41.21 Revegetation Seed Mixtures

The following seed mixtures will be used to revegetate areas disturbed by mining and all associated activities. These seed mixtures have been developed for this

mine with respect to a number of considerations. The climate of the area was reviewed to assess the need for drought-tolerance in species selected. The vegetation report was evaluated to determine seed mixture constituents in light of production, cover, and diversity requirements. The soils report was reviewed to assess potential seedbed quality, among other things, and select species adapted to these assumed physical and chemical conditions. Plant species appropriate for enhancing wildlife habitat were selected on the basis of known wildlife needs and requirements. In addition, the operations plan was reviewed to determine the need for species with quick establishment, rapid spreading, and high erosion control potentials. The exact schedule will be determined during the revegetation year.

mine with respect to a number of considerations. The climate of the area was reviewed to assess the need for drought-tolerance in species selected. The vegetation report was evaluated to determine seed mixture constituents in light of production, cover, and diversity requirements. The soils report was reviewed to assess potential seedbed quality, among other things, and select species adapted to these assumed physical and chemical conditions. Plant species appropriate for enhancing wildlife habitat were selected on the basis of known wildlife needs and requirements. In addition, the operations plan was reviewed to determine the need for species with quick establishment, rapid spreading, and high erosion control potentials. The exact schedule will be determined during the revegetation year.

One temporary and five permanent seed mixtures are listed (Appendix 3-E). The temporary or "Intermediate" mixture will be used on those sites which are to be temporarily reclaimed, such as: topsoil storage areas, temporary road locations and unused disturbances associated with the Soldier Canyon Mine facilities that will be totally reclaimed at the conclusion of operations. Permanent mixtures will be seeded following seedbed preparations at the locations listed below. All grass and forb seed rates are given in lbs/ac pure live seed (PLS) for seeding. When the grass and forbs seeds are to be broadcast, the rates will be doubled. Rates for shrub species are given in lbs/ac PLS for broadcasting. All seeds will be broadcast and/or incorporated with a small amount of mulch and applied by hydroseeding equipment. Hydroseeding will be accomplished in two applications, the first being the application of the seed to the soil and the second an application of mulch and tackifier on top of the seed.

#### 3.41.22-24 Revegetation Methodology

The area will be graded to final contours, and then ripped to relieve compaction (see Exhibit 7.60-1). Ripping will be completed to a maximum depth of 2 feet. Final ripping depths will be determined by the materials being ripped, to prevent incorporation of less desirable soil/rock into more productive materials.

Following ripping, stockpiled soil will be applied to the ripped surface and left in an extreme roughened state. Prior to seeding, one ton per acre of certified noxious weed free hay will be incorporated by gouging into the soils. Except as noted all areas will be seeded the same.

Soil samples will be collected and sent to the laboratory for analysis to determine if amendments are necessary (see Section 2.43). Nutrients will be

applied in a single application. The area will be broadcast fertilized with the recommended fertilizer using a hand held "cyclone-type" seeder in smaller areas, applied in a hydroseeding mixture or with a rotary implement attached to the revegetation tractor in larger areas. Where possible, a ripper equipped tractor or other appropriate equipment will be used to incorporate the fertilizer into the soil. On slopes too steep to accommodate the use of a tractor or other appropriate equipment the fertilizer will be incorporated with the track hoe bucket teeth or other Division approved technology. All nutrients will be applied in a single application.

On slopes greater than 3:1, the rough, disturbed surface will be treated by traversing a dozer perpendicular to the slope contour to incorporate the nutrients.

All seeds will be broadcast and/or incorporated with a small amount of mulch and applied by hydroseeding equipment.

**Mulching Techniques.** Following seeding, the disturbed areas will be mulched with an organic mulching material. Organic mulch will be applied at the rate of 2000 pounds per acre and anchored with a tackifier.

**Irrigation, Pest and Disease Control.** No irrigation is planned and pesticides will not be used unless previously approved by the Division.

#### Revegetation Methodology - Topsoil Storage Site/Sewage Lagoons Area

Methodologies used to revegetate these disturbed areas will parallel those used to revegetate the central mine facilities area according to slope resultant from final grading.

As shown in Exhibit 5.42-3 the proposed final slopes of the topsoil stockpile area and sewage lagoons are  $\leq 3:1$  or 4:1 (Exhibit 5.42-2). There is no topsoil stockpile at the sewage lagoons because the topsoil was utilized in the embankments.

#### Revegetation Methodology - Riparian Area

The riparian zone to be reclaimed on the mine site exists at the central mine facilities area and covers approximately 2.4 ac. The area will be graded, resoiled, sampled, seeded and mulched. The seed mixture to be planted is

listed under Sec. 3.41.21. In addition, willow (Salix) and cottonwood (Populus) seedlings will be planted. Figure 3.41-1 depicts typical seedling planting plan layout. Cuttings/transplants/seedlings will be planted in the following manner.

Seedlings/transplants will be planted by first clearing a circle of 12 to 24 inches in diameter from which mulch materials and grasses will be cleared. The hole will be dug 4 to 6 inches deeper than the seedling roots to accommodate positioning of the seedling. Fertilizer will either be mixed with the loose soil from the hole or a fertilizer tablet will be planted with each seedling. After seedling placement, the hole will be backfilled with soil and fertilizer then lightly tamped. A gently sloped basin will be formed around the seedling to catch water. The basin will be mulched to aid in moisture retention.

#### 3.41.25 Reference Areas

Three reference areas (Exhibits 3.7-2 and 3.7-3/Map A), established in undisturbed near-natural conditions, and adjacent to existing or future mine operations are described in Appendices 3-A and 3-B of this application.

#### Revegetation and Stabilization Success Determination

As identified within the revegetation plan, the Applicant will stabilize and revegetate sites disturbed by mine related activities. Rangeland is the primary intended postmining land use with wildlife habitat as a secondary land use. The Applicant will plant species of the same seasonal variety as those existing in pre-mine vegetation types in support of these postmining land uses. However, because dense stands of shrubs such as those growing on the pre-mining lands are not always optimally beneficial to wildlife (due to the phenomenon of edge effect), the Applicant may reduce stocking rates at the time of reclamation to reflect a more beneficial density and spatial distribution. The reduced stocking rate would only be implemented if prior approval was granted by the regulatory authority. Such approval, would require that an alternate shrub density standard be developed based on the best technology available at the time of reclamation.

In accordance with DOGM's requirements, the Applicant will request initial bond release (60% of the bond) following successful completion of backfilling, regrading, topsoil replacement and drainage control of a particular bonded area. Release of an additional 25% of the bond (interim release) will be requested at the end of the 10 year responsibility period when bonded lands exhibit successful revegetation as proven by statistical testing between revegetated areas and

approved reference areas. The last 15% of the bond will be requested when the Applicant has successfully completed all mining activities in the permitted area in accordance with the approved reclamation plan.

With respect to interim bond release, the Applicant will begin the bond release responsibility period when topsoil redistribution and seeding, mulching, etc. has been completed. During this period of responsibility, activities pursuant to R645-301-244.300 and those Division approved husbandry practices will be performed without reinitiating the bond responsibility period. Any husbandry practices must be approved as an amendment to the Utah Coal Regulatory Program. A monitoring program as detailed in the next subsection will allow close scrutiny of the progress of reclamation and will identify problems requiring remedial management action.

To effect interim bond release at the end of the 10 year responsibility period, the Applicant will measure required vegetation variables (ground cover, herbaceous productivity, and woody plant density) once per year in each bonded revegetated area and corresponding reference area during each of the last 2 years of the period. Measurements will occur during the same time of the year. Productivity sampling will involve use of a simple random technique whereby 1 to 2 m<sup>2</sup> plots (rectangular in shape) will be clipped by life form for all current annual production. Sample parameters determined for these variables will be used to test the success of revegetation during each of these years and will prove establishment of: 1) adequate cover, 2) suitable productivity, 3) reasonable density and 4) adequate species composition. (See Monitoring of Reclaimed Areas Prior to Bond Release for additional revegetation monitoring information)

The estimated parameters for the variables of ground cover, herbaceous productivity and woody plant density will be obtained in a statistically adequate manner from both revegetated areas and corresponding reference areas. In accordance with R645-301-356.231, the Division has specified that the standards identified in the plan of 2506, 3479 and 3051 woody stems per acre for the mountain brush, deciduous streambank, and sagebrush-grass-juniper reference areas respectively will be used. These parameters will then be used to complete a statistical t-test of the sample means to determine equivalency between revegetated areas and reference areas.

Parameters to be used in this test are:

\* estimated mean (x) ground cover, current annual herbaceous

production, and woody plant density for each postmining revegetated type and corresponding reference area; and

- \* variance of the estimated mean ( $s^2$ ) for ground cover, current annual herbaceous production, and woody plant density for each postmining revegetated type and corresponding reference area.

Methods will be consistent between each revegetated area and its corresponding reference area. Once sampling has begun it will continue on each revegetated area and corresponding reference area under consideration for bond release until an adequate number of samples has been obtained. Adequacy of sampling will be obtained when :

$$nm \leq n$$

Where:

- n = the number of cover, productivity, or density samples taken from the  $i^{\text{th}}$  revegetated type or corresponding reference area;
- nm = the minimum number of samples necessary to satisfy required statistical criteria, and nm is calculated as follows:

$$nm = (s^2 t^2) / (dx)^2$$

Where:

- x = estimated mean cover, productivity, or density taken from the  $i^{\text{th}}$  revegetated type or corresponding reference area;
- s = the standard deviation of the estimated mean for cover, productivity, or density taken from the  $i^{\text{th}}$  revegetated type or corresponding reference area;
- t = the t distribution table value for the required sampling

confidence level;

- d = the percentage change in the mean required to be detected.

When adequate sample parameters have been obtained for all three variables in each revegetated type and corresponding reference area up for bond release, they may be used to test for revegetation success.

Once these parameters are obtained for each variable of each revegetated type the means can be quickly checked arithmetically to determine if each revegetated area's variables are greater than the reference area's corresponding variables,

or whether a t-test must be performed. The arithmetic check requires a determination of the status of the following inequality for all variables within each revegetated type:

$$x_{rv} - Cx_{rf} \geq 0$$

Where:

- $x_{rv}$  = estimated mean for cover, production, or density taken from each revegetated area under consideration for bond release;
- $x_{rf}$  = estimated mean for cover, production, or density taken from each corresponding reference area;
- C = the allowable reduction from the reference area standard; and for this postmining land use the reduction will be 0.9.

If this inequality fails for any given variable on any given revegetated type, then a t-test will be performed for that variable; otherwise the success test has been passed. To perform this t-test the sample t statistic ( $t_c$ ) must first be determined for the revegetated type under consideration:

$$t_c = (x_{rv} - Cx_{rf}) / \sqrt{s_p^2 (x_{rv} - x_{rf})}$$

Where:

$$s_p^2 = (n_{rv} + n_{rf}) / (n_{rv}n_{rf})$$

and:

$$s_p^2 = \frac{(n_{rv} - 1)s_{rv}^2 + (n_{rf} - 1)s_{rf}^2}{n_{rv} + n_{rf} - 2}$$

This sample t statistic will then be compared with the tabular t statistic ( $t_t$ ) at the alpha = 0.05 level (two-tailed test). Then, if:

$$t_c \leq t_t$$

is true, the test has been successful for that particular variable, revegetated type, and year. When the arithmetic test or the t-test has been passed for each revegetated type for cover, production, and density for the last two consecutive years of the responsibility period, and composition (diversity), as examined below, is satisfactory, then conditions for final bond release have been met.

At the point of requesting interim bond release, a discussion will be provided evaluating species composition/diversity in the revegetated areas with respect to diversity of species within the appropriate reference areas, the approved seed mixtures planted, and the approved postmining land use. This evaluation of species composition/diversity is necessarily a subjective analysis as the state-of-the art revegetation planning and success determination presented in this application does not lend itself to a purely quantitative evaluation. As

technology advances over the years, diversity testing may become more quantitative and at such time the Applicant will, if appropriate, attempt to include these techniques in the revegetation success determination. Presently, approved quantitative measures are shown in Appendix B of the Division's "Vegetative Information and Monitoring Guidelines." Therefore, the evaluation of species diversity of a reclaimed area up for release of bond will be based on a review of cover data obtained in response to the testing program identified above. These data will be evaluated in terms of: richness (number of species present); evenness (relative contribution of each species to the community); the ability and potential of reclaimed species to perpetuate themselves: the influence of volunteer species; and the capability of the reclaimed community to support the postmining land use.

Also, at the point of requesting interim bond release, the Applicant will show that revegetated lands are capable of supporting the postmining land use of rangeland if the postmining landowners intend to graze livestock. Otherwise, proof that revegetated areas can sustain grazing pressure will be unnecessary. To show this capability, newly revegetated areas will be subjected to grazing at properly controlled levels prior to the implementation of the previously discussed qualitative and quantitative evaluations of revegetation success.

Livestock will be introduced onto newly revegetated land only when it is able to sustain the impact. This determination will be made by a qualified range ecologist and is anticipated to occur between years 3 and 8 of the 10 year responsibility period..

#### Monitoring of Reclaimed Areas Prior to Bond Release

Prior to bond release success determination, reclaimed areas will be monitored to determine seedling survivability and the general success of revegetation efforts. Such monitoring will be performed during years 1, 2, 3, and 5 of the bond responsibility period, and will provide information with respect to whether or not remedial action will be necessary. Monitoring will consist of a mixture of qualitative observations and quantitative measurements during these four years.

During the first year, only qualitative observations will be made except for the determination of seedling survival in the area to be reclaimed to riparian vegetation. Qualitative observations will consist of an ocular evaluation of seeding success. All areas not exhibiting planted species establishment will be

identified for future evaluation and possible remedial treatment. Areas exhibiting extensive noxious weed establishment will be identified for immediate remedial treatment. Within the 2.4 ac area to be reclaimed to riparian vegetation as many of the planted seedlings as can be found will be examined to determine whether or not they have survived the first season. All remaining live plants will be enumerated and a wood stake driven beside the first 50 plants. Only these 50 plants will be checked in the three subsequent monitoring years.

During the second, third, and fifth years of the bond responsibility period the 50 marked riparian seedlings will be revisited to determine survival and vigor. Information collected in this manner will allow an evaluation of overall seedling survivability and whether remedial action will be necessary for reestablishing woody plant density. If, during year one, any areas were found without planted species establishment (barren areas), they will again be visited. If these areas are still barren or exhibit noxious weed growth, they will be identified for immediate remedial treatment. Following these less formal evaluations, a quantitative technique will be employed to determine whether or not adequate ground cover is reestablishing. During each of the last three monitoring years 10 permanent cover transects within each revegetated community will be measured for ground cover. These transects will involve the point-intercept technique (100 intercepts per transect) and data will indicate ground cover by species. Data collected in this manner will allow tracking of revegetation establishment over time and allow a projection of potential revegetation success. If poor establishment becomes apparent from review of this data, remedial action can occur.

#### Monitoring of Field Trial Sites

To determine the revegetation potential of the project area following decommissioning of the mine, the applicant established three field trial sites about the mine area. The first site was established immediately east of the sewage lagoon during the fall of 1982. The second site was established on the down slope of the R.E.I. storage area (topsoil stockpile) during the early fall of 1982. The third and last site was established on the north side of the new exhaust fan and substation site during the late spring of 1984. These sites are indicated on Exhibit 5.21-1 and 5.42-2.

The details of establishment, seedbed preparation, topsoil application, seed mix used, method of seeding, type and rate of mulching, type of protection, etc., are indicated below for each field trial site. Per faxed memo dated Oct 18, 1993,

Paul Baker, UDOGM - monitoring of Fan Site Test Plot discontinued 1994, Sewage Lagoon and Topsoil Storage Area Test Plots, discontinued 1997.

Sewage Lagoon Field Trial

- 1) Established - Fall 1982 (approximately 0.7 ac)
- 2) Seedbed preparation - Regrading by dozer (uncompacted soil depth 3-9")
- 3) Topsoil application - None (in place material used)
- 4) Seed mix used (as approved by BLM)

Grasses	-	Western Wheatgrass	1.5 #PLS
		Indian Ricegrass	1.5
		Crested Wheatgrass	1.5
Forbs	-	Yellow Sweetclover	1.0
		Utah Sweetvetch	0.5
		Ranger Alfalfa	1.0
		Small Burnet	1.0
Shrubs	-	True Mountain Mahogany	1.0
		Utah Serviceberry	0.5
		Fourwing Saltbush	<u>2.0</u>
			11.5

- 5) Method of seeding - Drill seeding
- 6) Type and rate of mulch used - None
- 7) Type and rate of fertilizer used - Ammonium nitrate @100 lbs/ac
- 8) Type of protection - None
- 9) Monitoring occurrence - mid-July 1983, 1984, 1985, 1986, 1987, 1992, 1997.

Topsoil Stockpile Site Field Trial

- 1) Established - Early Fall 1982 (approximately 0.1 ac)
- 2) Seedbed preparation - Stockpiled by loader (uncompacted soil depth 6-12")
- 3) Topsoil application - Entire trial site topsoil
- 4) Seed mix used (as approved by OGM)

Grasses	-	Western Wheatgrass	3.0 #PLS
		Intermediate Wheatgrass	4.0
		Crested Wheatgrass	3.0

	Orchard Grass	4.0
	Smooth Brome	2.0
Forbs	- Yellow Sweetclover	2.0
	Ranger Alfalfa	<u>1.0</u>
		19.0

- 5) Method of seeding - Hand broadcast and raking
- 6) Type and rate of mulch used - Straw crimped into soil @2 t/ac and netted with jute matting stapled into soil
- 7) Type and rate of fertilizer used - None
- 8) Type of protection - Berming with straw bales
- 9) Monitoring occurrence - mid-July 1983, 1984, 1985, 1986, 1987, 1992, 1997.

New Fan Site Field Trial

- 1) Established - Late Spring 1984 (approximately 0.1 ac)
- 2) Seedbed preparation - Material disturbed during fan construction (uncompacted soil depth 6")
- 3) Topsoil application - Entire trial site topsoil substitute material
- 4) Seed mix used (as developed by the applicant)

Grasses	- Western Wheatgrass	2.0 #PLS
	Bluebunch Wheatgrass	2.0
	Crested Wheatgrass	4.0
	Great Basin Wildrye	2.0
Forbs	- Yellow Sweetclover	1.0
	Lewis Flax	1.0
	Ladak Alfalfa	1.0
	Small Burnet	1.0
	Globemallow	1.0
Shrubs	- Bitterbrush	2.0
	Rabbitbrush	1.0
	Mountain Big Sagebrush	1.0
	Fourwing Saltbush	<u>2.0</u>
		21.0

- 5) Method of seeding - Hand broadcast and raking
- 6) Type and rate of mulch used - Straw crimped into soil @2 t/ac
- 7) Type and rate of fertilizer used - 40 lbs/ac sulfur coated urea 45-0-0;

30 lbs/ac treble super phosphate 0-46-0

- 8) Type of protection - Fencing
- 9) Monitoring occurrence - mid-July 1985, 1986, 1987, 1989, 1994, 1999.

A stipulation on the previous Soldier Canyon permit (ACT/007/018) required periodic monitoring of revegetated test plots located at various sites about the operation. A letter from J.T. Paluso, to D. Wayne Hedberg, Permit Supervisor for the OGM, September 25, 1984 identified the details and methodology to be used for this monitoring program. However, after review of these methods during the repermitting efforts, the Applicant has opted to upgrade the methodology in 1986 and thereafter, to provide more meaningful information. The upgraded methodology was verbally approved by OGM representatives (Lynn Kunzler on October 28, 1985, and Holland Shepherd on July 8, 1986) prior to use during the 1986 sampling season. Details of this upgraded methodology (and where it differs from the previous methods) are presented below.

1) The field trial study sites will be monitored from early to mid-July of the first, second, third, and fifth years and every fifth year after the initial planting season for the life of the field trial site. A report with the results of the monitoring will be submitted to OGM at the end of each monitored year. These reports will be appended to this sub-section of the application.

2) All sites will be systematically sampled (not randomly as previously performed) along 10 permanent transects of 10 m length. These permanent transects are marked at the three field trial sites with No. 4 rebar driven into the ground at each end of each transect.

3) Cover by species is determined by placing a pin frame (10 pins at 10 cm intervals) along each transect at each meter interval. First contacts by each pin are recorded as well as all subsequent contacts as the pin is lowered through the vegetation canopy. All contacts are utilized to determine total cover by species, while only the first contact is utilized to determine total floral cover, litter cover, rock cover and bare ground exposure.

4) Woody plant density will be determined as in previous years - by totally enumerating all plants within the field trial site. Woody plants on the sewage lagoon trial site will only be enumerated in the 35 x 45 ft site which contains the 10 permanent transects.

5) Estimated site productivity will be performed by estimating the total amount

of production in pounds per acre by life form (as opposed to estimating production for each species) for the entire trial site. This estimate after 1986 will be performed solely by representatives of the SCS.

Monitoring data (1985) from the field trial sites and riparian reference area using the old monitoring methods are presented in Illustration 3-1. This information was forwarded to OGM in October, 1985. Monitoring data collected in 1986 and subsequent years from the field trial sites using the upgraded methods are presented in Table 3.41-2.

### 3.42 Fish and Wildlife Requirements

The fish and wildlife control plan is a set of specifications and procedures to avoid potential adverse impacts to wildlife and their habitat.

Following mining, revegetation will be primarily concerned with replacing the pre-mining habitats. High value habitats will be restored.

#### 3.42.10 Enhancement Measures Used During the Reclamation and Postmining Phase

The Applicant proposes to restore the Soldier Creek stream channel and riparian vegetation, established vegetation for wildlife food and cover, place large landscape boulders for use as shelter and perches.

#### 3.42.20 Plant Species used for Habitat for Reclaimed Areas

The goals of the Applicant are to establish useful, productive range and wildlife habitat and create an aesthetically acceptable site. These goals will be attained through the selection and placement of desirable and productive plant species, the return of the best available seedbed material to graded areas, and a commitment to monitor and maintain revegetated areas throughout the bond liability period.

#### 3.42.30 Cropland Postmining Land Use

There are not any croplands within the Applicants existing or proposed permit area. Therefore, crop production is not one of the proposed postmining land uses.

3.42.40 Residential, Public Service or Industrial Postmining Land Use

Due to limitations imposed by topography, climate, soil conditions, inadequate water supply and other natural features, use of the land within the area has been limited primarily to livestock grazing, wildlife habitat and outdoor recreational activities.

3.50 Performance Standards

3.51 General Requirements

SC<sup>3</sup> feels that the plans in sections 3.30 through 3.42 comply with the revegetation and wildlife protection performance standards as indicated in R645-301-353. through -358.

3.52 Contemporaneous Reclamation

No contemporaneous reclamation is planned, except the 10 X 20 foot area north of the No.2 Fan.

3.53 Revegetation: General Requirements

SC<sup>3</sup> will establish on regraded and all other disturbed areas, vegetation cover that is in accordance with the approved permit and reclamation plan.

3.53.10 Vegetative Cover

The vegetative cover will be diverse, effective and permanent. Refer to Section 3.41.21 for additional information.

3.53.12 Comprised of Native Plant Species

The revegetation species will be comprised of species native to the area and purchased from suppliers who will certify their percentages of purity, germination, hard seed; and percentages of maximum weed seed content.

3.53.13 Equal in Cover to Natural Vegetation

The revegetation species will be equal or greater than the natural cover of the surrounding area. The testing parameters for equal cover are discussed in Section 3.41.25.

3.53.14            Revegetation Stabilizing Capabilities

The operations plan was reviewed to determine the need for species with quick establishment, rapid spreading, and high erosion control potentials. Species were chosen specifically for their high erosion control potentials.

3.53.20            Reestablished Plant Species

The Applicant proposes to return the disturbed land to the general land uses of the area (rangeland, wildlife habitat and recreational use). This will be accomplished by reestablishing the original vegetation (See Section 3.41.21). The vegetation will be similar if not identical to the original vegetation (unless specified otherwise). The revegetation species will have the same growing season as the adjacent areas.

3.54                Revegetation: Timing

The applicant will follow the recommended guidelines for revegetation as discussed in Section 3.41.10.

3.55                Revegetation: Mulching and Other Soil Stabilization Practices

Mulching techniques are found in Section 3.41 and 3.41.23. Soil will be stabilized using the "intermediate" seed mixture in Section 3.31.

3.56                Revegetation: Standards for Success

The standard for revegetation success are detailed in Section 3.41.25.

3.56.10            Reference Area Coverage and Effectiveness for Postmining Land Use

Refer to Section 3.53.

3.56.20            Application of Standards for Success

Prior to bond release success determination, reclaimed areas will be monitored to determine seedling survivability and the general success of revegetation efforts. Such monitoring will be performed during years 1, 2, 3, and 5 of the bond responsibility period, and will provide information with respect to whether

or not remedial action will be necessary. Refer to Section 3.41.25, subsection entitled "Monitoring of Reclaimed Areas Prior to Bond Release" for additional information.

Standards of success will be met in accordance with the approved postmining land use. Any area which was previously disturbed will be revegetated in accordance with Utah Coal Mining Regulations.

3.56.30 Siltation Structures

Siltation structures will remain in place until removal is authorized by the Division, but no sooner than two years after the last augmented seeding.

3.56.40 Siltation Structure Revegetation

Revegetation will occur following the removal of all siltation structures in accordance with the reclamation plan R645-301-353 through R645-301-357.

3.57 Revegetation: Extended Responsibility Period

SC<sup>3</sup> commits to provide extended responsibility for a period of ten years following reclamation and will submit if necessary, a detailed plan for extended responsibility three years prior to the planned cessation of operations.

3.58 Protection of Fish, Wildlife, and Related Environmental Values

SC<sup>3</sup> will minimize disturbances and adverse impacts on fish, wildlife and related environment as outlined in Section 3.33.

3.58.10 Endangered or Threatened Species

Endangered and threatened species and their respective habitat are discussed in Section 3.22.21 through 3.22.23. The Applicant will promptly notify the Division of any state- or federally-listed endangered or threatened species within the permit area.

3.58.20 Bald or Golden Eagle

The protection of bald and golden eagles will comply with the regulations. If significant subsidence is scheduled to occur during the April to July period of any year, a nesting survey will be completed to determine if any active nests are in the potential area of impact.

3.58.4 Wetlands and Riparian Vegetation

SC<sup>3</sup> will avoid disturbances to the wetlands and riparian vegetation. Wildlife habitat will be preserved and enhanced where disturbance has occurred.

3.58.5 Wildlife Protection From Manmade Structures

Measures intended to reduce or alleviate the effects of construction, mining and increased human activity on wildlife and related resources are detailed in Section 3.33 of this permit.

## References

Anderson, P. B. 1980. Personal Communication to Mary Boucek (ERT, Inc.). Eureka Energy Company, Salt Lake City, UT.

Boner, T. C., A. W. Heggen, C. McAda, C. Phillips, C. Berry and R. Wydoski. 1977. Final report - a survey of endangered, threatened and unique terrestrial and aquatic wildlife in Utah's coal planning area. Report to U.S. BLM on Contract No. YA-512-CT6-257, UDWR.

Clark, T. W. 1978. Current status of the black-footed ferret in Wyoming. Journal of Wildlife Management. 42(1). pp. 128-134.

Dalton, L. B. 1980. Personal communication to Mary Boucek (ERT, Inc.). March 11, 1980. Resource Analyst, UDWR, Price, UT.

Johnson, D. R. 1978. The study of raptor populations. University of Idaho Press, Moscow. 57 pp.