0059

ENERGY WEST Mining Co.
PO Box 310
Huntington, Utah 84528

OK

Copy Wayne Tracing
C/015/018

FAX TRANSMITTAL MEMO

Date 8/26/02

PLEASE DELIVER TELECOPY TO: Wayne Western, C

LOCATION: DOGM - Saltlake

FROM:

NUMBER OF PAGES, INCLUDING THIS PAGE: 2

COMMENTS:

RECEIVED
AUG 26 2002
DIVISION OF
OIL, GAS AND MINING

This facsimile message is confidential. It may contain privileged information or be subject to other confidentiality requirements and exemptions from disclosure under applicable law. It is solely intended for the above-named individual(s). If you are not the intended recipient(s), or the person responsible to deliver this message to the intended recipient(s), you are hereby advised that any dissemination, distribution or copying of the communication is prohibited. If you have received this facsimile in error, please notify the sender immediately by calling (801) 687-4750. (Collect, if necessary.)

faxform.wpd

Huntington Office:
(435) 687-9821
Fax (435) 687-2695
Purchasing Fax (435) 687-9092

Deer Creek Mine:
(435) 687-2317
Fax (435) 687-2285

Trail Mountain Mine:
(435) 748-2140
Fax (435) 748-5125

Deer Creek Mine Coal Surge Bin
Concrete Storage Volume for Final Reclamation

Location	Vol. of Concrete	
Misc. Culverts		
96" Culvert (Deer Creek Canyon)	25	
96" Outlet (Deer Creek Canyon)	25	
96" Culvert Thrust Block (8 in Deer Creek Canyon)	70	
54" Culvert Thrust Block (4 in Deer Canyon)	20	
36" Culvert Thrust Block (3 in Deer Canyon)	11	
30" Culvert Thrust Block (4 in Elk Canyon)	10	
Culvert inlet (Deer Creek Canyon)	20	
Culvert inlet (Deer Canyon)	25	
Culvert inlet (3 in Elk Canyon)	60	
Misc. Concrete		
Portal Retaining Wall	107	
Substation Pads	114	
Pad around Warehouse and Shop	889	
Beltline Retaining Wall	76	
Auxillary Fan Pad	22	
Curb and Gutter along Main Road	34	
Truck Loadout	39	
Tipple Sediment Traps (2)	22	
Weigh Bin	53	
Footers for Tipple Structures	413	
Sediment Box	62	
Sediment Pond Spillway	10	
Fan Pad & Retaining Walls	56	
Transformer Pad at Fan	3	
		1900 *
Specific Structures		
Redwood Tank Pad	8	
100,000 Gal. Water Storage Tank	27	
Water Treatment Plant	39	
Pumphouse	20	
Skimmer	39	
Bathhouse & Office	776	
Parking Gargage	235	
Warehouse & Shop	314	
Trash Hopper & Salt Storage	96	
Fuel Station	26	
Tire Dock	150	
Storage Shed	67	
Septic Tanks	20	
Rock Dust Silo	45	
Yard Storage Docks	271	
Trash Bunker at Tipple	14	
Coal Surge Bin Retaining Walls (2)	60	
Belt Drive Pad	19	
Belt Scale Pad	28	
Belt Take-up Pad	35	
Belt Structure Footers	100	
Total (c.y.)	4555	

* Make 4000 to account for unrepresented or unknown concrete.