0047

EMERY MINING CORPORATION

A SAVAGE BROTHERS COMPANY

March 29, 1984

ACT/015/019
#3

Mr. D. Wayne Hedberg
Reclamation Hydrologist
Division of Oil, Gas and Mining
State of Utah
4241 State Office Building
Salt Lake City, UT 84114

RE: DEER CREEK AND WILBERG
FLUME INSTALLATION

Dear Wayne:

To satisfy the concerns of the Division, Emery Mining is planning on installing two flumes to measure flows in Deer Creek below the mine and in the left fork of Grimes Wash at the waterfall above the mine.

The Deer Creek flume will be located on the permit boundry line as shown on the accompanying drawing. (UP&L - East Mountain Property) DS698C is a detailed drawing of the installation. To access this area from the mine road approximately 300' x 15' of the surrounding terrain will need to be traversed. Disturbance will be kept at a minimum. Field Specialist, Ken Wyatt has seen the proposed location.

Flume installation at the Wilberg Mine will be as shown on Drawing WS 669D in the Grimes Wash left fork. Flume size on both installations is 3" x 15". Maximum Flow 2.75 CFS.

Your prompt attention to this matter is appreciated. We hope to install the flumes before high waters.

Sincerely,

Larry J. Guymon

Larry J. Guymon, P.E.
Construction Manager

RECEIVED
APR 2 1984
DIVISION OF
OIL, GAS & MINING

cc: Steve McNeal, Bureau of Water Pol. Control
Chris Shingleton, UP&L
Chuck Semborski, UP&L
Jim Hamlin, EMC
Dave Bocook, EMC
Morgan Moon, EMC
Jim Atwood, EMC

P.O. Box 310 • Huntington, Utah 84528 • (801) 687-9821