0028

STATE OF UTAH
NATURAL RESOURCES
Oil, Gas & Mining

Norman H. Bangerter, Governor
Dee C. Hansen, Executive Director
Dianne R. Nielson, Ph.D., Division Director

355 W. North Temple • 3 Triad Center • Suite 350 • Salt Lake City, UT 84180-1203 • 801-538-5340

April 1, 1986

CERTIFIED RETURN RECEIPT REQUESTED
(P592 429 544)

Mr. Val Payne
Environmental Engineer
Emery Mining Corporation
P. O. Box 310
Huntington, Utah 84528

Dear Mr. Payne:

RE: Conditional Approval of Abatement Plan for Notice of Violation N86-9-2-2, #1 of 2, Sediment Control, Class I Haul Road, Utah Power & Light Company, Wilberg Mine, ACT/015/019, #4 and #7, Carbon County, Utah

The Division has completed the review of Utah Power & Light Company's abatement plan for Notice of Violation N86-9-2-2 submitted to the Division February 21, 1986. The proposed plans are acceptable and approval is hereby granted by the Division provided all construction is completed by June 1, 1986 and with the following stipulations:

1. The operator must install a drop drain against the curb in conjunction with the slotted drain on the east fork of the haul road. Because of the steep grade of the road, the possibility exists that sheet-flow will bypass the drop culvert inlet. It is highly recommended that a small asphalt berm be constructed immediately downstream of the inlet structure.

   If these recommendations are acceptable, please revise the appropriate detail design sheet(s) and submit 12 copies to update all approved MRP's on file.

2. The operator must maintain all present temporary sedimentation controls until construction is completed.

FILE COPY

If possible, please respond to the above stipulations by April 14, 1986. Thank you for your cooperation in this matter. Please contact me or Dave Hooper should you have any questions.

Sincerely,

D. Wayne Hedberg

D. Wayne Hedberg
Permit Supervisor/
Reclamation Hydrologist

DH/btb
cc: Allen Klein
Lowell Braxton
Joe Helfrich
Dave Hooper
Sue Linner
Holland Shepherd
0338R-3 & 4