

GENWAL COAL COMPANY

June 21, 1993

Mr. Daron Haddock
Division of Oil Gas & Mining
3 Triad Center, Suite 350
355 West, North Temple
Salt Lake City, Utah 84180-1203

RECEIVED

JUN 23 1993

DIVISION OF
OIL GAS & MINING

RE: Permit # ACT 015-032
Genwal Coal Company

Dear Mr. Haddock;

Please find enclosed fourteen (14) copies of plate 5-3 (surface facility map). Replace the present copies with the newly submitted ones.

Genwal coal company proposes to install a truck scale at our Crandall Canyon mine site. The present pad under the truck loadout will be enlarged to accommodate the scale. No additional excavation or disturbance will be encountered. An additional 6 cyd on concrete will be poured enlarging the present pad. The truck scale will be installed totally above ground. The costs for reclaiming the additional concrete and scale structure is estimated to be less than \$5,000 which can easily be covered in the contingency amounts figured into our present bond.

In addition please note the temporary Savage loadout has been removed. Savage completed the removal of the temporary facility in mid June.

Note the additional guard rail that is shown on the map near the retaining wall. This guard rail will be installed on USFS road right-of-way. The guard rail is being installed to improve safety during the winter months and was request by MSHA.

If you have any question or comments please call.

Sincerely;



R. Jay Marshall P.E. Larry W. Johnson
Chief Engineer Engineer
Genwal Coal Company Genwal Coal Company