

CO41602 Incoming
#4635 Sufco Mine
Kenneth E. May

Kenneth E. May General Manage: 597 South SR24 Salma Utah 84654 (435) 286-4400 Fax (435) 286-4499

June 27, 2014

Permit Supervisor, Utah Coal Regulatory Program Utah Division of Oil, Gas and Mining 1594 West North Temple, Suite 1210 PO Box 145801 Salt Lake City, UT 84114-5801

Re: Amendment to Revise Soil Storage Pile Quantities at Waste Rock Site, Canyon Fuel Company, LLC, Sufco Mine, C/041/002

Dear Sirs:

Please find enclosed with this letter two copies of an amendment to revise the quantities of subsoil and topsoil stored at the Waste Rock Site. The subsoil pile quantity has been increased by the addition of subsoil excavated during the soil nail wall project and the topsoil pile quantity has increased with the excavation for the Lift #5 Expansion.

If you have questions or need addition information please contact Vicky Miller at (435)286-4481.

CANYON FUEL COMPANY, SUFCO Mine

Kenneth E. May General Manager

Encl.

cc: DOGM Correspondence File

DIV. OF OIL, GAS & MINING

APPLICATION FOR COAL PERMIT PROCESSING

Permit Change New Permit Renewal Exploration Bond Release Transfer Transfer							
Permittee: Canyon Fuel Company, LLC							
Mine: Sufco Mine		Number: <u>C/041/0002</u>					
Title: Amendment to Revise Soil Storage Pile Quantities at Waste	Rock Site						
Description , Include reason for application and timing required to implement:							
Instructions: If you answer yes to any of the first eight (gray) questions, this application may require Public Notice publication.							
Yes No 1. Change in the size of the Permit Area? Acres: Disturbed Area: increase decrease. Yes No 2. Is the application submitted as a result of a Division Order? DO# Yes No 3. Does the application include operations outside a previously identified Cumulative Hydrologic Impact Area? Yes No 4. Does the application include operations in hydrologic basins other than as currently approved? Yes No 5. Does the application result from cancellation, reduction or increase of insurance or reclamation bond? Yes No 6. Does the application require or include public notice publication? Yes No 7. Does the application require or include ownership, control, right-of-entry, or compliance information? Yes No 8. Is proposed activity within 100 feet of a public road or cemetery or 300 feet of an occupied dwelling? Yes No 9. Is the application submitted as a result of a Violation? NOV # Yes No 10. Is the application submitted as a result of other laws or regulations or policies?							
Explain: Yes No 11. Does the application affect the surface landowner or change the post mining land use? Yes No 12. Does the application require or include underground design or mine sequence and timing? (Modification of R2P2) Yes No 13. Does the application require or include collection and reporting of any baseline information? Yes No 14. Could the application have any effect on wildlife or vegetation outside the current disturbed area? Yes No 15. Does the application require or include soil removal, storage or placement? Yes No 16. Does the application require or include vegetation monitoring, removal or revegetation activities? Yes No 17. Does the application require or include construction, modification, or removal of surface facilities? Yes No 18. Does the application require or include water monitoring, sediment or drainage control measures? Yes No 20. Does the application require or include subsidence control or monitoring? Yes No 21. Have reclamation costs for bonding been provided? Yes No 22. Does the application involve a perennial stream, a stream buffer zone or discharges to a stream? Yes No 23. Does the application affect permits issued by other agencies or permits issued to other entities?							
Please attach four (4) review copies of the application. If the mine is on or adjacent to Forest Service land please submit five (5) copies, thank you. (These numbers include a copy for the Price Field Office)							
I hereby certify that I am a responsible official of the applicant and that the information contains and belief in all respects with the laws of Utah in reference to commitments, undertakings, and	Name, Position, Date	QUELYN NEBEKER Notary Public State Of Utah mmission Expires 3/24/2015 Commission# 606049					
For Office Use Only:	Assigned Tracking Number:	Received by Oil, Gas & Mining RECEIVED					
		JUN 3 0 2014					
		DIV. OF OIL, GAS & MINING					

APPLICATION FOR COAL PERMIT PROCESSING Detailed Schedule Of Changes to the Mining And Reclamation Plan

Permitte		Fuel Compan		
_	Sufco Mine	D : G !!		it Number: C/041/002
Title: _	Amendment to	o Revise Soil	Storage Pile Quantities at Waste Rock Site	
application of conten	on. Individually ts, section of the	list all maps a e plan, or other	to the Mining and Reclamation Plan, which is required and drawings that are added, replaced, or removed from the information as needed to specifically locate, identify and and drawing number as part of the description.	ne plan. Include changes to the table
			DESCRIPTION OF MAP, TEXT, OR MATER	IAL TO BE CHANGED
Add	Replace	Remove	Waste Rock Disposal Site	
Add	Replace	Remove	Pages WRDS 3-4 and 3-5	
Add	Replace	Remove		
Add	Replace	Remove	MRP	
Add	Replace	Remove	Chapter 2, Page 2-20	
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace	Remove		
Add	Replace			
	er specific or sp and Reclamation		on required for insertion of this proposal into the	Received by Oil, Gas & Mining
nne 27, 2014			RECEIVED	
				JUN 3 0 2014
				DIV OF OIL CAC & MINISTER

CHAPTER 2 SOILS

Canyon Fuel Company, LLC SUFCO Mine

runoff and erosion. This soil will not be moved or disturbed until it is required for redistribution during final reclamation. A figure of the surveyed topsoil stockpile and estimated quantity of soil stored in the pile is included in Appendix 2-2. Plate 5-2B shows the as-built features associated with the overflow pond.

Topsoil from the Link Canyon Substation No. 1 will be placed and stored on the outslope of the pad. This storage area will be protected with berms and/or silt fences, a three-strand barbwire fence, and revegetated to control erosion. This soil will not be moved or disturbed until it is required for redistribution during final reclamation.

Soil from the Link Canyon Substation No. 2 will be placed in a soil stock pile located at the south end of the pad area. The storage area will be protected with berms and/or silt fences, a three strand barbwire fence, and revegetated to control erosion. This soil will not be moved or disturbed until it is required for redistribution during final reclamation.

Soil from the Link Canyon Mine Portal area will be placed in a topsoil pile located south of the disturbed portal pad area out of the floodplain (Plate 5-2F). The storage area will be protected by installing a topsoil storage sign at the base of the pile, berms and/or silt fences, a three strand barbwire fence, and protected from wind and water erosion by surface pitting the stockpile to retain moisture and reduce erosion and by being revegetated with a quick growing vegetative cover (standard seed mix in section 3.4.1.2 minus the shrubs and trees) to control erosion. This soil will not be moved or disturbed until it is required for redistribution during final reclamation. The surface of the topsoil pile will be pitted to reduce runoff and erosion. Vegetation removed during site construction, such as sage brush and other woody plants, will be placed on top of the pile.

Excess subsoil associated with construction of a run of mine coal stockpile and the West Lease portal tunnel development is stored at SUFCO Mine's waste rock disposal site. At the mine site the substation binwall has approximately 2,160 cubic yards of subsoil material and 5,300 cubic yards of road base, with the additional 11,747 cubic yards of subsoil material (West Lease/run of mine stockpile/ soil nail wall) being stored at the waste rock site there is a total of $\frac{18,720}{19,207}$ 19,207cubic yards (approximate) that will be available for use as subsoil material during final reclamation of the mine site facilities. Reference Appendix 2-3 for the analyses of the subsoil being stored at the waste rock site to be used during reclamation of the mine site.

VOLUME 3 WASTE ROCK DISPOSAL SITE

Canyon Fuel Company, LLC SUFCO Mine

3.1.5 Acid and Toxic Forming Materials

Based on analyses of material that has been placed in the waste rock disposal site to date, no acid forming problems are anticipated. There is a potential for borderline toxicity problems from boron. Samples of the waste material will be collected for every 10,000 tons deposited at the waste rock site and will be analyzed for acid or toxic forming potential. All identified potential acid or toxic forming materials will be buried or otherwise treated.

Copies of laboratory reports on toxicity/acid-base accountability from representative waste samples are included in Volume 8 of the M&RP prior to 2005 and starting in 2005 will be included in the annual report.

3.1.6 Subsoil Stockpile

Excess subsoil material and a small amount of topsoil from the minesite is stockpiled at the Waste Rock Disposal Site for possible use during final reclamation of SUFCO minesite facilities. The location of the subsoil and topsoil material is shown on Map 2. Total acreage of the subsoil stockpile and associated topsoil piles 1A and 1B is 1.19 acres. Approximately 11,341 11747 cubic yards of subsoil material and approximately 8.2 cubic yards of minesite topsoil material are stockpiled at the site. The associated original topsoil pile 1B and new topsoil piles 2 and 3 removed from the subsoil stockpile area contains about 756.4 cubic yards. The top 24 inches of soil material was removed from the subsoil stockpile area as described in Section 3.1.2, Site Preparation. This topsoil was stored along the westerly boundary and east of the subsoil stockpile as shown on Map 2. Topsoil handling procedures complied with those described in Section 3.2.3, Topsoil Handling. These topsoil stockpiles will be stored and seeded using the grasses and forbes of the standard seed mix, Table 4.6.1-1. When the subsoil and minesite topsoil are removed the topsoil will be redistributed and the area reclaimed and seeded in accordance with sections 4.5 and 4.6.

Subsoil material was placed in 2-3 ft. lifts using dump trucks and a D-7 Cat dozer. Exterior slopes of the subsoil stockpile are approximately 1v:1.25h. At this slope the material will be stable as placed. The subsoil stockpile was seeded using the grasses and forbes of the standard seed mix, Table 4.6.1-1. This subsoil may be taken to the minesite and used for fill material during final reclamation of the minesite.

Run off from the subsoil and associated topsoil stockpiles is collected and routed through a silt fence treatment located as shown on Map 2. The total acreage of the five stockpiles is 1.24 acres. Alternate sediment control measures are in place as described above. This area is classified as an approved Alternate Sediment Control Area (ASCA).

Topsoil and Subsoil Storage Piles at Waste Rock Disposal Site

TOPSOIL					
Description	Volume (cy) ^(a)	Area (acres)	Distribution Location		
1A	8.2	1.19*	Mine Site		
1B	456.9	0*	Waste Rock		
2	161.4	0.03	Waste Rock		
3	138	0.02	Waste Rock		
2, 3 & Lift 5 Exp.***	4114	0.24	Waste Rock		
Sediment Pond	634.9	0.293	Waste Rock		
Lift # 4 Area**	1847	0.34	Waste Rock		
TOTAL	3246.2 7061	NA	NA		
SUBSOIL					
Subsoil	11,260	0*	Mine Site		
Soil Nail Wall	81 487	0*	Mine Site		

⁽a) Estimated Quantity

3.2 Components of Operation

3.2.1 Sedimentation Pond

A sedimentation pond was constructed down gradient from the rock fill area to control sediment removed from the disturbed areas by surface runoff. The pond was constructed prior to disturbing

^{*} The acreage for Piles 1A,1B and Subsoil are combined. Soil Nail Wall quantity of subsoil removed will be submitted in as-built amendment by June 30, 2014.,

^{**} Topsoil stored in piles on top of Lift #4, estimated depth of stored topsoil - 3.5 feet

^{***}Topsoil excavated for the Lift 5 Expansion was combined into a single pile with piles 2 and 3.