m/031/003

Fax Transmission

Date: February 12, 2004

From: Unico Incorporated

W. Dan Proctor

To: State of Utah

Department of Natural Resources Division of Oil, Gas and Mining

Salt Lake City, Utah c/o Lynn Kunzler

Dear Lynn,

The 4 pages to follow were filed with the Division of Water Quality c/o Lyle Stott. The letter is a formal request for a construction permit for a second tailings pond at our Deer Trail facility, along with preliminary analysis of the solids and water contained in the slurried tailings as per DWQ. They are presently reviewing our proposal and will advice us on any additional requirements we may need to supply them with before a construction permit can be issued. Once we have all that is needed for DWQ we will send it on to DOGM for your consideration and records.

Sincerely,

W. Dan Proctor Project Mgr. Unico Inc.

RECEIVED

FEB 1 2 2004

DIV. OF OIL, GAS & MINING

Unico Incorporated P.O. Box 777 Magalia, California 95954

Send correspondence to:

February 06, 2004
e to: W. Dan Proctor
951 East 830 South
Pleasant Grove, Utah 84062

To: State of Utah
Division of Water Quality
c/o Lyle Stott
288 North 1460 West
P.O. Box 144870
Salt Lake City, Utah 84114-4870

Re: Deer Trail Mine / Mill, Piute County, Utah, construction permit for additional tailings pond

Dear Mr. Stott,

This letter is a formal request to attain a construction permit for a second tailings pond at our operations near Marysvale in Piute County, Utah. The tailings that will be put in this new pond will be the tails produced from processing dump material from the upper Deer Trail mine area. The dump material has been tested and has proven to be an excellent candidate for the recovery of gold through a simple gravity separation process utilizing a 20" Knelson concentrator, which we have recently installed at our milling facility. The present permitted pond is filled to the point that any additional tails will exceed its capacity.

The dump material will be trucked approximately 1.25 miles to our processing facility where it will be crushed and ground and processed. The process will remain a zero discharge facility. All the water used in this operation will be recycled.

The process is as follows:

- Ore is crushed in a portable Cedar Rapids crusher to ½" minus.
- 2. The crushed material will then be fed into a 6x9 Marcy grated ball mill for grinding at 70% solids.
- 3. The ground material will receive additional water to bring it to 25% to 30% solids and pumped to either the present spiral classifier or a future cyclone for classification.
- 4. The classified material will be fed into a floor sump where it will be pumped to the feed hopper of the Knelson concentrator.
- 5. The hopper contains a static screen to eliminate any oversized material, this material will be returned to the ball mill.

- The screened material will be processed in the Knelson concentrator which is designed to produce a gold rich concentrate.
- The tailings will then be slurry discharged to the new tailings pond.
- 8. The tails will be allowed to settle and water will be pumped back to the water surge tank in the mill building and reused in the process.

The initial feed water to the mill is drawn from Cottonwood Creek on the up-hill side of the processing facility. It has been determined that this water does not need to be analyzed being that this water is one of the main contributors to the present ground water system in the immediate area.

The outside dimensions of the new pond will be 135' wide by 160' in length, the inside dimensions will be 75' wide and 130' in length, and 8' deep at the deep end and sloping to 0' at the upper end. The pond will be underlaid with a non-woven geo-fabric cloth to be used as a barrier between the rock laden surface and a 6" layer of clay that will overlay the fabric.

The tailings or slurry produced from this process have been analyzed by American West Analytical Laboratories of Salt Lake City. The slurry was allowed to settle at the lab and a analysis for As, Ba, Cd, Cr, Cu, Pb, Hg, Se, Ag, and Zn was made of the solids, as per the Division of Water Quality. A separate analysis of Cn, F, pH, nitrate (N02 and N03), and nitrate/nitrite (N02/N03) was made of the water, as per the Division of Water Quality. The analysis reports from the laboratory are included with this letter.

We are anxious to get the needed construction permit as soon as possible in order to continue processing these dump materials. The gold produced will be the main source of our immediate cash flow. If you have any questions about this request please don't hesitate to call, 801-361-4242.

Sincerely,

W. Dan Proctor, Project Manger



## INORGANIC ANALYSIS REPORT

**AMERICAN** WEST ANALYTICAL **LABORATORIES** 

Client: Cash Account

Date Received: February 3, 2004

Contact: U. Dan Procter

Date Sampled: February 2, 2004

Unico Inc. / Deer Trail Mill Project:

Lab Sample ID:

L58760-01A

Field Sample ID: Knelson Tails

463 West 3600 South Salt Lake City, Utah 84115

TOTAL METALS Analytical Results	Units	Date Analyzed	Method Used	Reporting Limit	Analytical Results	
Arsenic	mg/kg-wet	2/5/2004 1:40:40 PM	6020	5.0	120	2
Barium	mg/kg-wet	2/5/2004 1:40:40 PM	6020	2.0	210	,
Cadmium	mg/kg-wet	2/5/2004 1:40:40 PM	6020	0.40	9.3	
Chromium	mg/kg-wet	2/5/2004 1:40:40 PM	6020	10	17	~
Copper	mg/kg-wet	2/5/2004 1:40:40 PM	6020	4.0	300	2
Lead	mg/kg-wet	2/5/2004 1:40:40 PM	6020	50	2,400	•
Mercury	mg/kg-wel	2/5/2004	7471A	0.040	0.28	
Selenium	mg/kg-wet	2/5/2004 1:40:40 PM	6020	5.0	33	2
Silver	mg/kg-wet	2/5/2004 1:40:40 PM	6020	5.0	62	,
Zinc	mg/kg-wet	2/5/2004 1:40:40 PM	6020	100	1,100	2

<sup>&</sup>lt;sup>2</sup> Analyte concentration is too high for accurate spike recovery.

Peggy McNicol **OA** Officer

(801) 263-8686 Il Free (888) 263-8686 Fax (801) 263-8687 il: awal@awal-Labs.com

> Kyle F. Gross Laboratory Director

Report Date:

February 6, 2004

Page 1 of 2

<sup>~</sup> Poor spike recoveries due to suspected sample non-homogeneity.



## INORGANIC ANALYSIS REPORT

**AMERICAN** WEST

Client: Cash Account

Contact: U. Dan Procter

ANALYTICAL LABORATORIES

Date Sampled: February 2, 2004

Date Received: February 3, 2004

Project: Unico Inc. / Deer Trail Mill Lab Sample ID:

Field Sample ID: Knelson Tails

1.58760-01

463 West 3600 South Salt Lake City, Utah 84115

Analytical Results	Units	Date Analyzed	Method Used	Reporting Limit	Analytical Result
	mg/kg-wet	02/05/04	9012A	0.12	1.61
Cyanide Fluoride	mg/L	02/04/04	340.2	0.10	2.1
Nitrate (as N)	mg/L	02/04/04 2:19 pm	353.2	0.010	,2.0
Nitrate (as N) Nitrate/Nitrite (as N)	mg/L	02/04/04	353.2	0.010	2.0
Nitrite (as N)	mg/L	02/04/04 2:19 pm	353.2	0.010	0.020
pII	pH Units	02/03/04 8:40 pm	9045C	0	7.65 *

(801) 263-8686 oll Free (888) 263-8686 Fax (801) 263-8687

nail: awai@awal-Labs.com

\* The sample pH was measured in water at 25 degrees Celcius

Spike recovery indicates matrix interference. The method is in control as indicated by the laboratory control sample (LCS).

Kyle F. Gross Laboratory Director

> Peggy McNicol QA Officer

> > Released by: anoratory Supervisor

Report Date:

February 6, 2004