RECLAMATION SURETY ESTIMATE		
Unico Incorporated	last revision 05/24/05	
Deer Trail Mine & Mill	filename M031-003 xls]
DOGM file Number M/031/003	Piute County	!
Prepared by 1 to State Division of Oil Con 8 Mining (D.I)	•	

*** Bond has been amended to include additional structures at the site (fine ore bin & upstairs annex)
(Itemized estimate under separate cover)

No other changes made to the bond - bond escalation date remains 2009

4	date 10/07/02		table at the book ap		Note: actual unit costs may vary according to site cond
	acres			treatments =	Amount of disturbed area which will receive reclamation
ļ	acres				Estimated total disturbed area for this mine =
Note	<u>\$</u>	\$/unit	<u>Units</u>	Quantity	Activity Control of Control
(1)	1600	1600	lump sum	1	afety gates, signs, etc. (6 signs & 2 gates)
(2)	17066	0.26		65640	emolition of buildings and facilities
	3936	246	hours	16	Demolition of other buildings and structures
1		12900	lump sum		**Demolition of fine ore bin
1	3300	3300	lump sum	1	**Demolition of upstairs annex
	2460	246	hours		temoval & burial of ball mill floor & pedestal (dozer)
		15	hours		emoval of site fences
(3)		55	trips		ebris & equipment removal - trucking
(4)	0	60	ton	0	ebris & equipment removal - dump fees
		180	hours		ebris & equipment removal - loading trucks w/FE loader
1''		15	hours		emolition & debris removal - general labor
1		1500	lump sum		onstruct bat gate at PTH portal
(7)	1839	613	acre	3	egrading facilities areas (2 ft depth)
(8)	8910	06	CY	14850	egrading waste dump slopes
(9)	246	246	acre		ipping waste dump tops
		246	acre	6.65	ipping stockpile & compacted areas
(e)	123	246	асге	0.5	ipping access roads - dozer
	123	246	acre	0.5	egrading access roads - dozer
(9)	492	246	hours	2	emoval of water tank at PTH portal (dozer)
	738	246	hours	3	econtour fresh water pond
	180	15	hours	12	emoval of power lines
1	5000	5000	lump sum		emoval of substation (UP&L cost quote)
	1968	246	hours		emove culverts
1	45	15	hours	3	emove fresh water pond liner
	45	15	hours		emove reagent trailer fence
1	984	246	hours		rackhoe for access road reduction
	7200	180	hours	40	EL to load replacement soil
]	16115	55		293	ruck transport soil to mill site
(12)	4247	0.58	•	7322	opsoil redistribution- dozer
(00)	2283	300	acre	7.609	omposted manure (10 ton/acre)
/	3314	240		13.81	roadcast seeding
(00)	641	50	acre	12.81	eneral site cleanup & trash removal
(00)	8000	2000	equip	4	quipment mobilization
(15)	11515				eclamation supervision (10% of surety estimate)
ľ <i>′</i>	126671		Subtotal	-	
	12667			_	% Contingency
	139338		Subtotal	;	contact for Evenes at 0 500/
	19003			-	scalate for 5 years at 2.59% per year
ı	158341		Total	•	