

*mine file*

# BARRICK MERCUR GOLD MINES, INC.

July 12, 1985

RECEIVED

JUL 12 1985

Mr. Lowell Braxton, Administrator  
Mineral Resource Development & Reclamation Program  
Utah State Department of Natural Resources  
Division of Oil, Gas & Mining  
355 West North Temple  
3 Triad Center, Suite 350  
Salt lake City, Utah 84074

DIVISION OF OIL  
GAS & MINING

Dear Lowell:

SUBJECT: Mercur Gold Mine ACT/045/013. Tooele County, Utah  
(with Proposed Amendment)

Pursuant to our July 10, 1985 meeting, please find attached the recalculated bond estimates for our existing permit and the proposed dump leach operation. As shown, the new bond estimate for the existing permit is \$3,103,374 and \$1,094,219 for the ultimate dump leach operation. An inflation of 3.79% was applied to both items.

In summary, the new bond total will be \$4,197,593 as opposed to the existing bond amount of \$5,745,331 (both less the \$33,641 clean-up and salvage as approved by P. Littig's letter dated January 13, 1983). We are therefore requesting approval to bond both items at \$4,197,593.

Please review the attached spread sheets and advise if you have any questions. We trust this will allow for timely conditional approval of dump leach Area 1 by July 19, 1985.

Respectfully,



Glenn M. Eurick  
Environmental & Occupational Health Coordinator

GME/cg

Attachment

cc: J. C. Sprague

12-14-82

Revised 7-12-75

by: G. M. Eurick

Page One

ITEM #	ACTIVITY	AREAS EXCLUDED	AREAS INCLUDED	UNITS ACRES	HOURS WORK/ACRE	TOTAL HOURS/AREA	REQUIRED EQUIPMENT	\$/HOUR (includ. operator)	TOTAL COST/AREA	GENERAL NOTES
1	Clean-up and salvage	Foundations	structures(a) equipment	N/A			Loaders (2) Trucks (2) Crane (1)		33,640	All mining and process equipment and facilities have salvage value to balance demolition costs. Non-process buildings have less salvage value.
1	Subtotal								33,640	
2	Grading & Shaping	Open Pit Tailings Pond Public Roads	A. Dumps (b) B. Soils Piles C. Waterbars D. Mill Site E. Culvert Removal (c)	60 ac. 18 ac. 50 32 ac. 3 culverts 12 culverts	13 6 0.5 12 3.7 2.25	784 108 25 384 11.7 27 1,301	D8K Dozer D8K Dozer D8K Dozer D8K Dozer Cat 225 Excav Cat 225 Excav	\$114 Hr. \$114 Hr. \$114 Hr. \$114 Hr. \$140 Hr. \$140 Hr.	148,815 5,340	Aft. topsoil removal Covering foundations Haul Road Culverts Access Road Culverts
Calculations										
<p>D8K Dozer</p> <p>1.301 hrs ÷ 176 Hrs/mth = 7.4 mths.</p> <p>RB Pg 9-92 7.4 mths x \$10,045/mth \$ 74,333 Equip</p> <p>RB Pg 9-92 1301 hrs x \$28.00/hr \$ 36,428 O.C.</p> <p>Means pg 415 1301 hrs x \$29.25/hr \$ 38,054 Labor</p> <p><u>\$148,815</u></p> <p>Cat 225 Excav.</p> <p>38.1 hrs ÷ 8 hrs/day = 4.8 days</p> <p>(a) 4.8 days x \$755/day \$3,624 Equip</p> <p>(a) 38.1 hrs x \$15.80/hr \$ 602 O.C.</p> <p>(a) 38.1 hrs x \$29.25/hr \$1,114 Labor</p> <p><u>\$5,350</u></p> <p>(a) RB Pg 10-14</p> <p>(a) RB Pg 10-14</p> <p>(a) Means Pg 415</p>										
2	Subtotal								154,155	

(a) See attached demolition activity cost

(b) See attached dump reggrading profile

(c) See attached culvert removal profile

(continued)

ITEM #	ACTIVITY	AREAS EXCLUDED	AREAS INCLUDED	UNITS ACRES	HOURS WORK/ ACRE	TOTAL HOURS/ AREA	REQUIRED EQUIPMENT	\$/HOUR (includ. operator)	TOTAL COST/ AREA	GENERAL NOTES
3	Road Ripping	Public Roads Tailings Pond Access	All Dump Roads	15 Ac.	1	15	D-8K Dozer	\$139.00 Hr.	\$2,089	w/3 shank ripper at 2.2 mph, double coverage.
<u>Calculations</u>										
	RB Pg 9-92	*Monthly Rate \$ 10,045/mth ÷ 176 hrs/mth = \$57/hr								
		15 hrs x \$57/hr = \$855 Equip								
	RB Pg 9-92	15 hrs x \$28/hr = \$420 O.C.								
	Means Pg 415	15 hrs x \$29.25/hr = \$439 Labor								
	RB Pg 9-110	15 hrs x \$25/hr = \$375 3shk. Ripper								
2	Subtotal	\$2,089								
4	Scarifying before Topsoiling + Scarifying Topsoil Before Seeding	Open Pit Public Roads Plant Access Road	Plant Site Dump Tops Tailings Pond	208 Ac.	0.33	69 } 138	16-G Grader	\$139.50 hr	\$9,626	16g ripper/scarifier at 2.4 mph.
<u>Calculations</u>										
		138 hrs 176 hrs/mth = 0.8 mths								
	RB Pg 9-6	0.8 mths x \$11.560/mth = \$9,248 Equip								
	RB Pg 9-15	138 hrs x \$17/hr = \$2,346 Ripper/Scarifier								
	Means Pg 415	138 hrs x \$29.25/hr = \$4,036 Labor								
	RB Pg 9-6	138 hrs x \$26.25/hr = \$3,622 O.C.								
		\$19,252								
4	Subtotal	\$19,252								

(continued)

Plant Site = 32 acres  
Dump Tops = 95 acres  
Tailings Pond = 81 acres  
Total = 208 acres

ITEM #	ACTIVITY	AREAS EXCLUDED	AREAS INCLUDED	UNITS ACRES	HOURS WORK/ACRE	TOTAL HOURS/AREA	REQUIRED EQUIPMENT	\$/HOUR (includ operator)	TOTAL COST/AREA	GENERAL NOTES
5a	Topsoil Replacement Level Area	Open Pit Public Roads Plant Access Road	Plant Site Dump Tops Tailing Ponds Ripped Roads	341.3 ac ft N/A $\frac{14,867,028 \text{ ft}^3}{27} = 550,630 \text{ yds}^3$	N/A		Cat 6273 1 ea 20 yd <sup>3</sup> Elev. Scraper Self Prop Push-Pull 1500' Haul 1/4 Push Dozer 4 loads/br 80 yd <sup>3</sup> /hr	\$1.98/yd <sup>3</sup> calc.	\$1,091,079	Scraper will load, haul and spread soil to: Plant Site = 32 Acres Dump Tops = 95 Acres Ripped Roads = 15 ac Settling Ponds = 6 ac
<div>RB Pg 9-83 39 mths x \$15,195/mth = \$592,605 Equip } RB Pg 9-83 6,885 hrs x \$43.15/hr Oper \$ = \$297,088 O. C. } \$1,091,079 Means Pg 415 6,885 hrs x \$29,25/hr Labor = \$201,386 Labor }</div>										
<div>6,883 hrs/176 hrs/mth = 39 mths 550,630 yds<sup>3</sup>/hr = 6,883 hrs 1 mth = 176 hrs</div>										
<div>Tailings Pond = 81 ac Tailings Dam Borrow area = 21.8 102.8 x 2.6' = 267.3 Ac. Ft.</div>										

Calculations

5b	Topsoil Replacement	Open Pit Public Roads Road Tailings Pond Access Dump Tops Tailings Ponds Ripped Roads Settling Ponds Topsoil Piles	Dump Slopes Tailings Dams Additional Clearing Tailings Dam Excess Stockpile	128.6 Ac Ft N/A $\frac{14,867,028 \text{ ft}^3}{27} = 550,630 \text{ yds}^3$	N/A		5 yd <sup>3</sup> H550 Loader D8K Dozer	\$2.95	\$611,179	Separate load, haul, spread operations to cover; Dump Slopes = 57 acres 57 x 0.5' = 28.5 Ac Ft Tailings Dams = 25 ac Additional Clearing = 6.3 acres Excess Stockpile = 7.2 Acres 38.5 acres x 2.6' = 100.1 Ac Ft
----	---------------------	---	---	---	-----	--	--	--------	-----------	---

Calculations

50 Wabco (50T/31yd<sup>3</sup>)  
4 Lds/hr x 31 yd<sup>3</sup>/Ld → 124 yds<sup>3</sup>/hr  
207,475 yds<sup>3</sup> ÷ 124 yds<sup>3</sup>/hr → 1,673 hrs  
1,673 hrs/176 hrs/mth → 9.5 mths  
RB Pg 20-14 9.5 mths x \$13,830/mth → \$131,385 Equip  
RB Pg 20-14 1673 hrs x \$30.15/hr → \$50,441 O.C.  
Means Pg 415 1673 hrs x \$29.25/hr → \$48,935 Labor } \$230,761

Pg 9-58 Blue Book  
IH 550 Loader

RB Pg 9-58 9.5 mths x 9,615/mth → \$91,342 Equip  
RB Pg 9-58 1673 hrs x \$29.25/hr → \$48,935 O.C.  
Means Pg 415 1673 hrs x \$29.25/hr → \$48,935 Labor  
\$189,212

D8K Dozer

RB Pg 9-92 9.5 mths x \$10,045/mth → \$95,427 Equip  
RB Pg 9-92 1673 hrs x \$28.00/hr → \$46,844 O.C.  
Means Pg 415 1673 hrs x \$29.25 → \$48,935 Labor  
\$191,206

5 Subtotal \$1,702,258

ITEM #	ACTIVITY	AREAS EXCLUDED	AREAS INCLUDED	UNITS ACRES	HOURS WORK/ ACRE	TOTAL HOURS/ AREA	REQUIRED EQUIPMENT	\$/HOUR (includ. operator)	TOTAL COST/ AREA	GENERAL/NOTES
6	Cover Crop Seeding	All other areas	-Dump Tops -Tailings Pond	176 Ac. 176 Ac.	0.25 44		Seed Drill and Tractor	70.00/hr. 7.50/Ac.	3,080 1,320	Dump Tops = 95 acres Tailings Pond = 81 acres
6	Subtotal								4,400	
7	Perennial Seeding	-Open Pit -Public Roads -Plant and Tailings Access Roads	-Plant Site -Tailings Facility -Dumps -Soil Piles -Sediment Ponds	407 Ac. 407 Ac.	0.17 69.2		Hydroseeder Seed Material	95.00/hr. 166.00/Ac.	6,573 67,562	Plant Site = 32 acres Tailings = 106 acres Dump = 245 acres Soil Piles = 18 acres Sed. Ponds = 6 acres
7	Subtotal								74,135	
8	Fertilizing	As in #7	As in #7	407 Ac.			Fertilizer Mtr. 240 #/Ac. at 0.25/#	60.00/Ac.	24,420	Fertilizer is applied by hydroseeder with seed.
8	Subtotal								24,420	

(Continued)

ITEM #	ACTIVITY	AREAS EXCLUDED	AREAS INCLUDED	UNITS ACRES	HOURS WORK/ ACRE	TOTAL HOURS/ AREA	REQUIRED EQUIPMENT	\$/HOUR (includ. operator)	TOTAL COST/ AREA	GENERAL/NOTES	
9	Planting Trees & shrubs	-Open Pit	-Plant Site	341 Ac.							
		-Tailings Pond	-Soil Stockpiles								Plant 225 stems/acre Plant Site = 32 acres
			-Tailings Dams								Soil piles = 18 acres
		-Public Roads	-Dumps								Tailings Dams = 25 acres
		-Plant Access Road	-Ripped Roads								Dumps = 245 acres
		-Tailings Pond Access	-Settling Ponds							Ripped Roads = 15 acres Settling Ponds = 6 acres Total = 341 acres	
9	Subtotal								153,450		
10	Reseeding	As in #7	As in #7	(see notes)							
				204 Ac.	0.17	34.7	Hydroseeder	95.00/hr	3,295	based on perennial seeding of 50%	
				204 Ac.			Seed Material	166.00/Ac.	33,864	of original seeding area	
				204 Ac.			Fertilizer	2.40/Ac.	490		
10	Subtotal								37,649		
11	Monitoring	None	A11	A11							
					None	1000/yr.	3,000	annual inspections for 3 years following reclama- tion			
11	Subtotal								3,000		

(Continued)

(Continued)

ITEM #	ACTIVITY	AREAS EXCLUDED	AREAS INCLUDED	UNITS ACRES	HOURS WORK/ ACRE	TOTAL HOURS/ AREA	REQUIRED EQUIPMENT	\$/HOUR (inc lud. operator)	TOTAL COST/ AREA	GENERAL/NOTES
12	Total								2,174,808	
13	Contingency								217,481	10%
14	Final Total								2,392,289	

3.79%/Year

1985 - 2,392,289  
1986 - 2,482,957  
1987 - 2,577,061  
1988 - 2,674,312  
1989 - 2,775,668  
1990 - 2,880,866  
1991 - 2,990,051  
1992 - 3,103,374



MERCUR MINE DUMP LEACH RECLAMATION COST ESTIMATE  
 Prepared July 12, 1985  
 by G. M. Eurick

ITEM	ACTIVITY	AREAS INCLUDED	UNITS ACRES	HRS. WORK/ACRE	TOTAL HRS./AREA	REQUIRED EQUIPMENT	TOTAL \$/HR.	TOTAL \$/AREA	GENERAL NOTES	CALCULATIONS & REFERENCES
1	Grading/Shaping	Dumps Culverts	10 5 Culv.(Est)	13 3/Culv.	130 15 Est	D8K Dozer, Cat 225 Excav.	\$114.25(1) \$140.73(2)	\$ 14,852 \$ 2,111		(1) Monthly Rate Applied \$10,045 pg 9-92 RRB \$10,045 ÷ 176 hr/mo = \$57/hr Equip 130 hr x \$57/hr = 7,410 Equip 130 hr x \$28/hr = \$3,640 Oper \$ RRB 9-92 130 hr x \$29.25/hr = \$3,802 Labor Means pg 415 SUBTOTAL \$ 14,852
2	Road Ripping	Dump Roads	2	1	2	D8K Dozer, W/3 Shank Ripper	\$139	\$ 278		(2) Daily Rate Applied \$755 pg 10-14 RRB 15 hr ÷ 8 hr/day = 1.9 days 1.9 days x \$755/day = \$1,435 Equip 15 hr x \$15.80/hr = \$237 Oper \$ RRB pg 10-14 15 hr x \$29.25/hr = \$439 Labor Means pg 415 SUBTOTAL \$ 2,111
										TOTAL \$ 16,963
										Monthly Rate Applied \$10,045 pg 9-92 RRB \$10,045 ÷ 176 hr/mo = \$57/hr Equip 2 hr x \$57/hr = \$114.00 Equip 2 hr x \$25/hr = \$50.00 3 Shank Rip RRB pg 9-110 2 hr x \$28/hr = \$56 Oper \$ RRB pg 9-92 2 hr x \$29.25 = \$58 Labor SUBTOTAL \$ 278

ITEM	ACTIVITY	AREAS INCLUDED	UNITS ACRES	HRS. WORK/ACRE	TOTAL HRS./AREA	REQUIRED EQUIPMENT	TOTAL \$/HR.	TOTAL \$/AREA	GENERAL NOTES	CALCULATIONS & REFERENCES
3	Clay Cap Placement	Dump Tops	42 (101,640 Yds )	N/A	N/A	Cat 627B Scraper	\$1.99/yd <sup>3</sup>	\$201,388	1.5' Clay on 42 acres 4 Loads/hr 80 yd /hr	101,640 yd ÷ 80 yd <sup>3</sup> /hr = 1,270.5 hrs 1,270.5 hr ÷ 176 hr/mo = 7.2 mo 7.2 mo x \$15,195/mo = \$109,404 Equip, RRB pg 9-83 1,270.5 hr x \$43.15/hr = \$54,822 Oper \$/hr, RRB pg 9-83 1,270.5 hr x \$29.25/hr = \$37,162 Labor, Means pg 415 SUBTOTAL \$201,388
4	Soil/Topsoil Place, Level Areas	Ripped Roads Dump Tops	2 Acres 42 Acres 44 Acres (1613 yd <sup>3</sup> ) (+271,040 yd <sup>3</sup> ) 272,653 yd	N/A	N/A	Cat 627B Scraper	\$1.986/yd <sup>3</sup>	\$541,522	1' Topsoil 1' Topsoil, 3' Subsoil 20 yd <sup>3</sup> /Load 4 Loads/hr	272,653 yd <sup>3</sup> - 80 yd <sup>3</sup> /hr = 3,408 hr 3,408 hr - 176 hr/mo = 19.4 mo 19.4 mo x \$15,195 mo = \$294,783 Equip, RRB pg 9-83 3,408 hr x \$43.15 hr = \$147,055 Oper \$, RRB pg 9-83 3,408 hr x \$29.25 = \$99,684 Labor Means pg 415 SUBTOTAL \$541,522
5	Topsoil Replace Steep Areas	Dump Faces	19 Acres (9.5 A.F.) (15,327 yd <sup>3</sup> )	N/A	N/A	503 Wabco (31 yd <sup>3</sup> ) (1) IH 550 Loader(2) D8K Cat Dozer(3)	\$2.95/yd <sup>3</sup>	\$ 45,215	0.5' Topsoil Depth	(1) 4 Loads/hr x 31 yds <sup>3</sup> /ld = 124 yd <sup>3</sup> /hr 15,327 yd <sup>3</sup> ÷ 124 yd <sup>3</sup> /hr = 124 hr 124 hr ÷ 176 hr/mo = 0.7 mo 0.7 mo x \$13,830/mo = \$9,681 Equip RRB pg 20-14 124 hr x \$30.15/hr = \$3,739 Oper \$ 124 hr x \$29.25/hr = \$3,627 Labor Means, pg 415 \$ 17,047

ITEM	ACTIVITY	AREAS INCLUDED	UNITS ACRES	HRS. WORK/ ACRE	TOTAL HRS. / AREA	REQUIRED EQUIPMENT	TOTAL \$/HR.	TOTAL \$/AREA	GENERAL NOTES	CALCULATIONS & REFERENCES
------	----------	----------------	-------------	-----------------	-------------------	--------------------	--------------	---------------	---------------	---------------------------

(2) 0.7 mo x \$9,615/mo = \$6,731  
Equip  
124 hr x \$29.25/hr = \$3,627 Oper \$  
RRBB pg 9-58  
124 hr x \$29.25/hr = \$3,627 Labor  
Means pg 415  
\$ 13,985

(3) 0.7 x \$10,045/mo = \$7,032 Equip  
124 hr x \$28.00/hr = \$3,472 Oper \$  
RRBB pg 9-92  
124 hr x \$29.25/hr = \$3,627 Labor  
Means pg 415  
\$ 14,131

SUBTOTAL \$ 45,163

6	Topsoil Scarify Level Areas	Dump Tops Ripped Roads	42 2 44	0.33	14.5	Cat 16G Grader, w/Ripper/Scarifier	\$139.50	\$2,023±		14.5 hr ÷ 176 hr/mo = 0.082 Mo 0.082 mo x \$1,560/mo = \$953 Equip RRBB pg 9-6 14.5 hr x \$17/hr = \$247 Ripper RRBB pg 9-15 14.5 hr x \$26.25/hr = \$381 Oper \$ RRBB pg 9-6 14.5 hr x \$29.25/hr = \$424 Labor SUBTOTAL \$ 2,005
---	-----------------------------	------------------------	---------------	------	------	------------------------------------	----------	----------	--	--

7	Cover Crop Seeding	Dump Tops, Faces, Roads	42 19 2 63	0.25	16	Seed Drill/Tractor Seed →	\$70 \$7.50/Acre	\$1,120 \$ 473		\$ 1,593
---	--------------------	-------------------------	---------------------	------	----	------------------------------	---------------------	-------------------	--	----------

Mercur Mine Dump Leach Reclamation Cost Estimate  
Page 4

ITEM	ACTIVITY	AREAS INCLUDED	UNITS ACRES	HRS. WORK/ACRE	TOTAL HRS./AREA	REQUIRED EQUIPMENT	TOTAL \$/HR.	TOTAL \$/AREA	GENERAL NOTES	CALCULATIONS & REFERENCES
8	Perennial Crop Seeding	Dumps, Roads Soil Piles	42+19+2+1 = 64	0.17	11	Hydroseeder Seed	\$95/hr \$166/acre	\$ 1,045 \$ 10,624		
9	Fertilizing	Dumps, Roads Soil Piles	42+19+2+1 = 64	0.17	11	Hydroseeder Fertilizer	\$95/hr \$166/acre	\$ 1,045 \$ 10,624		
10	Planting	Dumps, Roads Soil Piles	42+19+2+1 = 64	---	---	Materials Install.	\$0.65/plant \$1.35/plant	\$ 9,360 \$ 19,440	225/Acres = 14,400 plants	
11	Reseeding	Dumps, Roads Soil Piles	42+19+2+1 = 64 - 2 = 32 acres	0.17	5.5	Hydroseeder Seed	\$95/hr \$166/acre	\$ 523 \$ 5,312	Reseed 50% Perennial Seed Area	
12	Monitoring	All	---	---	---			\$ 3,000		

SUBTOTAL \$869,885  
CONTINGENCY (10%) 86,988  
TOTAL \$782,897

Inflated @ 3.79% for 10 Years  
1985 = 782,897  
1986 = 812,569  
1987 = 843,365  
1988 = 875,329  
1989 = 908,504  
1990 = 942,936  
1991 = 978,673  
1992 = 1,015,764  
1993 = 1,054,262  
1994 = 1,094,219