ACT/047/002



Norman H. Bangerter, Governor Dee C. Hansen, Executive Director Dianne R. Nielson, Ph.D., Division Director

355 W. North Temple • 3 Triad Center • Suite 350 • Salt Lake City, UT 84180-1203 • 801-538-5340

December 8, 1986

Mitchell A. Lekas, President Geokinetics, Inc. 391 Chipeta Way Salt Lake City, Utah 84108

Dear Mr. Lekas:

Re: Reclamation and Revised Bonding (Round 2), Seep Ridge Project, ACT/047/002, Uintah County, Utah

This letter is in response to your letter dated November 10, 1986. Attached is a bond estimate which reflects the changes indicated in your letter.

As we discussed on November 25, 1986, Pam Grubaugh-Littig and I will meet you on site December 10, 1986 at noon, to field check the site status and reclamation completed in order to accommodate a bond reduction for this site. In the event that the weather prohibits our trip, we will re-schedule.

Sincerely,

John J. Whitehead Permit Supervisor/

July h hitcheal

Reclamation Hydrologist

dih

Enclosure(s)

cc: J. Blake, State Lands & Forestry

L. Braxton

P. Grubaugh-Littig

0800R/62

GEOKINETICS REVISED BOND ESTIMATE November 20, 1986

The improvements at the Geokinetics Seep Ridge site that will be retained during the indefinite suspension are:

- 1. Shop building and shop area
- Mobile home park (10 mobile homes)
- 3. Two water wells would be transferred to State Lands
- 4. 20,000 bbl tank battery
- 5. 3,000 bbl tanks (2)
- 6. Evaporation pond #2
- 7. Power house and power house yard
- 8. Afterburner
- 9. Absorber tower
- 10. Modular office building
- 11. Miscellaneous equipment stacked on site
- 12. Road

(It is assumed that previously reclaimed areas will be disked out and seeded during the fall of 1986).

Dismantling and Removal

(Assumption: Haulage of materials will be to Vernal.)

Shop Building

120' x 150' x 18' = 108,000 cf @ \$.17/cf = \$ 18,360

Office Building

 $30' \times 30' \times 15' = 13,500 \text{ cf } @ \$.17/\text{cf} = $2,295$

Page 2 Mr. Mitchell A. Lekas ACT/047/002 December 4, 1986

Power House

 $30' \times 40' \times 20' = 24,000 \text{ cf } @ \$.17/\text{cf} = $4,080$

Tank

20,000 bbl tank battery 112,300 cf

5 days dismantling

truck and trailer and driver = \$ 537.00/day

sheet metal worker = \$ 265.20/day

laborers = \$ 184.40/day (1)

crane = \$ 988.00/day

 $$1,974.60/day \times 5 days = $9,873$

2-3,000 bbl tanks

1.5 days of dismantling

and removal

@ \$1,974.60/day = \$ 2,962

Afterburner

2 days of dismantling and removal @\$1,974.60/day

\$ 3,950

Absorber Tower

2 days of dismantling and removal @ \$1,974.60/day

\$ 3,950

Page 3 Mr. Mitchell A. Lekas ACT/047/002 December 4, 1986

Mobile Homes

Truck and driver to move 10 mobile homes

(Tractor) \$ 225.20/day

(Driver) $\frac{$190.40/\text{day}}{}$ (driver)

 $$415.60 \times 4 \text{ days} = $1,662.40$

Equipment Removal and Site Clean Up

Tractor \$ 363.20 Trailer \$ 100.24

Driver \$ 190.40

\$ 653.84/day

Crane \$ 988/day

Laborers = \$184.40/day x 2 laborers = \$ 368.80

 $1,811/day \times 2 days = 3,622$

Areas to be Regraded, Recontoured and Ripped:

Mobile Home Park

Power House Yard

Tank Battery Area

Shop Area

Roads

1.72 ac.

5.50 ac.

2.00 ac.

1.84 ac.

13.56 ac.

13.56 ac. = 590,674 sf (@ 6") 295,337 cf

10,938 cy

@ \$.84/cy for 10,938 cy Sub Total

Page 4 Mr. Mitchell A. Lekas ACT/047/002 December 4, 1986

Backfilling Evaporation Ponds:

Ponds #2 and #3 -

150' haul common earth, 200 H.P. dozer @ \$94/cy:

 $#2 = 400 \times 400 \times 3$

17,778 cy @ **#.**94/cy \$ 16,711

Sub Total

\$ 16,711

Revegetation of 19.29 ac: -

Harrowed, Fertilized, Drill Seeded:

Harrowed @ \$200/day (including tractor & driver)

Fertilizer (applied) - \$45/ac.

Drill Seeder @ \$200/day (including tractor & driver)

Seed @ \$150/ac.

At the rate of 10 ac/day

Harrowed in 2 days @ \$200/day =	\$ 400
Fertilizer = \$45/ac. x 20 ac. =	900
Drill Seeder for 2 days @ \$200/day =	400
Seed = \$150/ac. x 20 ac. =	 3,000

4,700

20% rate for revegetation $$4,700 \times 1.2 = $5,880$

Page 5 Mr. Mitchell A. Lekas ACT/047/002 December 4, 1986

Dismantling and Building Removal	\$ 50,754
Backfilling Evaporation Ponds	\$ 16,711
Regraded & Recontoured	\$ 9,188
Revegetation	\$ 5,880
Monitoring @ \$500/year	\$ 1,500
Supervise Entire Project = 10 days	
@ \$262.80/day	\$ 2,628
	\$ 86,661
10% contingency	\$ 8,666
	\$ 95,327 (1986 dollars)

Escalate @ 1.62%

1987 - 96,871 1988 - 98,441 1989 - \$100,035

JJW/djh 0800R/63**-**67